

Eden Woodchip Mill Wharf Reconstruction 2016/2017



Eden Wood Chip Mill Wharf

Wharf Reconstruction

The wood chip loading facility sustained major storm damage in July 2016, with over 60% of the Jetty's infrastructure washed away by waves recorded at over 17 m high.

Australasian Marine Associates and its alliance partner, Australasian Marine Construction have extensive history in Twofold Bay, leading the delivery of all the technical pre-works for the proposed cruise ship terminal in Snug Cove.

In August 2016, AMA personnel began the process of rebuilding the wharf and providing the structure for the conveyor belt system. In line with the project timelines, in November 2016 the wharf was operational and exports were able to recommence.

The first shipment was an outstanding milestone and was attributed to strong project management and relentless around the clock work by the AMA team and suppliers.

Australasian Marine Associates successfully designed and built the replacement jetty infrastructure and are pleased to have assisted in making the wharf fully operational.



Scope of the Works:

- Removal of old wharf debris from inside the construction footprint
- Design and construction of the new wharf structure, including installation of 600mm and 900mm diameter piles, headstocks and roadway
- Crane assist for lifting in the new conveyor system

For further information please contact:

Australasian Marine Associates Pty Ltd
3B, 23 Township Drive, Burleigh Heads QLD 4220

Key Personnel Contacts:

Dr Adam Cohen - 0413 033 500 or
Dr Daniel Spooner 0404 834 164