

**Huntington Beach Union High School District**  
**CTE Infrastructure Enhancement Projects: Scope Number Descriptions**

January 16, 2019

**Bid Descriptions**

1. RESERVED
  
2. Huntington Beach High School – Culinary Arts – (Scope 2)  
Scope consists of the removal of existing casework and sinks at the student workstations, partial demolition of interior walls, and floor finishes throughout the approximately 1,208 square foot classroom. Stainless steel shelving and cabinets to be installed on the walls with stainless steel wall protection at the workstations. Floor finish is to be epoxy with rubber base throughout. District to provide equipment for contractor to install which consists of stainless steel tables and oven/ranges.
  
3. Huntington Beach High School – Photo Lab – (Scope 3)  
The scope consists of the removal of casework, floor finishes, lighting, and ACT ceiling for an approximately 1,347 square foot classroom. Provide new lights and polished concrete throughout the classroom. Install a wood display wall feature and provide floor outlets as shown on plans. Contractor to install district provided studio lighting rig.
  
4. RESERVED)
  
5. Ocean View High School – Photo Lab – (Scope 5)  
The scope consists of the removal of floor finishes for an approximately 1,947 square foot classroom. Provide new lights and ventilation in the dark room and polished concrete throughout the classroom.
  
6. Ocean View High School – Culinary Arts – (Scope 6)  
Scope consists of the removal of existing casework and sinks at the student workstations and floor finishes throughout the approximately 1,979 square foot classroom. Stainless steel shelving and cabinets to be installed on the walls with stainless steel wall protection at the workstations. Floor finish is to be epoxy with rubber base throughout. District to provide equipment for contractor to install which consists of stainless steel tables and oven/ranges.
  
7. Westminster View High School – Culinary Arts – (Scope 7)  
Scope consists of the removal of existing casework and sinks at the student workstations and floor finishes throughout the approximately 1,718 square foot classroom. Stainless steel shelving and cabinets to be installed on the walls with stainless steel wall protection at the workstations.

**Huntington Beach Union High School District**  
**CTE Infrastructure Enhancement Projects: Scope Number Descriptions**

Floor finish is to be epoxy with rubber base throughout. District to provide equipment for contractor to install which consists of stainless steel tables and oven/ranges.

8. Marina High School – Culinary Arts – (Scope 8)

Scope consists of the removal of existing casework and sinks at the student workstations and floor finishes throughout the approximately 1,259 square foot classroom. Stainless steel shelving and cabinets to be installed on the walls with stainless steel wall protection at the workstations. Floor finish is to be epoxy with rubber base throughout. District to provide equipment for contractor to install which consists of stainless steel tables and oven/ranges.

9. Fountain Valley High School – Culinary Arts – (Scope 9)

Scope consists of the removal of existing casework and sinks at the student workstations and floor finishes throughout the approximately 1,243 square foot classroom. Stainless steel shelving and cabinets to be installed on the walls with stainless steel wall protection at the workstations. Floor finish is to be epoxy with rubber base throughout. District to provide equipment for contractor to install which consists of stainless steel tables and oven/ranges.

10. Fountain Valley High School – Culinary Arts – (Scope 10)

Scope consists of the removal of existing casework and sinks at the student workstations and floor finishes throughout the approximately 1,020 square foot classroom. Stainless steel shelving and cabinets to be installed on the walls with stainless steel wall protection at the workstations. Floor finish is to be epoxy with rubber base throughout. District to provide equipment for contractor to install which consists of stainless steel tables and oven/ranges.

11. Edison View High School – Culinary Arts – (Scope 11)

Scope consists of the removal of existing casework and sinks at the student workstations and floor finishes throughout the approximately 1,243 square foot classroom. Stainless steel shelving and cabinets to be installed on the walls with stainless steel wall protection at the workstations. Floor finish is to be epoxy with rubber base throughout. District to provide equipment for contractor to install which consists of stainless steel tables and oven/ranges.

12. Edison High School – Photo Lab – (Scope 12)

The scope consists of the removal of approximately 25 feet of nonbearing wall, casework, floor finishes, lighting, and ACT ceiling for an approximately 1,660 square foot classroom. Provide new walls, door, lights, ACT ceiling, and polished concrete in the classroom. Install a district provided studio lighting rig along with sound proofing as required by contract documents.