

Use of Trackless Tack at Bus Garage & Parking Area





Project Title: Owner:

Location: Product Used:

Installed By: Install Date: Contact: Bus Garage & Parking Columbus Regional Airport Authority Stelzer Rd. Columbus, OH Trackless Tack NTSS-1HM Decker Construction May 6, 2009 Jonathan Apple Decker Construction

BACKGROUND

Reason for product use:

High traffic area did not want tack tracked onto Stelzer Rd.. Also looking for better adhesion between asphalt layers.

PRODUCT DETAILS

Туре:	NTSS—1HM
	"Trackless Tack"
Design Type:	Used between base
	course and asphalt
	wearing course.
Existing Product:	Asphalt

INSTALLATION

Weather:

60 degrees/foggy/overcast

Comments:

Installation was completed in less than 45min. The tack was "cured" and dry to the touch in 20 minutes.

RESULTS

No tracking onto Stelzer Rd. The construction was easier and quicker as the parking crew could get on the tack much earlier than normal emulsions. Expect to achieve better adhesion between layers since the trackless tack is actually there during construction.



For Detailed Information & Specifications <u>Contact Tom Letizia</u> Product Manager Meredith Brothers, Inc. 440-668-1772 Mobile 440-543-7973 Cleveland Office/Fax 800-878-4991 Columbus Headquarters <u>tletizia@roadrunner.com</u> <u>www.MeredithBrothersInc.com</u>

Check out video of actual installation: http://www.youtube.com/user/MeredithBrothersInc