





750 Gallon Dual Compartment Septic Tank

Tank: 750 Gallon Dual Compartment Tank
Reinforced with Fiber & #4 Steel 12" O/C Both Ways.
2.5" Walls & 2.5" Bottom. Tank # 16-065-01S-C3

Lid: 4" Lid w/ 2-24" Manhole Covers at each end. Lid
reinforced w/ grade #4 Rebar on 12" centers each way.
Tank & Lid 4000 PSI Concrete at 28 Days.



8300 W. Beaver St.
Jacksonville, FL 32220
PH. 904.781.4818
Fax 904.783.3197