

### Jenkintown-Wyncote Station Improvements

#### **Consultant Team:**

Gannett Fleming, Inc. PB Americas, Inc. Sowinski Sullivan Architects, P.C. Pinto Engineering, Inc. ASC Group, Inc. CHPlanning, Ltd.

April 14, 2009

# **Project Purpose**

## Merging of Two Initiatives

- SEPTA Station Improvements
  - Provide Accessibility
  - State of Good Repair
  - Reduce Dwell Times
- Parking Expansion
  - Glenside at Capacity as Early as 8:10 am
  - Jenkintown at Capacity as Early as 8:15 am



## **Project Purpose**

#### Process to Date

- Parking Demand Study (2000)
- Updated Parking Demand Study (2004)
- Feasibility Studies (2004/2005)
- Current Design for Jenkintown at 15%
- 100% Design by Spring 2010



## **Project Objectives**

- Accessibility (High Level Platforms)
- Reduce Dwell Times (High Level Platforms)
- Parking Expansion
- Customer Convenience
- Address Known Traffic Concerns
- Address Known Flooding Concerns
- Preserve Historic Nature of the Station and Reflect the Character of the Surrounding Communities (Gain Input)
- Utilize Existing Property (Minimize Acquisition)



## **Project Objectives**


The Proposed Station Improvements Meet All of These Objectives and the Parking Garage is the Key Project Element



#### Traffic

#### Project as Proposed Improves Local Traffic Flow at the Intersection of Glenside and Greenwood Avenue





#### Traffic

#### Greenwood/Glenside Intersection Peak Hour Level of Service (LOS)

	Existing		2011		2025	
	A.M.	P.M.	A.M.	P.M.	A.M.	P.M.
Existing Condition	D	Е	D	F	E	F
With 700 Car Garage (Additional 350 cars)	n/a	n/a	В	С	С	С

.

Legend:						
LOS	Average Delay	General Description				
Α	0 - 10 sec./veh.	Under Capacity				
В	10 - 20 sec./veh.	Under Capacity				
С	20 – 35 sec./veh.	Under Capacity				
D	35 – 55 sec./veh.	At Capacity				
E	55 – 80 sec./veh.	At Capacity				
F	> 80 sec./veh.	Over Capacity				




## Flooding

#### Project as Proposed Dramatically Improves Flooding Impacts



#### **Tookany Creek Improvements**



## **Tookany Creek Improvements**



# **Station Building Options**

	Number of Cars in Garage	Total Number of Levels	Recessed Bottom Level	Top Floor Parapet Height Above Grade	Height Above or Below Bridge
Feasibility Study	690	4 Full	Yes	25.5 ft.	-2.0 ft.
Initial Concept	700	4 Full, 1 Partial	No	49.5 ft.	+17.5 ft.
Alternate 1	700	4 Full, 1 Partial	Yes	37.0 ft.	+9.5 ft.
Alternate 2	600	4 Full	Yes	27.0 ft.	-0.5 ft.



# Security

- Passive Safety / Security Measures
  - Increased Floor to Floor Heights
  - Flat Floors (No Sloping Decks)
  - Open Deck (Clear Sight Lines)
- Active Safety / Security Measures
  - CCTV in Stairs / Elevators
  - Emergency Call Boxes
  - Sprinklers Throughout Deck
  - Consistent, Even Lighting
- SEPTA Presence
  - Station Ticket Agent
  - Parking Management Personnel
  - Adjacent to Platforms

Southeastern Pennsylvania Transportation Authority
















nts

ARTIAL NORTH ELEVATION - PROPOSED REDESIGN - OPTION D-1 w/ OVERPASS ts









BUILDING HEIGHT COMPARISON: CONCEPT D-1 & EXISTING STATION BUILDING nts



## **Design Changes to Date**

Recessed First Level (Flood Plain)
Reduced Number of Garage Spaces (Eliminate Upper Level)
Evaluating Pedestrian Underpass Option



## **Other Project Issues**

Eliminate Temporary Parking at Park Adjacent to Post Office
Need to Update Parking Demand Study
No Adjacent Station Closings
Construction Tied with PADOT Bridge Project to Minimize Impacts
Glenside Parking Garage Next
Commitment to Workshops

