



Ft. Jackson Battalion Headquarters

Truss Link partnered with Ryeco Drywall to help Alutiiq develop this fast track project. This +/- 30,000 structure was a panelized load bearing wall system with light gauge steel trusses. The walls and trusses were set and decked/sheathed in approximately 6 weeks in one of the rainiest winters on the books. K&P Engineering produced shop drawings for both Truss Link and Ryeco which allowed for a very efficient framing system and minimal field design errors. Despite the weather, this project came in on schedule at budget.

Location:	Columbia, SC
Contractor:	Alutiiq
Design Partner:	Ryeco Drywall
Contract Amount:	\$293,992
Approx Sqft:	29,296
Delivery Method:	Design/Build
Scope:	Site-fabricated trusses Metal roof deck