

Not to Scale

NOTES:

- 1. Concrete or sand-cement endwalls may be used to shorten the culvert length. All work shall be in accordance with Florida D.O.T. Specifications.
- 2. All disturbed slopes, berms and other areas shall be seeded, fertilized and mulched (or sodded) in accordance with Florida D.O.T. specifications within 14 days of the completed activity.
- 3. Drainage shall not be blocked or impaired at any time.
- 4. The applicant shall notify the St. Johns Improvement District Office (772-562-9176) 24 hours prior to construction of the crossing.

