

Scope of Work

Work to be completed:

The applicant will utilize contract for repairs for the Wayne Johnson Community Center to restore facilities back to pre-disaster design, capacity and function within the existing footprint.

HVAC:

- A. Remove and Replace: 15,000 sf of HVAC system
- B. Clean and sanitize units, registers and ducts

Corridor 111:

- A. Remove and Replace: 780 sf. Of R-13 foil-faced batt ceiling insulation (156 ft. LX 5 ft. W).
- B. Remove and Replace: 780 sf pf 2 ft. x 2 ft. acoustical ceiling tiles (156 ft. L x 5 ft. W).
- C. Replace 2,808 sf of 5/8 in Gypsum wallboard, textured, painted (312 ft. L x 9 ft. H).
- D. Replace: 4 in vinyl cove base (312 ft. Long)

Corridor 142:

- A. Remove and Replace: 270 SF of R-13 foil-faced batt ceiling insulation (54 ft. L x 5 ft. W).
- B. Remove and Replace: 270 sf of 2 ft. x 2 ft. acoustical ceiling tiles (54 ft. L x 5 ft. W).
- D. Replace: 684 sf of 5/8 in gypsum wallboard, textured, painted (76 ft. L x 9 ft. H)
- E. Replace: 4 in vinyl cove base (76 ft. L).

Corridor 143:

- A. Replace: 828 sf of 5/8 in gypsum wallboard, textured, painted (92 ft. L x 9 ft. H).
- B. Replace: 4 in vinyl cove base (92 ft. L).
- C. Remove and Replace: 230 sf of 2 ft. x 2 ft. acoustical ceiling tiles (46 ft. L x 5 ft. W).
- D. Remove and Replace: 230 sf of R-13 foil-faced batt ceiling insulation (46 ft. L x 5 ft. W).

Room 100 (Lobby):

- A. Replace: 477 sf of 5/8 in gypsum wallboard textured, painted (53 ft. L x 9 ft. H).
- B. Replace: 477 sf of R-13 foil-faced batt wall insulation (53 ft. L x 9 ft. H).
- C. Replace: 4 in x 8 in ceramic cove base (53 ft. L).
- D. Remove and Replace: 892 sf of 2 ft. x 2 ft. acoustical ceiling tiles (39 ft. x 20 ft.) + (14 ft. X 8 ft.).
- E. Remove and Replace: 892 sf of R-13 foil-faced batt ceiling insulation (39 ft. x 20 ft.) + (14 ft. x 8 ft.).

Room 104 (Receptionist):

- A. Replace: 447 sf of 5/8 in gypsum wallboard textured, painted (49.67 ft. L x 9 ft. H).
- B. Replace: 158 sf of R-13 foil-faced ball wall insulation (17.5 ft. L x 9 ft. H)
- C. Replace: 4 in x 8 in ceramic cove base (50 ft. L).
- D. Remove and Replace: 354 sf of 2 ft. x 2 ft. acoustical ceiling tiles (17.5 ft. L x 20.2 ft. W).
- E. Remove and Replace: 354 sf of R-13 foil-faced batt ceiling insulation (17.5 ft. L x 20.2 ft. W).

Room 105 (Admin Assistant):

- A. Replace: 432 sf of 5/8 in gypsum wallboard, textured, painted (48 ft. L x 9 ft. H).
- B. Replace: 108 sf of R-13 foil-faced, batt wall insulation (12 ft. L x 9 ft. H).
- C. Replace: 4 in vinyl cove base (48 ft. L).
- D. Remove and Replace: 144 sf of 2 ft. x 2 ft. acoustical ceiling tiles (12 ft. L x 12 ft. W).
- E. Remove and Replace: 144 sf of R-13 foil-faced batt ceiling insulation (12 ft. L x 12 ft. W).
- E. Replace: 144 sf. Of Tandem 2 ft. x 2 ft. x 3/8 in glue down **CARPET** tiles (12 ft. L x 12 ft. W).

Room 106 (Permitting):

- A. Replace: 432 sf of 5/8 in gypsum wallboard, textured, painted (48 ft. L x 9 ft. H).
- B. Replace: 108 sf of R-13 foil-faced batt wall insulation (12 ft. L x 9 ft. H).
- C. Replace: 4 in vinyl cove base, (48 ft. Long)
- D. Remove and Replace: 144 sf of 2 ft. x 2 ft. acoustical ceiling tiles (12 ft. L x 12 ft. W)
- E. Remove and Replace: 144 sf of R-13 foil-faced batt ceiling insulation (12 ft. L x 12 ft. W)
- F. Replace: 144 sf of Tandem 2 ft. x 2 ft. x 3/8 in glue down **CARPET** tiles.

Room 107 (Admin Assistant):

- A. Replace: 432 sf of 5/8 in gypsum wallboard, textured, painted (48 ft. L x 9 ft. H)
- B. Replace: 108 sf of R-13 foil-faced batt wall insulation (12 ft. L x 9 ft. H)
- C. Replace: 4 in vinyl cove base (48 ft. Long)
- D. Remove and Replace: 144 sf of 2 ft. x 2 ft. acoustical ceiling tiles (12 ft. L x 12 ft. W).
- E. Remove and Replace: 144 sf of R-13 foil-faced batt ceiling insulation (12 ft. L x 12 ft. W).
- F. Replace: 144 sf of Tandem 2 ft. x 2 ft. x 3/8 in glue down **CARPET** tiles. (12 ft. L x 12 ft. W)

Room 108 (Admin Assistant):

- A. Replace: 432 sf of 5/8 in gypsum wallboard, textured, painted (48 ft. L x 9 ft. H).
- B. Replace: 108 sf. of R-13 foil-faced batt wall insulation (12 ft. L x 9 ft. H).
- C. Replace: 4 in vinyl cove base (48 ft. Long)
- D. Remove and Replace: 144 sf. of 2 ft. x 2 ft. acoustical ceiling tiles (12 ft. L x 12 ft. W).
- E. Remove and Replace: 144 sf of R-13 foil-faced batt ceiling insulation (12 ft. L x 12 ft. W).
- F. Replace: 144 sf. of Tandem 2 ft. x 2 ft. x 3/8 in glue down **CARPET** tiles. (12 ft. L x 12 ft. W)

Room 109 (Director):

- A. Replace: 549 sf. of 5/8 in gypsum wallboard, textured, painted (61 ft. L x 9 ft. H).
- B. Replace: 275 sf. of R-13 foil-faced batt wall insulation (30.5 ft. L x 9 ft. H).
- C. Replace: 4 in vinyl cove base (61 ft. Long)
- D. Remove and Replace: 222 sf of 2 ft. x 2 ft. acoustical ceiling tiles (18.5 ft. L x 12 ft. W).
- E. Remove and Replace: 222 sf of R-13 foil-faced batt ceiling insulation (18.5 ft. L x 12 ft. W).
- F. Replace: 222 sf of Tandem 2 ft. x 2 ft. x 3/8 in glue down **CARPET** tiles (18.5 ft. L x 12 ft. W).

Room 110 (Storage):

- A. Replace: 396 sf of 5/8 in gypsum wallboard, textured, painted. (44 ft. L x 9 ft. H).
- B. Replace: 77 sf. of R-13 foil-faced batt wall insulation (8.5 ft. L x 9 ft. H).
- C. Replace: 4 in vinyl cove base (44 ft. Long).
- D. Remove and Replace: 115 sf of 2 ft. x 2 ft. acoustical ceiling tiles ((13.5 ft. L x 8.5 ft. W).
- E. Remove and Replace: 115 sf of R-13 foil-faced batt ceiling insulation (13.5 ft. L x 8.5 ft. W)
- F. Replace: 115 sf of 12 in x 12 in x 1/8 in **CARPET** (13.5 ft. L x 8.5 ft. W).

Room 112 (Asst. Director – Planning):

- A. Replace: 504 sf of 5/8 in gypsum wallboard, textured, painted (56 ft. L x 9 ft. H).
- B. Replace: 131 sf of R-13 foil-faced batt wall insulation (14.5 ft. L x 9 ft. H)
- C. Replace: 4 in vinyl cove base (56 ft. Long).
- D. Remove and Replace: 196 sf of 2 ft. x 2 ft. acoustical ceiling tiles (14.5 ft. L x 13.5 ft. W).
- F. Remove and Replace: 115 sf of R-13 foil-faced batt ceiling insulation (14.5 ft. L x 13.5 ft. W)
- G. Replace: 196 sf of Tandem 2 ft. x 2 ft. x 3/8 glue down **CARPET** tiles. (14.5 ft. L x 13.5 ft. W).

Room 113 (Asst. Director- Admin):

- A. Replace: 459 sf of 5/8 in gypsum wallboard, textured, painted (51 ft. L x 9 ft. H).
- B. Replace: 108 sf. of R-13 foil faced wall insulation. (12 ft. L x 9 ft. H).
- C. Replace: 4 in vinyl cove base. (51 ft. Long).
- D. Remove and Replace: 162 sf of 2 ft. X 2 ft. acoustical ceiling tiles. (13.5 ft. L x 12 ft. W).
- E. Remove and Replace: 162 sf of R-13 foil faced batt ceiling insulation (13.5 ft. L x 12 ft. W).
- F. Replace: 162 sf of Tandem 2 ft. x 2 ft. x 3/8 in glue down **CARPET** tiles (13.5 ft. L x 12 ft. W).

Room 114 (Asst. Director – Operations):

- A. Replace: 537 sf of 5/8 in gypsum wallboard, textured, painted. (59.8 ft. L x 9 ft. H).
- B. Replace: 96 sf of R-13 foil faced batt wall insulation. (10.6 ft. L x 9 ft. H).
- C. Replace: 4 in x 8 in ceramic cove base, (60 ft. Long)
- D. Remove and Replace: 204 sf of 2 ft. x 2 ft. acoustical ceiling tiles (10.6 ft. L x 19.2 ft. W).
- E. Remove and Replace: 204 sf of R-13 foil faced batt ceiling insulation. (10.6 ft. L x 19.2 ft. W).
- F. Replace: 201 sf of Tandem 2 ft. x 2 ft. x 3/8 glue down **CARPET** tiles. (10.6 ft. L x 19.2 ft. W)

Room 116 (Park Security):

- A. Replace: 435 sf of 5/8 in gypsum wallboard, textured, painted. (48.33 ft. L x 9 ft. H).
- B. Replace: 82 sf of R-13 foil faced batt wall insulation. (9.16 ft. L x 9 ft. H).
- C. Replace: 4 in vinyl cove base (48 ft. Long)
- D. Remove and Replace: 137 sf of 2 ft. x 2 ft. acoustical ceiling tiles 9.16 ft. L x 15 ft. W).
- E. Remove and Replace: 137 sf of R-13 foil faced batt ceiling insulation. (9.16 ft. L x 15 ft. W).
- F. Replace: 137 sf of tandem 2 ft. x 2 ft. x 3/8 in glue down **CARPET** tiles. (9.16 ft. L x 15 ft. W).

Room 118 (Men's Restroom):

- A. Remove and Replace: 92 sf of 2 ft. x 2 ft. acoustical ceiling tiles. (11.5 ft. L x 8 ft. W)
- B. Remove and Replace: 92 sf of R-13 foil faced batt ceiling insulation. (11.5 ft. L x 8 ft. W).
- C. Replace: 351 sf of 5/8 gypsum wallboard, textured, painted. (39 ft. L x 9 ft. H).
- D. Replace: 351 sf of R-13 foil-faced batt wall insulation (39 ft. L x 9 ft. H) – FEMA will not cover

Room 119 (Women's Restroom):

- A. Remove and Replace: 104 sf of 2 ft. x 2 ft. acoustical ceiling tiles (11.5 ft. L x 9 ft. W).
- B. Remove and Replace: 104 sf of R-13 foil faced batt ceiling insulation. (11.5 ft. L x 9 ft. W).
- C. Replace: 369 sf of 5/8 in gypsum wallboard, textured, painted. (41 ft. L x 9 ft. H).
- D. Replace: 369 sf of R-13 foil-faced batt wall insulation (41 ft. L x 9 ft. H) – FEMA will not cover

Room 120 (Break Room):

- A. Replace: 432 sf -5/8 gypsum wallboard with vinyl wallpaper-textured, painted (48 ft. L x 9 ft. H).
- B. Replace: 117 sf of R-13 foil faced batt wall insulation. (13 ft. L x 9 ft. H).
- C. Replace: 4 in vinyl cove base. (48 ft. Long)
- D. Remove and Replace: 143 sf of 2 ft. x 2 ft. acoustical ceiling tiles. (13ft. L x 11 ft. W).
- E. Remove and Replace: 143 sf of R-13 foil faced batt ceiling insulation (13 ft. L x 11 ft. W).
- F. Remove and Replace: 143 sf of 12 in x 12 in x 1/8 in **VINYL COMPOSITION TILE FLOORING** (13 ft. L x 11 ft. W).
- G. Replace: **BASE CABINETS**: (12 ft. x 3 ft. x 2 ft.)
- H. Replace: **OVERHEAD CABINETS**: (12 ft. x 3 ft. x 1 ft.)

Room 121 (Storage):

- A. Remove and Replace: 112 sf. of 2 ft. x 2 ft. acoustical ceiling tiles (14 ft. L x 8 ft. W).
- B. Remove and Replace: 112 sf of R-13 foil faced batt ceiling insulation. (14 ft. L x 8 ft. W).
- C. Replace: 396 sf of 5/8 in gypsum wallboard, textured, painted. (44 ft. L x 9 ft. H)
- D. Replace: 396 sf of R-13 foil faced batt wall insulation. (44 ft. L x 9 ft. H).
- E. Replace: 4 in vinyl cove base – (44 ft. Long)

Room 122 (Print Room):

- A. Remove and Replace: 70 sf of 2 ft. x 2 ft. acoustical ceiling tiles. (10 ft. L x 7 ft. W).
- B. Remove and Replace: 70 sf of R-13 foil faced batt ceiling insulation. (10 ft. L x 7 ft. W).
- C. Replace: 306 sf of 5/8 in gypsum wallboard, textured, painted. (34 ft. L x 9 ft. H).
- D. Replace: 4 in vinyl cove base – (34 ft. Long)

Room 123 (Copy Room):

- A. Remove and Replace: 155 sf of 2 ft. x 2 ft. acoustical ceiling tiles. (15.5 ft. L x 10 ft. W).
- B. Remove and Replace: 155 sf of R-13 foil faced batt ceiling insulation. (15.5 ft. L x 10 ft. W).
- C. Replace: 459 sf of 5/8 in gypsum wallboard, textured, painted. (51 ft. L x 9 ft. H).
- D. Replace: 4 in vinyl cove base – (51 ft. Long)
- E. Replace: 155 sf of Tandem 2 ft. x 2 ft. x 3/8 in glue down **CARPET** tiles. (15.5 ft. L x 10 ft. W)
- F. Remove for reuse and Replace: **SHELVING UNIT**. (10.5 ft. W x 8 ft. H x 1 ft. D) 6 sections – 20 in W ea.
- G. Remove for reuse and Replace: **BASE CABINET WORK SURFACE**. (9 ft. W x 3 ft. H x 2 ft. D)
- H. Remove for reuse and Replace: **OVERHEAD CABINETS** (9 ft. L x 3 ft. H x 2 ft. D)

Room 124 (Planning Room):

- A. Remove and Replace: 322 sf of 2 ft. x 2 ft. acoustical ceiling tiles (23 ft. L x 14 ft. W).
- B. Remove and Replace: 322 sf of R-13 foil faced batt ceiling insulation. (23 ft. L x 23 ft. W).

Room 125 (conference Room):

- A. Remove and Replace: 296 sf of 2 ft. x 2 ft. acoustical ceiling tiles (18.5 ft. L x 16 ft. W).
- B. Remove and Replace: 296 sf of R-13 foil faced batt ceiling insulation (18.5 ft. L x 16 ft. W).
- C. Replace: 296 sf of Tandem 2 ft. x 2 ft. x 3/8 in glue down **CARPET** tiles. (18.5 ft. L x 16 ft. W).
- D. Replace: 4 in vinyl cove base – (69 ft. Long)

Room 126 (IT Room):

- A. Remove and Replace: 36 sf of 2 ft. x 2 ft. acoustical ceiling tiles. (8 ft. L x 4.5 ft. W).
- B. Remove and Replace: 36 sf of R-13 foil faced batt ceiling insulation (8 ft. L x 4.5 ft. H).

Room 127 (Seating Area):

- A. Replace: 684 sf -5/8 gypsum wallboard with vinyl wallpaper textured, painted (76 ft. L x 9 ft. H).
- B. Replace: 253 sf of R-13 foil faced batt wall insulation. (28 ft. L x 9 ft. H).
- C. Replace: 4 in vinyl cove base – (76 ft. Long)
- D. Remove and Replace: 280 sf of 2 ft. x 2 ft. acoustical ceiling tiles. (28 ft. L x 10 ft. W).
- E. Remove and Replace: 280 sf of R-13 foil faced batt ceiling insulation. (28 ft. L x 10 ft. W).
- F. Replace: 280 sf of Tandem 2 ft. x 2 ft. x 3/8 in glue down **CARPET** tiles. (28 ft. L x 10 ft. W).

Room 128 (Center Manager):

- A. Replace: 558 sf of 5/8 in gypsum wallboard, textured, painted. (62 ft. L x 9 ft. H).
- B. Replace: 279 sf of R-13 foil faced batt wall insulation (31 ft. L x 9 ft. H).
- C. Replace: 4 in vinyl cove base – (62 ft. Long)
- D. Remove and Replace: 220 sf of 2 ft. x 2 ft. acoustical ceiling tiles (20 ft. L x 11 ft. W).
- E. Remove and Replace: 220 sf of R-13 foil faced batt ceiling insulation. (20 ft. L x 11 ft. W).
- F. Replace: 220 sf of Tandem 2 ft. x 2 ft. x 3/8 in glue down **CARPET** tiles. (20 ft. L x 11 ft. W).

Room 129 (Meeting Room):

- A. Replace: 540 sf of 5/8 in gypsum wallboard, textured, painted. (60 ft. L x 9 ft. H).
- B. Replace: 99 sf of R-13 foil faced batt wall insulation (11 ft. L x 9 ft. H).
- C. Replace: 4 in vinyl cove base – (60 ft. Long)
- D. Remove and Replace: 209 sf of 2 ft. x 2 ft. acoustical ceiling tiles (19 ft. L x 11 ft. W).
- E. Remove and Replace: 209 sf of R-13 foil faced batt ceiling insulation. (19 ft. L x 11 ft. W).
- F. Replace: 209 sf of Tandem 2 ft. x 2 ft. x 3/8 in glue down **CARPET** tiles (19 ft. L x 11 ft. W).

Room 130 (Arts & Crafts):

- A. Replace: 612 sf -5/8 gypsum wallboard with vinyl wallpaper textured, painted (68 ft. L x 9 ft. H).
- B. Replace: 135 sf of R-13 foil faced batt insulation. (15 ft. L x 9 ft. H).
- C. Replace: 4 in vinyl cove base – (68 ft. Long)
- D. Remove and Replace: 285 sf of 2 ft. x 2 ft. acoustical ceiling tiles. (19 ft. L x 15 ft. W).
- E. Remove and Replace: 285 sf. of R-13 foil faced batt ceiling insulation. (19 ft. L x 15 ft. W).
- F. Remove and Replace: 285 sf of 12 in x 12 in x 1/8 in **VINYL COMPOSITION TILE FLOORING** (15 ft. L x 19 ft. W)
- G. Replace: **SHELVING UNIT** – 13.25 ft. W x 8 ft. H x 1 ft. D. (8 sections) (18 in Sections)
- H. Remove for reuse and Replace: **BASE CABINETS work surface** (12 ft. W x 3 ft. H x 2 ft. D) – 4 sections.
- I. Remove for reuse and Replace: **OVERHEAD CABINETS** – (12 ft. W x 3 ft. H x 1 ft. D) - 4 sections.

Room 131 (Pottery):

- A. Replace: 527 sf -5/8 in gypsum wallboard with vinyl wallpaper textured, painted (58.6 ft. L x 9 ft. H).
- B. Replace: 93 sf of R-13 foil faced batt wall insulation. (10.3 ft. L x 9 ft. H).
- C. Replace: 4 in x 8 in ceramic cove base – (59 ft. Long)
- D. Remove and Replace: 196 sf of 2 ft. x 2 ft. acoustical ceiling tiles. (19 ft. L x 10.3 ft. W).
- E. Remove and Replace: 196 sf. of R-13 foil faced batt ceiling insulation. (19 ft. L x 10.3 ft. W).
- F. Remove for reuse and Replace: **BASE CABINET AND WORK SURFACE** (19ft. W x 3ft. H x 2ft. D) – 5 sections.
- G. Remove for reuse and Replace: **SHELVING UNIT**. (9.5 ft. W x 8 ft. H x 1 ft. D) – 6 sections – 18 in W.

Room 131 A (Pottery Storage):

- A. Replace: 297 sf of 5/8 in gypsum wallboard, textured, painted. (33 ft. L x 9 ft. H).
- B. Replace: 149 sf of R-13 foil faced batt wall insulation. (16.5 ft. L x 9 ft. H).
- C. Replace: 4 in vinyl cove base – (33 ft. Long)
- D. Remove and Replace: 65 sf of 2 ft. x 2 ft. acoustical ceiling tiles. (10 ft. L x 6.5 ft. W).
- E. Remove and Replace: 65 ft. of R-13 foil faced batt ceiling insulation. (10 ft. L x 6.5 ft. W).
- F. Remove for reuse and Replace: **SHELVING UNIT** – 10 ft. W x 8 ft. H x 1.5 ft. D. 3 sections – 3.25 ft. W.

Room 132 (Library):

- A. Replace: 617sf -5/8 gypsum wallboard ~~with vinyl wallpaper~~ textured, painted (68.67 ft. L x 9 ft. H)
- B. Replace: 138 sf of R-13 foil faced batt wall insulation. (15.3 ft. L x 9 ft. H).
- C. Replace: 4 in vinyl cove base – (69 ft. Long)
- D. Remove and Replace: 291 sf of 2 ft. x 2 ft. acoustical ceiling tiles. (15.3 ft. x 19 ft. W).
- E. Remove and Replace: 291 sf of R-13 foil faced batt ceiling insulation. (15.3 ft. L x 19 ft. W).
- F. Replace: 291 sf of Tandem 2 ft. x 2 ft. x 3/8 glue down **CARPET** tiles. (15.3 ft. L x 19 ft. W)
- G. Replace: **SHELVING UNIT** – 36 ft. W x 8 ft. H x 1 ft. D - 24 sections – 18 in W.

Room 133 (Chase / Utility Room):

- A. Replace: 594 sf of 5/8 in gypsum wallboard, textured, painted. (66 ft. L x 9 ft. H).
- B. Replace: 297 sf of R-13 foil faced batt wall insulation. (33 ft. L x 9 ft. H).
- C. Replace: 4 in vinyl cove base – (66 ft. Long)
- D. Remove and Replace: 200 sf of 2 ft. x 2 ft. acoustical ceiling tiles (25 ft. L x 8 ft. W).
- E. Remove and Replace: 200 sf of R-13 foil faced batt ceiling insulation. (25 ft. L x 8 ft. W).

Room 134 (Kitchen):

- A. Replace: 630 sf of 5/8 gypsum wallboard, textured, painted. (70 ft. L x 9 ft. H).
- B. Replace: 180 sf of R-13 foil faced batt wall insulation. (20 ft. L x 9 ft. H).
- C. Replace: 4 in vinyl cove base – (70 ft. Long)
- D. Remove and Replace: 300 sf of 2 ft. x 2 ft. acoustical ceiling tiles. (20 ft. L x 15 ft. W).
- E. Remove and Replace: 300 sf of R-13 foil faced batt ceiling insulation. (20 ft. L x 15 ft. W).
- F. Remove and Replace: 300 sf of 12 in x 12 in x 1/8 in. **CERAMIC TILE** (20 ft. L x 15 ft. W).
- G. Replace: **BASE CABINETS** – 15 ft. W x 3 ft. H x 2 ft. D (5 sections).
- H. Replace: **OVERHEAD CABINETS** – 15 ft. W x 3 ft. H x 1 ft. D. (5 sections).
- I. Replace: **INDUSTRIAL TYPE STAINLESS STEEL SINKS**– 3ea. & frame. (4 ft. W x 3 ft. H x 2 ft. D).

Room 135 (Storage):

- A. Remove and Replace: 441 sf of 2 ft. x 2 ft. acoustical ceiling tiles. (21 ft. L x 21 ft. W).
- B. Remove and Replace: 441 sf of R-13 foil faced batt ceiling insulation. (21 ft. L x 21 ft. W).
- C. Replace: 756 ft. of 5/8 of gypsum wallboard, textured, painted. (84 ft. L x 9 ft. H).
- D. Replace: 4 in vinyl cove base – (84 ft. Long)

Room 136 (Women's Restroom):

- A. Remove and Replace: 250 sf of 2 ft. x 2 ft. acoustical ceiling tiles (21 ft. L x 21 ft. W).
- B. Remove and Replace: 250 sf of R-13 foil faced batt ceiling insulation. (25 ft. L x 10 ft. W).
- C. Replace: 630 5/8 of gypsum wallboard ~~of vinyl wallpaper~~ textured, painted– (70 ft. L x 9 ft. H).
- D. Replace: 630 sf of R-13 foil faced batt wall insulation. (70 ft. L x 9 ft. H).

Room 137 (Men's Restroom):

- A. Remove and Replace: 250 sf of 2 ft. x 2 ft. acoustical ceiling tiles (25 ft. L x 10 ft. W).
- B. Remove and Replace: 250 sf of R-13 foil faced batt ceiling insulation (25 ft. L x 10 ft. W).
- C. Replace: 630 sf 5/8 of gypsum wallboard, textured, painted – (70 ft. L x 9 ft. H).
- D. Replace: 630 sf of R-13 foil faced batt wall insulation. (70 ft. L x 9 ft. H).

Room 138 (Janitor Closet):

- A. Remove and Replace: 50 sf of 2 ft. x 2 ft. acoustical ceiling tiles – (10 ft. L x 5 ft. W)
- B. Remove and Replace: 50 sf of R-13 foil faced batt ceiling insulation (10 ft. L x 5 ft. W)
- C. Replace: 630 5/8 of gypsum wallboard textured, painted– (10 ft. L x 9 ft. H).
- D.-Replace: 630 sf of R-13 foil faced batt wall insulation. (10 ft. L x 9 ft. H).

Room 139 (Storage):

- A. Remove and Replace: 75 sf of 2 ft. x 2 ft. acoustical ceiling tiles. (15 ft. L x 5 ft. W).
- B. Remove and Replace: 75 sf of R-13 foil faced batt ceiling insulation. (15 ft. L x 5 ft. W).
- C. Replace: 630 5/8 of gypsum wallboard of vinyl wallpaper textured, painted– (15 ft. L x 9 ft. H).
- D.-Replace: 630 sf of R-13 foil faced batt wall insulation. (15 ft. L x 9 ft. H).

Room 140 (Storage):

- A. Remove and Replace: 115 sf of 2 ft. x 2 ft. acoustical ceiling tiles (23 ft. L x 5 ft. W).
- B. Remove and Replace: 115 sf of R-13 foil faced batt ceiling insulation. (23 ft. L x 5 ft. W).

Room 141 (Chase / Utility Room):

- A. Replace: 450 sf of 5/8 in gypsum wallboard, textured, painted. (50 ft. L x 9 ft. H).
- B. Replace: 153 sf of R-13 foil faced batt wall insulation. (17 ft. L x 9 ft. H).
- C. Replace: 4 in vinyl cove base – (50 ft. Long)
- D. Remove and Replace: 136 sf of 2 ft. x 2 ft. acoustical ceiling tiles (17 ft. K x 8 ft. W).
- E. Remove and Replace: 136 sf of R-13 foil faced batt ceiling insulation. (17 ft. L x 8 ft. W).

Room 144 (Kiln):

- A. Replace: 234 sf pf 5/8 in gypsum wallboard, textured, painted. (26 ft. L x 9 ft. H).
- B. Replace: 117 sf of R-13 foil faced batt wall insulation (13 ft. L x 9 ft. H).
- C. Replace: 4 in vinyl cove base – (26 ft. Long)
- D. Remove and Replace: 42 sf of 2 ft. x 2 ft. acoustical ceiling tiles. (7 ft. L x 6 ft. W).
- E. Remove and Replace: 42 sf of R-13 foil faced batt ceiling insulation (7 ft. L x 6 ft. W)..

Rooms 101 – 103 (Multi-Purpose):

- A. Remove and Replace: 4,946 sf of 2 ft. x 2 ft. acoustical ceiling tiles. (67.75 ft. L x 73 ft. W).
- B. Remove and Replace: 4,946 sf of R-13 foil faced batt ceiling insulation. (6.75 ft. L x 73 ft. W).
- C. Replace: 813 sf of 5/8 in gypsum wallboard with vinyl wallpaper. (67.75 ft. L x 12 ft. H).
- D. Replace: 204 sf of R-13 foil faced batt wall insulation. (17 ft. L x 12 ft. H).
- E. Replace: 4 in x 8 in ceramic cove base – (68 ft. Long)
- F. **SPECIAL NOTED ITEM: Remove and Replace: 26 ea. ROOM DIVIDERS (4 ft. W x 12 ft. H) - 104 LF**

**406 HMP (Hazard Mitigation Project) Scope of Work****1. Vents:**

Replace with water-resistant vents.

2. Weather Stripping:

Upgrade the weather stripping around doors and windows to prevent water infiltration.

3. Windows and Doors:

Replace all windows and doors, door frames, hinges, and hardware with wind-resistant units, as indicated on the drawings.

4. French Drain:

Improve drainage around the perimeter of the building to reduce the risk of water infiltration through doors and weep holes.

County to Pay for these items – They should be bid and invoiced separately

Room 124 (Planning Room):

Replace: 322 sf of 2 ft. x 2 ft. CARPET (23 ft. L x 14 ft. W).

Room 126 (IT Room):

Replace: 36 sf of 2 ft. x 2 ft. **CARPET** (8 ft. L x 4.5 ft. W).

Replacement of 24 Windows throughout building.