

March 13, 2020

ADDENDUM NO. 2

Eden Isle Corporation

WASTEWATER PUMP STATION & FORCE MAIN

CWB Project No. 17-075

This addendum shall be considered part of the Plans, Specifications, and Contract Documents and is issued to change, amplify, delete from, or otherwise explain these documents where provisions of this addendum differ from those of the original documents. This addendum shall have precedence over the original documents and shall govern.

Force Main Project Technical Specifications

PVC Pipe Restraint within encasement was not specified. Please see below. This applies to the encasement at the HWY 107 crossing.

1. Section 333400 – PVC PRESSURE PIPE

ADD Paragraph 6 to Part 2.02, D. of Specification Section 333400, Page 3 to read as follows:

- 6. *PVC Joint Restraint Within Encasement Pipe:***
PVC pipe within encasement shall be restrained by the use of split bell restraint harnesses at each joint, or by the installation of integral bell restrained joint pipe such as Certa-Lok PVC, or equal. Harnesses shall be Series 6500 as manufactured by EBAA Iron, Inc., or equal.