

eBid eXchange Export							
Solicitation: Borough of Fleetwood - Berks County Concession Stand Modifications and New Toilet Room Bldg							
Generated 11/21/2018 11:48:24 AM Eastern							
Line Item	User Field	Description	Type	Unit of Me	Quantity	Unit P	Comment
1		The construction of a new concrete masonry toilet room building, replacement of the existing concession stand drinking fountains, the associated site improvements and utility work and all other work indicated in the contract documents.	BASE	LS	1		
2	Allowance	1,100 square feet of plywood deck replacement as specified in Division 01 Section "Unit Prices" per Unit Cost #1.	BASE	SF	1100		
3		1,000 square yards of geotextile separation fabric as specified in Division 01 Section "Unit Prices" per Unit Cost #2.	BASE	SY	1000		
4		20 cubic yards of rock removal in utility trenches as specified in Division 01 Section "Unit Prices" per Unit Cost #3.	BASE	CY	20		
5		10 cubic yards of unsatisfactory soil removal as specified in Division 01 Section "Unit Prices" per Unit Cost #4.	BASE	CY	10		
6	Unit Prices	Removal of any damaged wood decking and furnish and install 5/8" plywood decking to match the existing roof construction.	ADD	SF	1		
7		Furnish and install class 3 geotextile separation fabric.	ADD	SY	1		
8		Include excavation and legal disposal of rock for utility trenches in accordance with Division 01 Section "Earth Moving".	ADD	CY	1		
9		Include excavation, legal disposal of soils and backfill to grades indicated with PennDOT 2A stone in accordance with Division 01 Section "Earth Moving".	ADD	CY	1		

10	Alternates	Provide all labor and material necessary to furnish and install the fixtures indicated on Drawing P3.0, "Alternate Plumbing Equipment Schedule," in lieu of the "Base Bid Plumbing Equipment Schedule".	ADD	EACH	1		
11		Provide all labor and material necessary to excavate, backfill, furnish, and install the entrance CMU screen walls and associated foundations in accordance with the contract drawings and specifications, including Drawing T-S1.0.	ADD	EACH	1		
12		Provide all labor and material necessary to furnish and install electrical panel 'B', including all associated feeders from electrical panel 'A', in accordance with the contract drawings and specifications.	ADD	EACH	1		
13		Provide all labor and material necessary to furnish and install the electric ceiling heaters, electric unit heaters, disconnects, breaks and the associated wiring, boxes and conduit for the new toilet room building in accordance with the contract drawings and specifications.	ADD	EACH	1		
14		Provide all labor and material necessary to furnish and install the concession stand modification in accordance with the contract drawings and specifications. (Base Bid includes replacement of the exterior drinking fountains)	ADD	EACH	1		
15		Provide all labor and material necessary to furnish, install Masonry Wall type MW8-S (standard 8-inch CMU), including Foundation Wall type MFW8, complete with paint PT-5 on each side, all in lieu of the Echelon Insultech block for the construction of the exterior walls.	ADD	EACH	1		