

NRCS LITTLE RIVER WATERSHED DAM NO. 25

# Watershed Dam Rehabilitation Stakeholder Engagement Meeting December 15, 2016

Gregg W. Hudock, P.E. ghudock@golder.com





#### INTRODUCTIONS









- Golder Associates Inc.
- USDA Natural Resources Conservation Service
- Georgia Soil & Water Conservation Commission
- Fulton County Soil & Water Conservation District
- Georgia State Financing and Investment Commission
- City of Milton, Georgia











#### **AGENDA**









- Overview of NRCS Watershed Program and State of Georgia Rules for Dam Safety
- Little River Dam No. 25 background information
- Little River Dam No. 25 present studies
- Rehabilitation Alternatives to be studied
- Future activities
- Questions











# NRCS WATERSHED PROGRAM BACKGROUND

- Soil Erosion Service (1933), then Soil Conservation Service (1935), then NRCS (1994)
- NRCS Watershed Protection and Flood Prevention Conservation Program constructed more than <u>11,000</u> flood control dams in 47 states since 1948.
- Watershed Program (PL-534 Flood Control Act of 1944 and PL-566 Watershed Protection and Flood Prevention Act); Pilot Watershed Program (1952-1954); and Resource Conservation and Development Program
- Benefits include: flood control, erosion control, sediment control, recreation, fish and wildlife habitat, watershed protection, water quality, groundwater recharge, water supply














#### **NRCS Watershed Dams**

# Cross Section of a Watershed Dam



http://www.watershedcoalition.org












#### **NRCS Watershed Dams**

# Flood Storage



http://www.watershedcoalition.org












## **NRCS Watershed Dams - NWC Video**














# STATE OF GEORGIA WATERSHED DAM REHABILITATION PROGRAM

- State of Georgia has 357 NRCS watershed dams constructed in the last half century.
- Exempt from GA Rules for Dam Safety until November 1, 2000.
- 189 dams are classified as high hazard.
- Pilot Rehabilitation Program in 1999
- Planning Studies in 2004 to 2006
- Gwinnett County CIP Program 2001 to 2011 – 9 dams rehabilitated
- GA SWCC Rehabilitation Program
  - 2009 2011: 5 dams rehabilitated
  - 2011 2015: 2 dam rehabilitated
  - 2013 Present: 3 dams underconstruction
  - 2014 & 2016 2 dams under design













#### LITTLE RIVER DAM NO. 25 INFORMATION









- LR-25 was designed and constructed in 1960.
- One of 17 watershed dams in the Little River
   Watershed. 10 structures in Fulton County and 7 structures in Cherokee County.
- LR-27 structure is upstream of LR-25
- The LR-25 reservoir receives runoff from a 9.74 square mile (mi²) watershed.
- Dam Height = ~35 ft.
- Spillways = 30 diameter concrete pipe with a single stage riser & 2 earthen vegetated spillways on the left and right abutments. Left = 200 ft.; Right = 100 ft.
- Storage = ~52.8 million gallons at normal pool & ~578 million gallons at the dam crest.
- Dam classified as a high hazard dam (no permit).













## LR-25 Dam






## **LR-25 Watershed**





# **LR-25 Dam Breach Inundation Map**





#### LITTLE RIVER DAM 25 PRESENT STUDIES









- Existing Dam is SAFE and operating as designed
- Dam Assessments completed in 2007 confirmed High Hazard Classification with 8 structures in the breach inundation zone
- Minor repairs are needed to the embankment and principal spillway
- Supplemental Watershed Plan will determine compliance with GA SDP and NRCS Design criteria and recommend alternatives
- Typical to find a lack of spillway capacity for design storms and erosion of earthen spillway











#### REHABILITATION ALTERNATIVES









- Alternatives to be studied:
  - Do nothing
  - Breach the dam
  - Non structural
  - Structural







































































#### **NEXT STEPS**









- Site work:
  - Geotechnical Investigation
  - Cultural Resources Evaluation
  - Natural Resources Evaluation
- Alternatives Analyses/Costs
- Public Meeting(s)
- NRCS Watershed Plan Update
- Design
- Permitting
- Construction
- Schedule: typically 2 to 3 years start to finish (depends on funding)











# **QUESTIONS?**

Gregg W. Hudock, P.E. ghudock@golder.com

