


Corbelstone, Inc.

5831 Hilltop Drive
Flowery Branch, Ga. 30542
Office: 770-967-0076
www.corbelstone.com



04 72 00

Cast Stone Masonry

1. PART 1 - GENERAL

1.1. SECTION INCLUDES - Architectural Cast Stone.

A. Scope - All labor, materials and equipment to provide the Cast Stone shown on architectural drawings and as described in this specification.

1. Manufacturer shall furnish Cast Stone covered by this specification.

2. Installing contractor shall unload, store, furnish all anchors, set, patch, clean and seal (optional) the Cast Stone as required.

1.2. RELATED SECTIONS

A. Section - 04065 - Mortar and Grout.

B. Section - 04810 - Unit Masonry Assemblies.

C. Section - 04820 - Reinforcing Unit Masonry Assemblies.

D. Section - 07900 - Joint Sealers.

1.3. REFERENCES

A. ACI 318 - Building Code Requirements for Reinforced Concrete.

C. ASTM A 615/A 615M - Standard Specification for Deformed and Plain Billet-Steel Bars for Reinforced Concrete.

D. ASTM C 33 - Standard Specification for Concrete Aggregates.

E. ASTM C 150 - Standard Specification for Portland Cement.

F. ASTM C 270 - Standard Specification for Mortar for Unit Masonry.

G. ASTM C 494 - Standard Specification for Chemical Admixtures for Concrete.

H. ASTM C 642 - Standard Test Method for Specific Gravity, Absorption, and Voids in Hardened Concrete.

I. ASTM C 666 - Standard Test Method for Resistance of Concrete to Rapid Freezing and Thawing.

J. ASTM C 979 - Standard Specification for Coloring Pigments for Integrally Pigmented Concrete.

K. ASTM C 1194 - Standard Test Method for Compressive Strength of Architectural Cast Stone.

L. ASTM C 1195 - Standard Test Method for Absorption of Architectural Cast Stone.

M. ASTM C 1364 - Standard Specification for Architectural Cast Stone.

N. ASTM D 2244 - Standard Test Method for Calculation of Color Differences from Instrumentally Measured Color Coordinates.

1.4. DEFINITIONS

A. Cast Stone - an architectural pre-cast concrete building unit intended to simulate natural cut stone.

1. Vibrant Dry Tamp (VDT) casting method: Vibratory ramming of earth moist, zero-slump concrete against a rigid mold until it is densely compacted.

1.5. SUBMITTALS

A. Comply with Section 01 33 00 - Submittal Procedures.


B. Samples: Submit pieces of the Cast Stone that are representative of the general range of finish and color proposed to be furnished for the project.

C. Test results: Submit manufacturers test results of Cast Stone previously made by the manufacturer.

D. Shop Drawings: Submit manufacturers shop drawings including profiles, cross-sections, reinforcement, exposed faces, arrangement of joints (optional for standard or semi-custom installations), anchoring methods, anchors (if required), annotation of stone types and their location.

Corbelstone, Inc.

5831 Hilltop Drive
Flowery Branch, Ga. 30542
Office: 770-967-0076
www.corbelstone.com



1.6. QUALITY ASSURANCE

A. Manufacturer Qualifications:

1. Manufacturer shall have sufficient plant facilities to produce the shapes, quantities and size of Cast Stone required in accordance with the project schedule.

2. Manufacturer shall submit a written list of projects similar in scope and at least three (3) years of age, along with owner, architect and contractor references.

B. Mock-up (Optional) Provide full size unit(s) for use in construction of sample wall. The approved mock-up shall become the standard for appearance and workmanship for the project.

2. PART 2 - PRODUCTS

2.1. ARCHITECTURAL CAST STONE

A. Physical properties: Provide the following:

1. Compressive Strength - ASTM C 1194: 6,500 psi (45 Mpa) minimum for products at 28 days.

2. Absorption - ASTM C 1195: 6% maximum by the cold water method, or 10% maximum by the boiling method for products at 28 days.

B. Job site testing – One (1) sample from production units may be selected at random from the field for each 500 cubic feet (14 m³) delivered to the job site.

1. Three (3) field cut cube specimens from each of these samples shall have an average minimum compressive strength of not less than 80% of design strength or as allowed by ACI 318.

2. Three (3) field cut cube specimens from each of these samples shall have an average maximum cold-water absorption of 6%.

3. Field specimens shall be tested in accordance with ASTM C 1194 and C 1195.

2.2. RAW MATERIALS

A. Portland cement – Type I or Type III, white and/or grey, ASTM C 150.

B. Coarse aggregates - Granite, quartz or limestone, ASTM C 33, except for gradation, and are optional for the VDT casting method.

C. Fine aggregates - Manufactured or natural sands, ASTM C 33, except for gradation.

D. Colors - Inorganic iron oxide pigments, ASTM C 979 except that carbon black pigments shall not be used.

E. Admixtures- Comply with the following:

1. ASTM C 260 for air-entraining admixtures.

2. ASTM C 494 for water reducing, retarding or accelerating admixtures.

3. Other admixtures: integral water repellents and other chemicals for which no ASTM Standard exists, shall be previously established as suitable for use in concrete by proven field performance or through laboratory testing.

4. ASTM C 618 mineral admixtures of dark and variable colors shall not be used in surfaces intended to be exposed to view.

5. ASTM C 989 granulated blast furnace slag may be used to improve physical properties. Tests are required to verify these features.

F. Water – Potable

G. Reinforcing bars:

1. ASTM A 615/A 615M. Galvanized or epoxy coated when cover is less than 1-1/2 inches (37 mm).

H. All anchors, dowels and other anchoring devices and shims shall be standard building stone anchors commercially available in a non-corrosive material such as zinc plated, galvanized steel, brass, or stainless steel Type 302 or 304.


2.3. COLOR AND FINISH

A. Match sample on file in architect's office.

B. All surfaces intended to be exposed to view shall have a fine-grained texture similar to natural stone, with no air voids in excess of 1/32 in (0.8 mm) and the density of such voids shall be less than 3 occurrences per any 1 in. (25 mm²) and not obvious under direct daylight illumination at a 5 ft. (1.5m) distance.

Corbelstone, Inc.

5831 Hilltop Drive
Flowery Branch, Ga. 30542
Office: 770-967-0076
www.corbelstone.com



C. Units shall exhibit a texture approximately equal to the approved sample when viewed under direct daylight illumination at a 10 ft. (3 m) distance.

1. ASTM D 2244 permissible variation in color between units of comparable age subjected to similar weathering exposure.

a. Total color difference – not greater than 6 units.

b. Total hue difference – not greater than 2 units.

D. Minor chipping resulting from shipment and delivery shall not be grounds for rejection. Minor chips shall not be obvious under direct daylight illumination from a 20-ft (6 m) distance.

2.4. REINFORCING

A. Reinforce the units as required by the drawings and for safe handling and structural stress.

B. Welded wire fabric reinforcing shall not be used in dry cast products.

2.5. CURING

A. Cure units in a warm curing chamber at 95 percent relative humidity for approximately 18 hours, or yard cure for 350 degree-days (i.e. 7 days @ 50°F (10°C) or 5 days @ 70°F (21°C)) prior to shipping.

B. Remove cement film from exposed surfaces prior to packaging for shipment.

2.6. MANUFACTURING TOLERANCES

A. Cross section dimensions shall not deviate by more than $\pm 1/8$ inch (3 mm) from approved dimensions.

B. Length of units shall not deviate by more than length/ 360 or $\pm 1/8$ inch (3 mm), whichever is greater, not to exceed $\pm 1/4$ inch (6 mm).

1. Maximum length of any unit shall not exceed 15 times the average thickness of such unit unless otherwise agreed by the manufacturer.

C. Warp, bow or twist of units shall not exceed length/ 360 or $\pm 1/8$ inch (3 mm), whichever is greater.

D. Location of dowel holes, anchor slots, flashing grooves, false joints and similar features – On formed sides of unit, $1/8$ inch (3 mm), on unformed sides of unit, $3/8$ inch (9 mm) maximum deviation.

2.7. DELIVERY, STORAGE AND HANDLING

A. Mark production units with the identification marks as shown on the shop drawings.

B. Package units and protect them from staining or damage during shipping and storage.

Provide an itemized list of product to support the bill of lading.

2.8. APPROVED MANUFACTURERS

A. All Cast Stone products will be provided by:

Corbelstone, Inc. 5831 Hilltop Drive Flowery Branch, GA 30542

Phone: 770.967.0076, Fax: 770.967.7102, or approved equal.

3. PART 3—EXECUTION

3.1. EXAMINATION

A. Installing contractor shall check Cast Stone materials for fit and finish prior to installation. Do not set unacceptable units.

3.2. SETTING TOLERANCES

A. Comply with Cast Stone Institute Technical Manual.

B. Set stones $1/8$ inch (3 mm) or less, within the plane of adjacent units.

C. Joints, plus - $1/16$ inch (1.5 mm), minus - $1/8$ inch (3 mm).

3.3. JOINTING

A. Joint size:


1. At stone/brick joints $3/8$ inch (9.5 mm).

2. At stone/stone joints in vertical position $_\$ inch (6 mm) ($3/8$ inch (9.5 mm) optional).

3. Stone/stone joints exposed on top $3/8$ inch (9.5 mm).

Corbelstone, Inc.

5831 Hilltop Drive
Flowery Branch, Ga. 30542
Office: 770-967-0076
www.corbelstone.com



B. Joint materials:

1. Mortar, Type N, ASTM C 270.
2. Use a full bed of mortar at all bed joints.
3. Flush vertical joints full with mortar.
4. Leave all joints with exposed tops or under relieving angles open for sealant.
5. Leave head joints in copings and projecting components open for sealant.

C. Location of joints:

1. As shown on shop drawings.
2. At control and expansion joints unless otherwise shown

3.4. SETTING

- A. Drench units with clean water prior to setting.
- B. Fill dowel holes and anchor slots completely with mortar or non-shrink grout.
- C. Set units in full bed of mortar, unless otherwise detailed.
- D. Rake mortar joints (18 mm) inch for pointing.
- E. Remove excess mortar from unit faces immediately after setting.
- F. Tuck point unit joints to a slight concave profile.

3.5. JOINT SEALANT

- A. Comply with requirements of Section 07 90 00.
- B. Prime ends of units, insert properly sized backing rod and install required sealant.

3.6. REPAIR AND CLEANING

- A. Repair chips with touchup materials furnished by manufacturer.
- B. Saturate units to be cleaned prior to applying an approved masonry cleaner.
- C. Consult with manufacturer for appropriate cleaners.

3.7. INSPECTION AND ACCEPTANCE

- A. Inspect finished installation according to Section 2.3
- B. Do not field apply water repellent until repair, cleaning, inspection and acceptance is completed.