

MEST ELEVATION

SCALE: 9/32" = 1'-0"





EAST ELEVATION

SCALE: 8/82" = 1'-0"

	EXTERIOR MATERIAL SCHEDULE
	CERTAINTEED LANDMARK SHINGLES COLOR DRIFTWOOD
2	WHITE AZEK: FASCIA BOARD
(3)	CERTAINTEED FRIEZE BOARD
4	CERTAINTEED CERTATRIM TRIM BOARD
(5)	CERTAINTEED MONOGRAM VINYL SIDING COLOR NATURAL CLAY
6	ANDERSEN DOUBLE HUNG WINDOW.
7	WHITE AZEK TRIM PANEL
8	ROCKCAST ACCENT BAND
<a>9</a>	ELDORADO STONES HILLSTONE VERONA SERIES
(10)	KALINEER STOREERONT ALLIM/GLASS DOOR

DATE

12-1-2023 REVISED DRAWING

ISSUED

SEAL

215 ROANOKE AVENUE RIVERHEAD, NY 11901 (631) 727-5352



Terryville fire district 632 old Town Road Port Jefferson Station, ny 11776 SCTM # 0200-311-1-1,3&16,1

PROPOSED ELEVATIONS


PROJECT No. 2201.02


CHECKED BY: MFS


DRAWN BY: JC

DRAWING:

A-2







## PARK EAST CONSTRUCTION CORP.

266 E. Jericho Turnpike Huntington Station New York 11746

пu	ntington Station New York 11746
	Project: Terryville Fire District

Address: 632 Old Town Rd Port Jefferson Station NY 11776

Floors / Size: 1 Floor

Architect / Engineer: Sendlewski Architects

## Terryville FD Station #2

1/16/2024

18,027

2023-059 R1

Date

SQ. FT

Estimator

Estimate Number

	Terryvine FD Station #2		
CSI Name	CSI Sec Description of work		Subtotal
<u>Site work</u>	CSI Sec Description of work		
Site Demolition	02 40 00 Clear & grub Area		
Land Clearing	02 40 00 Clear forested area		
Site Demolition	02 40 00 Excavate, disconnect, and remove existing gas & water mains		
Site Demolition	02 40 00 Excavate site, remove soil		
Site Work	02 40 00 Grade and level land		
Site work	02 40 00 Survey & soil testing		
Site work	02 40 00 Backfill and compact demolished building basement		
Site work	02 40 00 Disconnect & abandon existing sanitary system. Install (2) new sanitary systems		
Site work	02 40 00 Tap and connect into existing water and gas mains supplied by local utility.		
Site work	02 40 00 Install trench drain at front of property		
Site work	02 40 00 Install catch basins and associated piping in parking lot		
Site work	02 40 00 Trenching for utility mains		
Site work	02 40 00 Oil & water separator		
Site Work	02 40 00 Oli & Water Separator	SUBTOTAL	\$ 67
	COCCO Description of work	SUBTUTAL	<del>y</del> 07
<u>Demolition</u>	CSI Sec Description of work		
Site Demolition	02 10 00 Demo & remove existing building on site		
Site Demolition	02 10 00 Chop and remove curbs, sidewalk, existing asphalt		
Site Demolition	02 10 00 Surgical demo of existing radio tower building (all electronics to remain in place protected from elements)		
Site Demolition	02 10 00 Remove any existing fencing on site		
Site Demolition	02 10 00 Chop and remove poured epoxy flooring in existing apparatus bay		
Site Demolition	02 10 00 Remove existing shipping containers on site		
Site Demolition	02 10 00 Asbestos remediation & associated air monitoring. <b>Budgetary pricing based on no ACM report at time of budget.</b>		
		SUBTOTAL	\$ 47
Asphalt	CSI Sec Description of work	SOBIOTAL	<del>Y</del>
Asphalt sub base	32 12 00 RCA		
Asphalt sub base  Asphalt prep	32 12 00 Fine Grade parking lot		
Asphalt Paving	32 12 00 Paving of parking lot		
Asphalt Marking	32 12 00 Line Striping		
Asphalt Marking	52 12 00 Line Striping	SUBTOTAL	\$ 43
Familia I Cata	CCCC - Description of work	SOBIOTAL	<del></del>
Fencing   Gates	CSI Sec Description of work		
Fencing	32 31 00 Perimeter 6' chain link fence w privacy screen		
Fencing	32 31 00 Set fence posts in concrete	CURTOTAL	<u> </u>
		SUBTOTAL	\$ 13
Building   Site Concrete	CSI Sec Description of work		
Concrete	03 30 00 Sidewalk, curbs, islands		
Concrete	03 30 00 Building foundation & footings		
Concrete	03 30 00 Concrete slab 8"		
Concrete	03 30 00 Scarify existing concrete slab to accept new slab.		
		SUBTOTAL	\$ 65
Masonry	CSI Sec Description of work	SUBTUTAL	<del>y</del> 03
Masonry	04 22 00 Brick pavers		
Masonry	04 22 00 CMU Wall	<del>-</del>	
Masonry	04 22 00 Rockcast accent band		
Masonry	04 22 00   Stone Wall	<del></del>	
Masonry	04 22 00   Storie Wall	<del></del>	

Characterist Adian Charal				
Structural - Misc. Steel	05 13 00	14' v 14' Poll up garage dears meterized	+	
Rolling Doors	05 12 00	14' x 14' Roll up garage doors motorized	+	
Structural Steel	05 12 00	Steel support members for garage bay doors  Mazzanina system including stair, bandrall decking		
Structural Steel	05 12 00	Mezzanine system including stair , handrail, decking  Steel Columns, Beams, Lintels		
Structural Steel	05 12 00		ċ	548,000
		SUBTOTAL	۶	548,000
Carpentry	CSI Sec	Description of work	4	
Carpentry	09 25 00	Exterior building furring for vinyl siding & building wrap	+	
Carpentry	09 25 00	Sheetrock partitions single single	+	
Carpentry	09 25 00	Sheetrock partitions double double water resistant (green board or similar)	+	
Carpentry	09 25 00	Exterior vinyl siding	+	
Carpentry	09 25 00	Azek fascia board	+	
Carpentry	09 25 00	Frieze board	+	
Carpentry	09 25 00	Install bathroom accessories	+	
Carpentry	09 25 00	Install Doors, frames, hardware	+	
Carpentry	09 25 00	Andersen double hung window w trim panel	<b>↓</b>	
Carpentry	09 25 00	Andresen single window		
Carpentry	09 25 00	Master keying		
Carpentry	09 25 00	Roof sheathing		
Carpentry	09 25 00	ACT CONTRACT	+	
Carpentry	09 25 00	Roof Truss	1	
		SUBTOTA	\$	1,416,89
Roofing	CSI Sec	Description of work		
Roofing	07 54 00	Architectural shingle roof		
		SUBTOTA	L \$	225,33
<u>Doors Frames Hardware</u>		Description of work	A	
HM Doors	08 10 00	Interior HM Doors w HM Frame & Hardware		
Exterior Doors	08 13 00	Exterior doors Kawneer Storefront Aluminum/Glass Door		
		SUBTOTA	. \$	94,50
Rolling Doors		Description of work		
Rolling Doors	05 12 00	Motorized roll up bay doors		
			\$	160,000
Flooring		Description of work		
Poured Floor	09 67 00	Epoxy flooring at apparatus bay		
Carpet	09 60 00	LVT in ready room, storage areas, EMS, ALS, BLS, tool work room, radio room, & hall		
Resilient Base	09 65 00	Rubber wall base in all LVT & Carpeted Areas		
Carpet	09 68 13	Carpet tile in offices, bunk rooms & training room		
·		SUBTOTA	. \$	221,00
Ceramic Tile Stone		Description of work		
Tile	09 65 19	Bathroom tile flooring		
Tile	09 65 19	Bathroom tile wall & base		
		SUBTOTA	\$	36,64
Painting		Description of work		
Painting	09 91 00	Finish paint partitions		
Painting	09 91 00	Epoxy paint in apparatus bay	<b>†</b>	
Painting	09 91 00	Paint concrete floor in mezzanine, & mechanical rooms	1	
	1	SUBTOTAL	\$	146,16
Accessories	CSI Sec	Description of work		-11,20
Lavatory Partitions	10 21 13	Toilet partitions & accessories (grab bar, toilet paper holder, toilet seat cover dispenser, sanitary napkin disposal for women's rooms & single use restrooms)		
Shower & Dressing Compartments	10 21 16	Shower stalls	<del>+</del>	
Appliances	10 30 00	Allowance refrigerator	+	
Appliances	10 30 00	Allowance oven	+	
Appliances  Appliances	10 30 00	Allowance microwave	+	
Appliances Appliances	10 30 00	Allowance coffee maker	+	-
Appliances	10 30 00	Gear wash / dryer	+	
Appliances	10 30 00	FFE (Bunks, office furniture, lockers)	+	
	10 30 00	Stainless Steel Kitchen Cabinetry & Island	+	
Appliances	10 30 00	Stainless Steel Kitchen Cabinetry & Island SUBTOTAL	¢	260,50
Cierran	CCI C		,	200,50
<u>Signage</u>	CSI Sec	Description of work	4	
Signage	10 14 00	Exterior signage for building	+	
Signage	10 14 00	Interior signage (wayfinding, room labeling)	+	
		SUBTOTAL	Ş	45,00
14.0	CSI Sec	Description of work	4	
Millwork   Casework				
Millwork	06 22 00	PLAM Base cabinetry & countertop for the training room & gear wash area)		
				46,00

1/16/2024

<u>Fire Suppression</u>	Sec Description of work	
Sprinkler System 2	000 Allowance for sprinkler system including, sprinkler heads (both concealed & upright), main piping, and associated branch piping as required.	
	SUBTOTAL	\$ 144,21
Plumbing	Sec Description of work	
Lavatories 2	0 00 Men's Lavatory (1 toilet stall, 2 urinals, 2 sinks)	
Lavatories 2	0 00 Women's Lavatory (3 toilet stalls, 2 sinks)	
Lavatories 2	0 00 Single use lavatory (1 toilet, 1 Sink, 1 shower)	
Plumbing 2	0 00 Drinking fountain hookup	
Plumbing 2	0 00 Janitors closet slop sink	
Plumbing 2	0 00 Pantry Sink	
Plumbing Piping 2	0 00 Water lines for appliances	
Plumbing Piping 2	0 00 Connect gas to existing utility	
Plumbing Piping 2	0 00 Connect water to existing utility	
Plumbing 2	0 00 Floor drains	
Plumbing 2	0 00 Chemically clean system prior to use	
Plumbing Piping 2	0 00 Water boiler	
Plumbing Piping 2	0 00 Misc. pipe, fittings, connections	
	SUBTOTAL	\$ 653,500
<u>HVAC</u>	Sec Description of work	
HVAC Air Distribution 2	0 00 Allowance for HVAC System including HVAC units, ductwork, diffusers, etc.	
Garage Accessories 1	9 00 Allowance Air Hawk Exhaust Removal System	
	SUBTOTAL	\$ 1,056,485
Electrical   Fire Alarm	Sec Description of work	
Electric 2	0 00 Allowance for electric service panel, conduit, devices, wire etc.	
Electric 2	0 00 Parking lot light fixtures	
Electric 2	0 00 Exterior building lights	
Electric 2	0 00 Exit signs with battery packs	
Electric 2	0 00 Allowance fire alarm system including fire alarm speaker/strobes, smoke detectors, etc.	
Electric 2	0 00 BDA System (NOT INCLUDED)	
	SUBTOTAL	\$ 1,074,985
<u>Low Voltage</u>	Sec Description of work	
	0 00 Allowance for low voltage system including PA, Security Devices, Data, Voice, Etc.	
· ·	SUBTOTAL	\$ 63,095
Landscaping	Sec Description of work	
	0 90 New sod, including irrigation system	
Landscaping 3	0 90 Allowance trees & privacy planting	
1 0	SUBTOTAL	\$ 151,499
Trade Sub-total	Trade Sub-total	\$ 9,347,618
General Conditions	8%	\$ 747,80
	Construction Total Including General Conditions	\$ \$ 10,095,42
	Construction Total Including General Conditions per Square Foot	
Construction Contingency (Hard Costs)	5%	
Arch & Engineering	7%	
CM Fee		5 \$ 567,11
Soft Costs Soft Costs		\$ 952,74
Escalation		5 \$ 514,48
	Project Tota	
	Project Total per Square Foot	
	BUDGET SUMMARY INCLUDING SOFT COSTS, ESCALATION, & CONTINGENCY, FEES	
	Terryville Station #2 Renovations	\$ \$ 13,376,552
	Profabricated Motal Ruilding Located at the site of Terreville Station #3	1 5 225 0//
	Prefabricated Metal Building Located at the site of Terryville Station #2  Main Firehouse Work	



CORP.		1
- NO. (Bouleact of the		1
266 E. Jericho Turnpike		1
Huntington Station New York 11746		
Project: Terryville Fire District	Date	1/16/2024
Address: 632 Old Town Rd Port Jefferson Station NY 11776	Estimate Number	2023-059 R1
Floors / Size: 1 Floor	Estimator	JS
Architect / Engineer: Sendlewski Architects	SQ. FT	8,000
	Terryville Station #2 Prefabricated Metal Building	
CSI Name CSI Sec	Description of work	Subtotal
Site work CSI Sec	Description of work	
Site Demolition 02 40 00	Trenching for water & gas main	
Site Work 02 40 00	Excavation for building foundation & footings	
Site Work 02 40 00	Catch basins & associated piping for roof drainage	
Site Work 02 40 00	Bollards	
	SUBTOTAL	\$ 25,363
Building   Site Concrete CSI Sec	Description of work	
Concrete 03 30 00	Sidewalk, curbs, islands	
Concrete 03 30 00	Foundation & Footings	
Concrete 03 30 00	Concrete slab 6"	
Concrete 03 30 00	Concrete decking at mezzanine	
	SUBTOTAL	\$ 148,500
Structural - Misc. Steel	Description of work	
Rolling Doors 05 12 00	Steel member supports for garage bay doors	
Mezzanine System 05 12 00	Mezzanine system including stair, handrail, decking	
	SUBTOTAL	\$ 120,000
<u>Carpentry</u> CSI Sec	Description of work	· ·
Carpentry 09 25 00	Sheetrock partitions Approx 120 LF	
Carpentry 09 25 00	Sheetrock partitions water resistant (green board or similar) in restrooms Approx 50LF	
Carpentry 09 25 00	Framing & insulation of garage interior	
Carpentry 09 25 00	Install bathroom accessories	
Carpentry 09 25 00	ACT Ceilings	
Carpentry 09 25 00	Install Doors, frames, hardware	
Carpentry 09 25 00	Andersen double hung window w trim panel (4 windows total in prefab building)	
Carpentry 09 25 00	Master keying	
	SUBTOTAL	\$ 169,355
Roofing CSI Sec	Description of work	
Roofing 07 54 00	Gutters & downspouts	
	SUBTOTAL	\$ 6,000
Prefabricated Buildings CSI Sec	Description of work	
Prefabricated Buildings 10 09 00	Butler style building or equal with standing seam roof. Turnkey shell	
	SUBTOTAL	\$ 330,000
<u>Doors Frames Hardware</u>	Description of work	
HM Doors 08 10 00	Interior hollow metal doors, with hollow metal frames & hardware	
Exterior Doors 08 13 00	Exterior steel man doors	
	SUBTOTAL	\$ 8,500
Rolling Doors	Description of work	
Garage Bay Doors 08 00 00	Motorized roll up bay doors	
		\$ 80,000
<u>Flooring</u>	Description of work	
Poured Floor 09 67 00	Polished concrete flooring	
Carpet 09 60 00	LVT	
Resilient Base 09 65 00	Rubber wall base	
	SUBTOTAL	\$ 35,170

Painting	Description of work	
Painting 09 91 00	Finish paint partitions	
Painting 09 91 00	Paint polished concrete floor in garage bay	
		\$ 73,2
<u>Accessories</u> CSI Sec	Description of work	
Lavatory Partitions 10 21 13	Toilet accessories (grab bar, toilet paper holder, toilet seat cover dispenser, sanitary napkin disposal)	
Signage 10 09 00	Misc. interior signage (ADA & Directional)	
	SUBTOTAL	\$ 10,5
<u>Fire Suppression</u> CSI Sec	Description of work	
Sprinkler System 21 00 00	Sprinkler system	
	SUBTOTAL	\$ 72,0
Plumbing CSI Sec	Description of work	
Lavatories 22 00 00	(2) Single use lavatory (1 toilet, 1 Sink)	
Plumbing 22 00 00	Drinking fountain hookup	
Plumbing Piping 22 00 00	Connect gas to existing utility	
Plumbing Piping 22 00 00	Connect water to existing utility	
Plumbing 22 00 00	Chemically clean system prior to use	
Plumbing Piping 22 00 00	Misc. pipe, fittings, connections	
Plumbing 22 00 00	Check valves	
Plumbing 22 00 00	Hot Water Heater (Electric)	
	SUBTOTAL	\$ 75,0
<u>HVAC</u> CSI Sec	Description of work	
HVAC 23 00 00	Mini split HVAC System (Heat Pump & A/C)	
HVAC 23 00 00	Gas fired heaters for apparatus bay (Modine or similar)	
HVAC 23 00 00	Exhaust Fans (5)	
Garage Accessories 10 99 00	Allowance Air Hawk Exhaust Removal System	
	SUBTOTAL	\$ 190,00
Electrical   Fire Alarm CSI Sec	Description of work	
Electric 26 00 00	Allowance for electric service panel, conduit, devices, wire etc.	
Fire Alarm 26 00 00	Allowance FA System speaker/strobe, smoke detectors, etc.	
	SUBTOTAL	\$ 270,00
<u>Low Voltage</u> CSI Sec	Description of work	
Low Voltage 27 00 00	Low Voltage allowance	
	SUBTOTAL	\$ 9,00
Trade Sub-total	Trade Sub-total	\$ 1,622,5
General Conditions	8%	
	Construction Total Including General Conditions	\$ 1,752,3
	Construction Total Including General Conditions per Square Foot	\$ 2
Construction Contingency (Hard Costs)	5%	
Arch & Engineering		
CM Fee		
Soft Costs	4%	\$ 82,6
Escalation	4%	
	Project Total	
	Project Total per Square Foot	\$ 2

5



66 E. Jericho Turnpike Iuntington Station New York 11746			
Project: Terryville Fire District		Date	1/16/2024
Address: 632 Old Town Rd Port Jefferson Station NY 11776		Estimate Number	2023-059 R1
Floors / Size: 1 Floor		Estimator	JS
Architect / Engineer: Sendlewski Architects		SQ. FT	25,960
, and a second s		Terryville Main Firehouse Refresh	
CSI Name	CSI Sec	Description of work	Subtotal
<u>Demolition</u>	CSI Sec	Description of work	
Site Demolition	02 10 00	Remove existing RTU	
Site Demolition	02 10 00	Remove existing curbing at RTUs	
Site Demolition	02 10 00	Surgically demo and remove existing siren tower	
Interior Demolition	02 10 00	Remove existing flooring in meeting room carpet & assumed wood flooring, includes decking as required	
Interior Demolition	02 10 00	Remove existing wallpaper, wall base & chair rails in meeting room, entry vestibule, chiefs offices, & misc. areas as required	
Interior Demolition	02 10 00	Remove all existing gold light fixture grids	
Interior Demolition	02 10 00	Chop and remove existing flooring in apparatus bay	
Interior Demolition	02 10 00	Remove flooring at interconnecting hallways bathrooms, kitchen	
		CURTOTAL	\$ 213,140
	2010	SUBTOTAL	3 213,140
Building   Site Concrete	CSI Sec	Description of work	
Concrete	03 30 00	Pour new curbs for RTUs on flat ceiling	4 440
		SUBTOTAL	\$ 4,410
<u>Carpentry</u>	CSI Sec	Description of work	
Carpentry	09 25 00	Fabricate new siren tower housing with drainage and install Allowance	
Carpentry	09 25 00	Remove existing sub flooring in meeting room as required and install new.	
Carpentry	09 25 00	Install new chair rail & bead board in meeting room	
Carpentry	09 25 00	Install new white or chrome grids in light fixtures	
Carpentry	09 25 00	Replace sub flooring in kitchen and men's restroom	
Carpentry	09 25 00	Cut out water damaged sheetrock ceiling and replace Allowance	
Carpentry	09 25 00	Allowance to replace ceiling tiles (2 boxes)	
		SUBTOTAL	\$ 79,890
<u>Roofing</u>	CSI Sec	Description of work	
Roofing	07 54 00	Remove existing roofing & decking	
Roofing	07 54 00	Install new decking & architectural shingle roofing, entire pitched roof of firehouse	
Roofing	07 54 00	Install gutters in all locations where pitched roof meets flat roof	
Roofing	07 54 00	Install new flat roof	
Roofing	07 54 00	Replace drain covers	
		SUBTOTAL	\$ 286,200
<u>Doors Frames Hardware</u>		Description of work	
Wood Doors	08 10 00	F/I New 90 minute wood doors, hardware	
		SUBTOTAL	\$ 54,000
<u>Flooring</u>		Description of work	
Poured Floor	09 67 00	Poured epoxy flooring in apparatus bay, interconnecting hallways, bathrooms, kitchen. Level floors as required	
Carpet	09 60 00	New LVT or Carpet tile flooring in meeting room. Self level as required to reduce ramping as much as possible	
Resilient Base	09 65 00	New Rubber base in meeting room	
Poured Floor	09 67 00	Replace terrazzo treads in stairwell	
Poured Floor	09 67 00	Replace terrazzo style tiles on main level	
Flooring	09 60 00	Level floor in kitchen	
<u> </u>		SUBTOTAL	\$ 403,078
<u>Ceramic Tile Stone</u>		Description of work	, in the second second
Tile	09 65 19	Simulated stone feature wall in vestibule	
Tile	09 65 19	Subway tile backsplashes in kitchen	
Tile	09 65 19	Replace first course of tile in restrooms	
	1 22 22 29	SUBTOTAL	\$ 43,900

		<del>-</del>		
<u>Painting</u>				
Painting	09 91 00	Skim and paint partitions in all areas where wall paper has been removed.		
			\$	52,500
<u>Accessories</u>	CSI Sec	Description of work		
Kitchen Cabinetry	10 21 13	Stainless steel cabinetry in kitchen & ready room.		
		SUBTOTAL	\$	40,000
Signage	CSI Sec	Description of work		
Signage	10 14 00	Allowance for fire department logo signage on feature wall lit or backlit		
Signage	10 14 00	Lettering on feature wall		
		SUBTOTAL	\$	45,000
Millwork   Casework_	CSI Sec	Description of work		
Millwork	06 22 00	New display cabinetry in meeting room		
Millwork	06 22 00	New base cabinets in rear of meeting room		
		SUBTOTAL	\$	68,750
Plumbing	CSI Sec	Description of work		
Plumbing	22 00 00	Abandon and safe off floor drain in kitchen currently not in use.		
		SUBTOTAL	\$	3,000
HVAC	CSI Sec	Description of work		
HVAC	23 00 00	Furnish & Install (2) new RTUs		
HVAC	23 00 00	Disconnect & reconnect existing to remain RTUs to allow for new roof work		
		SUBTOTAL	\$	170,000
Electrical   Fire Alarm	CSI Sec	Description of work		
Electric	26 00 00	Disconnect & reconnect RTU electricity		
Electric	26 00 00	Disconnect & reconnect siren at roof		
Electric	26 00 00	Connect new lighting in millwork display cabinetry in meeting room.		
Electric	26 00 00	Replace wallpacks on building exterior		
Electric	26 00 00	Replace FA System with addressable system		
1	1	SUBTOTAL	\$	260,500
Trade Sub-total		Trade Sub-total	Ś	1,724,368
General Conditions		8%	Ś	137,949
Citetal Containons		Construction Total Including General Conditions	-	1,862,317
Construction Contingency (Hard Costs)	1	5%		93,116
Architecture & Engineering Fees		7%		136,880
CM Fee		5%		104,616
Soft Costs		4%		87,877
Escalation	1	4%		91,392
Total		7/0	Ś	2,376,199
TOLAI			Ÿ	2,3,0,133

1/16/2024



## How Much is it Going to Cost Me?

Amount of Bond	Proposed Term	Est. Interest Rate (Current Market Conditions)	Estimated Net Increase per \$100 Assessed Value
\$17,990,000	25 Years	4.60%	\$ 5.73

For the average house assessed at \$2,850, the tax increase would be approximately \$164 per year  $(28.50 \times 5.73 = $163.31)$ 







## STATEMENT OF TAXES: 2023-2024

PHYSICAL ADDRESS: STAR SAVINGS: \$.00

SCTM: STAR SAVINGS: \$.00

ITEM NUMBER: \$23.50 x \$5.73 = \$134.66

SCHOOL PHONE 631-474-8116

LAND ASSSESSMENT

FULL ASSESSED VALUE
2,350

UNIFORM %
FULL VALUE
2,350

WHICH IS 0.62% of 379,032

LEVY DESCRIPTION	TAXABLE VALUE	TAX RATE PER 100	TAX AMOUNT W/ EXEMPTIONS	TAX AMOUNT W/O EXEMPTIONS
School Tax	69.94% OF TO	TAL BILL	\$7,052.94	\$7,052.94
SCHOOL DISTRICTS - COMSEWOGUE UFSD	2,350	285.749	\$6,715.10	\$6,715.10
LIBRARY DISTRICTS - COMSEWOGUE UFSD	2,350	14.376	\$337.84	\$337.84
County Tax	10.89% OF TO	TAL BILL	\$1,097.85	\$1,097.85
COUNTY OF SUFFOLK	2,350	2.422	\$56.92	\$56.92
COUNTY OF SUFFOLK - POLICE	2,350	44.295	\$1,040.93	\$1,040.93
Town Tax	6.16% OF TOTA	AL BILL	\$621.65	\$621.65
TOWN - TOWN WIDE FUND	2,350	6.773	\$159.17	\$159.17
HIGHWAY - TOWN WIDE FUND	2,350	1.785	\$41.95	\$41.95
TOWN - PART TOWN FUND	2,350	2.121	\$49.84	\$49.84
HIGHWAY - PART TOWN FUND / SNOW REMOVAL	2,350	15.774	\$370.69	\$370.69
Other Taxes	13.01% OF TO	TAL BILL	\$1,311.49	\$1,311.49
NEW YORK STATE MTA TAX	2,350	.145	\$3.41	\$3.41
OPEN SPACE PRESERVATION	2,350	2.294	\$53.91	\$53.91
BROOKHAVEN REFUSE - RECYCLING IMP 1 FAMI	2,350		\$387,98	\$387.98
FIRE DISTRICTS - TERRYVILLE	2,350	30.589	\$718.84	\$718.84
LIGHTING DISTRICTS - BROOKHAVEN	2,350	1.282	\$30.13	\$30.13
REAL PROPERTY TAX LAW	2,350	4.033	\$94.78	\$94.78
OUT OF COUNTY TUITION	2,350	.746	\$17,53	\$17.53
SUFFOLK COUNTY COMMUNITY COLLEGE TAX	2,350	.209	\$4.91	\$4.91
Total Tax Rate	Tax Amounts	412.593	\$10,083.93	\$10,08

BILLED AMOUNTS

1ST HALF: \$5,041.97 - 2ND HALF: \$5,041.96 - TOTAL: \$10,083.93

PAYMENTS

Type Process Date RCPT Pmt\_Date Penalty Amt Paid Payor Operid

EXEMPTIONS

DESCRIPTION CODE VALUE FULL VALUE REAL SAVINGS

