County Rebuild Alabama Fund 2020 - 2024 Projected Projects

ROAD NAME/NUMBER	WIDTH (FEET)	MI.	Zipping $130/ton	Double Surface	Single Surface	Micro ($2.50/sy)	Asphalt Patching (660 lbs/sy)	Asphalt Leveling (100 lb/sy)	Asphalt Level/ Wearing (165 lbs/sy)	Asphalt Level/ Wearing (110 lbs/sy)	Thermo Striping (Centerline Only) $6,000/mi	Paint Striping (Centerline Only) $1,400/mi	Total
BLOUNT AVE	18	0.19	$4,499	$9,029	$6,521	$5,016	$37,244	$13,042	$21,519	$13,042	$1,140	$266	**$58,762**
HOWLE ST	20	0.09	$4,736	$4,752	$3,432	$2,640	$19,602	$6,864	$11,326	$6,864	$540	$126	**$30,928**
RIVER STONE CRT	20	0.07	$368	$3,696	$2,669	$2,053	$9,148	$5,339	$8,809	$5,339	$420	$98	**$14,486**
RIVER STONE WAY	20	0.28	$1,473	$14,784	$10,677	$8,213	$36,590	$21,355	$35,235	$21,355	$1,680	$392	**$57,945**
BROOKLEY DR	17	0.37	$2,483	$16,606	$11,993	$9,225	$41,099	$23,986	$39,577	$23,986	$2,220	$518	**$80,676**
MOCKINGBIRD LN	18	0.72	$6,820	$34,214	$24,710	$19,008	$84,681	$49,421	$53,945	$49,421	$4,320	$1,008	**$142,945**
OLD SALEM RD	20	0.81	$8,525	$36,115	$30,888	$23,760	$70,567	$61,776	$67,431	$61,776	$4,860	$1,134	**$142,858**
Totals		**2.53**	**$28,905**	**$119,196**	**$90,891**	**$69,916**	**$298,931**	**$181,782**	**$237,841**	**$181,782**	**$15,180**	**$3,542**	**$528,600**
Patching & repair work as necessary	***	Continue to patch pot-holes and do road repairs as needed and funds are available.											
Intersection of Hwy 63 and E Collins Ave	***	Coordinate with ADOT to put in turn-lane and widen road for truck traffic (possible grant application).											
First Ave (Main to East Collins)													
Nichols Ave (Main to Collins)													
Varner St													
Town Hall Parking Lot													
** Elmore County contracted to complete road work with town reimbursing them for the related cost. (August 2022)													
Completed													