

March 10, 2020

ADDENDUM NO. 1
Eden Isle Corporation

WASTEWATER PUMP STATION & FORCE MAIN
CWB Project No. 17-075

This addendum shall be considered part of the Plans, Specifications, and Contract Documents and is issued to change, amplify, delete from, or otherwise explain these documents where provisions of this addendum differ from those of the original documents. This addendum shall have precedence over the original documents and shall govern.

Force Main Project Technical Specifications

HDPE installed by HDD in areas with unimproved surfaces, will not require annular grout. Refer to the specification change below.

1. Section 330523.15 - UTILITY LINE BORES

Edit *Part 3.04 C.* of Specification *Section 330523.15, Page 4* to read as follows:

- C. *For HDPE Carrier pipe installed by HDD in areas under improved surfaces, such as, driveways, alleys, city streets, and county roads, the pipe must either be installed in encasement pipe under and to five feet outside of each improved surface, OR annular grout must be injected after pullback, extending under and to five feet outside of each improved surface. For areas of unimproved surface, the carrier pipe may be installed by HDD, without encasement or annular grout.***