

**La Plata Archuleta Water District**  
**Phase 1H Part 1 Water Distribution System Project**  
**Bid and Contract Documents:**

**To:** Prospective Project Bidders and Sub-Contractors  
**From:** David Henry, Harris Water Engineering obo LAPLAWD  
**Subject:** Addendum 4, Phase 1H Part 2 Water Distribution System Project  
**Date:** August 18, 2020

Greetings,

We have received one additional question, with a general answer provided below. A specific edit to the bid package is given in the following formal Addendum No. 4:

Questions received, with summary / clarification answers:

- 1) **Q.** For the fusible PVC Pipe now allowed in Gem village, can we use DR18 instead of DR14?  
**A.** AWWA C-900 and NSF-16 compliant DR18 Fusible PVC pipe (blue) will be allowed.

The Addendum follows. If you have any questions regarding this document, or if there are any additional Bid document or Project questions, please contact me per below, preferably in writing.

Thank you,

*David J. Henry*

Dave Henry, PE  
Harris Water Engineering  
(970) 259-1028 / Dave@durangowater.com

## **Addendum No. 4**

August 18, 2020

**This Addendum of the LAPLAWD Phase 1H Part 2 Water Distribution System Project is hereby issued as follows:**

1. Please ADD the text “or DR18” to the text provided in Addendum 2

Sheets 13, 14, 15, Drawing Notes, text previously added to note B4 shall now read:

[Pipe used in this boring may be] . . . “blue DR14 or DR18 AWWA C-900 and NSF-61 compliant Fused PVC (FCVP) pipe. All fusing shall be completed using manufacturer-approved equipment by a manufacturer-certified fusion technician. Technician shall complete and submit, to the Owner, data and log reports and certifications for all fusions.”

End