Conservation Cooperator

PROJECT FACT SHEET



LSC Highway Dept. Grade Stabilization

Cooperator & Location

Applicant(s): Le Sueur County Hwy/Brad Carlson

Address:

City State Zip: U

Twp/Range: T 109N - R 25W

Section:

City or Twp: Derrynane Twp

Funding Source: Jefferson Cermon CWF Watershed: 39107

Project Information

Practice

Grade Stabilization Structure

Resource Protected

Swedes Bay, Cannon River

Dates SWCD Review 5/6/2019

Project Start 12/31/2020 Project Finish 12/31/2020

Description

Install a grade stabilization structure 133' long. The ravine will be excavated out and granite stone will be used to backfill the ravine to stabilize it.

Environmental Benefits

<u>Parameter</u>	<u>Before</u>	After	Saved
Soil Erosion (tons/yr)	264.92	0	264.92
Sediment Load (tons/yr)	92.72	0	92.72
Phosphorus Load (lbs/yr)	96.6	0	96.6
Runoff Reduction (acre ft)	N/A	N/A	N/A

Construction Photo



Completed Photo



Cost Analysis

PROJECT	Costs	FUNDING SOURCES		%
<blank>></blank>		Landowner:	\$8,306.00	25
Contruction:	\$33,224.00	Federal:		
	33-7/	State:		
Total:	\$33,224.00	Grant:	\$28,429.00	75





Conservation Cooperator

PROJECT FACT SHEET



Cooperator & Location

Applicant(s): Brad Carlson

Address:

City State Zip:

Twp/Range: T 109N - R 25W

City or Twp: Washington Twp

Funding Source: Jefferson German CWF Watershed: 39107

Project Information

Practice

WASCOB

Resource Protected

Swedes Bay, Cannon River

Dates SWCD Review 2/26/2021 Project Start 3/9/2021 Project Finish 6/10/2021

Section: 13

Description

Install 4 water and sediment control basins approximately 1000 linear feet of basin to treat 26.7 acres of highly erodeable soils in the Swedes Bay watershed.

Environmental Benefits

<u>Parameter</u>	Before	After	Saved
Soil Erosion (tons/yr)	158.23	0	158.23
Sediment Load (tons/yr)	158.23	0	158.23
Phosphorus Load (lbs/yr)	185.23	0	158.23
Runoff Reduction (acre ft)	N/A	N/A	N/A

Cost Analysis

PROJECT COSTS	
<blank>></blank>	
Contruction:	\$35,909
Total:	\$35,909

FUNDING SOURCES %		
Landowner:	\$8,977.25	25
Match:	\$26,931.75	75
State:		
Grant:	\$35,909.00	

Brad Carlson WASCOB's

Before Photo



Completed Photo





Above: Brad Carlson WASCOB Construction Below: Brad Carlson completed WASCOB

