

TOWN of GRANT, Portage County

2018-19 ROAD PLAN

Submitted December 4, 2017

Road Construction Projects Recommended Candidate Listing

Road	Termini	Improvement	Length
Birch Drive	130 th Street S – Townline Rd	1X chip seal	1 mile
Elm Road	90th Street S – 100th Street S	Gravel/AC Overlay	1 mile
Grant Street	100 th Street S – 110 th Street S	1X chip seal	1 mile
Griffith Ave.	100 th Street S – 110 th Street S	Wedge/1x chip seal	1 mile
Grove Ave.	CTH U – 84th Street	Pulverize/Prep (ditch cuts, add swales), gravel, 2x chip seal	1/3 mile
Lake Road	90th Street S- 100th Street S	1X chip seal	1 mile
Mertz Acres	82 nd – 84 th Streets, Arbor, Cedar Spruce Lanes	AC overlay/ paved shoulders	~ 2 miles
Mill Road	CTH F – 100th Street	Prep/gravel/AC overlay/ shoulders	2 miles
Oak Street	CTH U – 90th Street	Prep/pulverize/gravel/AC overlay/shoulders	~ ½ mile
Oak Street	CTH F – 110 th Street	Spray patch/wedge, 2X chip seal or AC overlay	1 mile
100th Street	Elm St - cranberry marsh	Prep/gravel/AC overlay/Shoulders	¾ mile
100th Street	CTH WW – Lake Road (low priority)	Prep/gravel/AC overlay /shoulders	½ mile
87 th Street	Evergreen – Tower	Remove trees out to 25' from road center/prep/gravel, 2x chip seal	1 mile
90 th Street	CTH W – Griffith	Culvert replacements (6)	1 mile
95 th Street	Evergreen – termini	1x chip seal	½ mile
95 th /100 th St (see below)	Buena Vista Creek crossings	Replace headwalls, reconstruct approaches	

Road Maintenance/Materials Project Recommended Candidate Listing

- **Joint & Crack-sealing (TBA)** = ~\$20,000
- **Bridge/Culvert Maintenance (PRIORITY):**
Work includes but not limited to: fixing wash-outs, adding vertical end walls or culvert extensions and rip-rap, installing beam guards, replacing existing structures
 - 95th Street crossing Buena Vista Creek
 - 95th Street crossing Four Mile Creek
 - 100th Street crossing Buena Vista Creek
 - 100th Street crossing Four Mile Creek
 - 110th Street crossing Buena Vista Creek
 - 110th Street crossing Four Mile Creek
- Buena Vista Road (CTH F – 130th) –PRIORITY = clean ditches, reclaim materials, add granite as needed [note: Okray and Prairie Star willing to assist - culvert(s), equipment (backhoe, etc.)]
- Deer Road (110th – CTH F) – granite @ 1” = \$6,120 – 4” = \$24,862

- Griffith Avenue (110th – CTH F & CTH F – 130th) – excavate soft spots/ditch cuts/sand lift/gravel
- Kellner Road (CTH F – 130th) – granite
- Lake Road (CTH F – Town Line) – granite
- Mill Road (CTH F – Town Line) – take material from ditch bank build/lift road
- Tower Road (CTH F – Town line) = lower priority
- Town Line Road (Buena Vista – Plover Maint.) – excavate soft spots/sand lift/gravel (300 lf)
- Town Line Road (Swamp Road – CTH W) – gravel
- 100th Street (Cranberry Marsh – STH 54) – ~ 1 mile of gravel 1 ¼ inch @ 3” thickness/24’ width = \$27,724
- 110th Street (Griffith – CTH WW) – excavate soft spots/sand lift/gravel (300 lf)
- 130th Street (Buena Vista – Maple) - gravel
- Dust control on select gravel roads