


NEW YORK STATE STANDARD SHEETS

BOOK 3 of 4

SHEETS 608-01 THRU 632-01



**Department of
Transportation**

U.S. CUSTOMARY UNITS
ENGINEERING DIVISION, OFFICE OF DESIGN

MAY 01, 2019

NOTE: INDIVIDUAL STANDARD SHEETS IN THIS BOOK BECOME PART OF A CONTRACT BY REFERENCE TO THE SHEET NUMBER IN THE PROJECT PLANS OR PROPOSAL. THIS ENTIRE SET OF 4 BOOKS IS OFFICIALLY FINALIZED AND ADOPTED AS OF THE DATE SHOWN ON THIS COVER.

| SHEET NO. | SUBJECT | ISSUED BY | EFFECTIVE |
|--------------------|--|------------------|-----------------|
| BOOK 1 of 4 | | | |
| 203-01 | CONSTRUCTION DETAILS UNSUITABLE MATERIAL EXCAVATION AND BACKFILL | EB 08-036 | 01/08/09 |
| 203-02 | EARTHWORK TRANSITION AND BENCHING DETAILS (ERRATA ISSUED BY EB 14-025) | EB 08-036 | 01/08/09 |
| 203-03 | INSTALLATION DETAILS FOR GRANULAR FILL-SLOPE PROTECTION | EB 08-036 | 01/08/09 |
| 203-04 | INSTALLATION DETAILS FOR REINFORCED CONCRETE PIPES | EB 13-038 | 01/09/14 |
| 203-05 | INSTALLATION DETAILS FOR CORRUGATED AND STRUCTURAL PLATE PIPE AND PIPE ARCHES | EB 16-020 | 09/01/16 |
| 204-01 | CONTROLLED LOW STRENGTH MATERIAL (CLSM) INSTALLATION DETAILS FOR CIRCULAR AND ELLIPTICAL CORRUGATED METAL PIPES, STRUCTURAL PLATE PIPES AND PIPE-ARCHES, AND REINFORCED CONCRETE AND OTHER "RIGID" PIPES | EB 08-036 | 01/08/09 |
| 209-01 | LINEAR MEASURES | EB 09-036 | 09/02/10 |
| 209-02 | CHECK DAMS (SHEET 1 OF 2) (ERRATA ISSUED BY EB 13-042) | EB 09-036 | 09/02/10 |
| | CHECK DAMS (SHEET 2 OF 2) | EB 09-036 | 09/02/10 |
| 209-03 | DRAINAGE STRUCTURE INLET PROTECTION (SHEET 1 OF 2) | EB 09-036 | 09/02/10 |
| | DRAINAGE STRUCTURE INLET PROTECTION (SHEET 2 OF 2) | EB 09-036 | 09/02/10 |
| 209-04 | PIPE INLET/OUTLET PROTECTION PIPE SLOPE DRAIN | EB 09-036 | 09/02/10 |
| 209-05 | CONSTRUCTION ENTRANCES | EB 09-036 | 09/02/10 |
| 209-06 | TURBIDITY CURTAIN | EB 09-036 | 09/02/10 |
| 209-07 | SEDIMENT TRAPS | EB 09-036 | 09/02/10 |
| 212-01 | WIRE ROPE ROCK CATCHMENT FENCE (SHEET 1 OF 3) | EB 10-004 | 05/06/10 |
| | WIRE ROPE ROCK CATCHMENT FENCE (SHEET 2 OF 3) | EB 10-004 | 05/06/10 |
| | WIRE ROPE ROCK CATCHMENT FENCE (SHEET 3 OF 3) | EB 10-004 | 05/06/10 |
| 212-02 | CHAIN LINK ROCK CATCHMENT FENCE (SHEET 1 OF 2) | EB 18-020 | 01/01/19 |
| | CHAIN LINK ROCK CATCHMENT FENCE (SHEET 2 OF 2) | EB 18-020 | 01/01/19 |
| 212-03 | WIRE MESH SLOPE PROTECTION (SHEET 1 OF 2) | EB 10-004 | 05/06/10 |
| | WIRE MESH SLOPE PROTECTION (SHEET 2 OF 2) | EB 10-004 | 05/06/10 |
| 212-04 | WIRE MESH DRAPE (ERRATA ISSUED BY EB 13-042) | EB 10-004 | 05/06/10 |
| 212-05 | TEMPORARY ROCK CATCHMENT BARRIER (SHEET 1 OF 2) | EB 10-004 | 05/06/10 |
| | TEMPORARY ROCK CATCHMENT BARRIER (SHEET 2 OF 2) | EB 10-004 | 05/06/10 |
| 402-01 | HOT MIX ASPHALT OVERLAY SPLICE (PAVEMENT TERMINATION DETAIL) | EB 08-036 | 01/08/09 |
| 502-01 | METAL REINFORCEMENT FOR CONCRETE PAVEMENT | EB 18-044 | 05/01/19 |
| 502-02 | TYPICAL PLAN, CROSS SECTION AND JOINT LAYOUT | EB 18-044 | 05/01/19 |
| 502-03 | LONGITUDINAL JOINTS | EB 18-044 | 05/01/19 |
| 502-04 | LONGITUDINAL JOINT TIES | EB 18-044 | 05/01/19 |
| 502-05 | TRANSVERSE JOINTS | EB 18-044 | 05/01/19 |
| 502-06 | JOINT SAWING AND SEALING | EB 18-044 | 05/01/19 |
| 502-07 | UTILITY ISOLATION AND JOINT LAYOUT GENERAL NOTES | EB 18-044 | 05/01/19 |
| 502-08 | UTILITY ISOLATION GUIDELINES | EB 18-044 | 05/01/19 |
| 502-09 | TELESCOPING MANHOLE CASTING LAYOUT | EB 18-044 | 05/01/19 |
| 502-10 | NON-TELESCOPING MANHOLE CASTING LAYOUT | EB 18-044 | 05/01/19 |
| 502-11 | SHALLOW STRUCTURE ISOLATION | EB 18-044 | 05/01/19 |
| 502-12 | DRAINAGE STRUCTURE ISOLATION | EB 18-044 | 05/01/19 |
| 502-13 | DRAINAGE STRUCTURE ISOLATION NEAR MANHOLE CASTINGS | EB 18-044 | 05/01/19 |
| 502-14 | MULTIPLE UTILITIES ISOLATION | EB 18-044 | 05/01/19 |
| 554-01 | PROPRIETARY FILL TYPE RETAINING WALLS - SHEET 1 OF 5 GENERAL NOTES (ERRATA ISSUED BY EB 13-042) | EB 10-041 | 05/05/11 |
| | PROPRIETARY FILL TYPE RETAINING WALLS - SHEET 2 OF 5 GENERAL DETAILS | EB 10-041 | 05/05/11 |
| | PROPRIETARY FILL TYPE RETAINING WALLS - SHEET 3 OF 5 TYP. SECTIONS FOR MECH. STABILIZED EARTH SYSTEMS | EB 10-041 | 05/05/11 |
| | PROPRIETARY FILL TYPE RETAINING WALLS - SHEET 4 OF 5 TYP. SECTIONS FOR MECH. STABILIZED WALL SYSTEMS | EB 10-041 | 05/05/11 |
| | PROPRIETARY FILL TYPE RETAINING WALLS - SHEET 5 OF 5 TYP. SECTIONS FOR PREFABRICATED WALL SYSTEMS | EB 10-041 | 05/05/11 |

| SHEET NO. | SUBJECT | ISSUED BY | EFFECTIVE |
|-----------|---|-----------|-----------|
| 554-02 | GEOSYNTHETICALLY REINFORCED SOIL SYSTEMS SHEET 1 OF 6 - WALLS - GENERAL NOTES AND DETAILS | EB 10-041 | 05/05/11 |
| | GEOSYNTHETICALLY REINFORCED SOIL SYSTEMS SHEET 2 OF 6 - WALLS - TYPICAL SECTIONS | EB 10-041 | 05/05/11 |
| | GEOSYNTHETICALLY REINFORCED SOIL SYSTEMS SHEET 3 OF 6 - SLOPES - GENERAL NOTES AND DETAILS | EB 10-041 | 05/05/11 |
| | GEOSYNTHETICALLY REINFORCED SOIL SYSTEMS SHEET 4 OF 6 - SLOPES - TYPICAL SECTIONS | EB 10-041 | 05/05/11 |
| | GEOSYNTHETICALLY REINFORCED SOIL SYSTEMS SHEET 5 OF 6 - FACING DETAILS | EB 10-041 | 05/05/11 |
| | GEOSYNTHETICALLY REINFORCED SOIL SYSTEMS SHEET 6 OF 6 - FACING DETAILS | EB 10-041 | 05/05/11 |
| 601-01 | PRECAST CONCRETE STREET PAVING LAYOUT DETAILS | EB 12-009 | 09/06/12 |
| 603-01 | REINFORCED CONCRETE PIPE END SECTIONS AND CONCRETE COLLARS | EB 08-036 | 01/08/09 |
| 603-02 | ALUMINUM AND STEEL END SECTIONS FOR CORRUGATED PIPE AND PIPE-ARCH | EB 08-036 | 01/08/09 |
| 603-03 | CATTLE PASS | EB 08-036 | 01/08/09 |
| 603-04 | CUT-OFF WALLS FOR END SECTIONS | EB 11-013 | 01/12/12 |
| 603-05 | CULVERT-END SAFETY GRATE | EB 08-036 | 01/08/09 |
| 604-01 | PRE-CAST CONCRETE TRANSVERSE DRAINAGE INTERCEPTOR (ERRATA ISSUED BY EB 14-025) | EB 08-036 | 01/08/09 |
| 604-02 | DRAINAGE STRUCTURE DETAILS (SHEET 1 OF 4) | EB 12-044 | 05/02/13 |
| | DRAINAGE STRUCTURE DETAILS (SHEET 2 OF 4) | EB 08-036 | 01/08/09 |
| | DRAINAGE STRUCTURE DETAILS (SHEET 3 OF 4) | EB 08-036 | 01/08/09 |
| | DRAINAGE STRUCTURE DETAILS (SHEET 4 OF 4) | EB 08-036 | 01/08/09 |
| 605-01 | POROUS CONCRETE PIPE UNDERDRAIN | EB 08-036 | 01/08/09 |



U.S. CUSTOMARY STANDARD SHEET

**INDEX OF SHEETS EFFECTIVE
05/01/2019
(LATEST CHANGES HIGHLIGHTED)
BOOK 1**

| SHEET NO. | SUBJECT | ISSUED BY | EFFECTIVE |
|--------------------|---|-----------|-----------|
| BOOK 2 of 4 | | | |
| 606-01 | CABLE GUIDE RAIL (SHEET 1 OF 3) (ERRATA ISSUED BY EB 18-003) | EB 12-003 | 09/06/12 |
| | CABLE GUIDE RAILING (SHEET 2 OF 3) | EB 12-003 | 09/06/12 |
| | CABLE GUIDE RAILING (SHEET 3 OF 3) | EB 12-003 | 09/06/12 |
| 606-02 | CABLE MEDIAN BARRIER (SHEET 1 OF 2) (ERRATA ISSUED BY EB 18-003) | EB 12-003 | 09/06/12 |
| | CABLE MEDIAN BARRIER (SHEET 2 OF 2) (ERRATA ISSUED BY EB 18-003) | EB 12-003 | 09/06/12 |
| | CABLE MEDIAN BARRIER (SHEET 3 OF 3) | EB 12-003 | 09/06/12 |
| 606-04 | BOX BEAM GUIDE RAIL (SHEET 1 OF 4) | EB 11-013 | 01/12/12 |
| | BOX BEAM GUIDE RAIL (SHEET 2 OF 4) (ERRATA ISSUED BY EB 14-025 & EB 18-003) | EB 11-013 | 01/12/12 |
| | BOX BEAM GUIDE RAIL (SHEET 3 OF 4) | EB 11-013 | 01/12/12 |
| | BOX BEAM GUIDE RAIL (SHEET 4 OF 4) | EB 10-022 | 01/06/11 |
| 606-05 | BOX BEAM MEDIAN BARRIER | EB 08-036 | 01/08/09 |
| 606-06 | BOX BEAM END ASSEMBLY TYPE III GRADING, PAYMENT, AND LAYOUT DETAILS | EB 09-025 | 01/07/10 |
| 606-07 | WEAK POST CORRUGATED-BEAM GUIDE RAILING SHEET 1 OF 3 (ERRATA ISSUED BY EB 14-025 & EB 18-003) | EB 13-028 | 05/08/14 |
| | WEAK POST CORRUGATED-BEAM GUIDE RAILING SHEET 2 OF 3 (ERRATA ISSUED BY EB 14-025 & EB 18-003) | EB 13-028 | 05/08/14 |
| | WEAK POST CORRUGATED-BEAM GUIDE RAILING SHEET 3 OF 3 (ERRATA ISSUED BY EB 14-025 & EB 18-003) | EB 13-028 | 05/08/14 |
| 606-08 | WEAK POST W-BEAM MEDIAN BARRIER (ERRATA ISSUED BY EB 14-025 & EB 18-003) | EB 11-013 | 01/12/12 |
| 606-09 | HEAVY POST BLOCKED-OUT (MOD.) CORRUGATED-BEAM GUIDE RAILING (SHEET 1 OF 2) (ERRATA ISSUED BY EB 16-008 & EB 18-023) | EB 13-028 | 05/08/14 |
| | HEAVY POST BLOCKED-OUT (MOD.) CORRUGATED-BEAM GUIDE RAILING (SHEET 2 OF 2) (ERRATA ISSUED BY EB 14-025) | EB 13-028 | 05/08/14 |
| 606-10 | HEAVY POST BLOCKED-OUT (MOD.) CORRUGATED-BEAM MEDIAN BARRIER (ERRATA ISSUED BY EB 18-003) | EB 13-028 | 05/08/14 |
| 606-11 | GRADING DETAILS FOR PROPRIETARY HPBO (MOD.) TERMINALS | EB 13-028 | 05/08/14 |
| 606-13 | SINGLE-SLOPE CONCRETE HALF SECTION BARRIER | EB 13-028 | 05/08/14 |
| 606-14 | SINGLE-SLOPE CONCRETE MEDIAN BARRIER AND SINGLE-SLOPE CONCRETE WIDE BARRIER (ERRATA ISSUED BY EB 12-026) | EB 08-036 | 01/08/09 |
| 606-15 | SINGLE-SLOPE CONCRETE BARRIER TERMINAL SECTION - RAMPED TERMINAL (ERRATA ISSUED BY EB 12-026) | EB 08-036 | 01/08/09 |
| 606-19 | TRANSITION: BOX - CABLE | EB 12-003 | 09/06/12 |
| 606-20 | TRANSITION: BOX - W-BEAM (MOD.) (ERRATA ISSUED BY EB 16-008 & EB 18-003) | EB 08-036 | 01/08/09 |
| 606-21 | TRANSITION: BOX - HPBO (MOD.) (ERRATA ISSUED BY EB 18-003) | EB 13-028 | 05/08/14 |
| 606-22 | TRANSITION: BOX - SINGLE SLOPE (SHEET 1 OF 3) (ERRATA ISSUED BY EB 13-042) | EB 08-036 | 01/08/09 |
| | TRANSITION: BOX - SINGLE SLOPE (SHEET 2 OF 3) (ERRATA ISSUED BY EB 14-025 & EB 18-003) | EB 08-036 | 01/08/09 |
| | TRANSITION: BOX - SINGLE SLOPE (SHEET 3 OF 3) | EB 13-028 | 05/08/14 |
| 606-24 | TRANSITION: BOX MEDIAN - WEAK POST AND HPBO (MOD.) MEDIAN (SHEET 1 OF 2) (ERRATA ISSUED BY EB 18-003) | EB 13-028 | 05/08/14 |
| | TRANSITION: BOX MEDIAN - WEAK POST AND HPBO (MOD.) MEDIAN (SHEET 2 OF 2) (ERRATA ISSUED BY EB 14-025 & EB 18-023) | EB 13-028 | 05/08/14 |
| 606-25 | TRANSITION: BOX MEDIAN - SINGLE SLOPE MEDIAN (SHEET 1 OF 3) (ERRATA ISSUED BY EB 13-042) | EB 08-036 | 01/08/09 |
| | TRANSITION: BOX MEDIAN - SINGLE SLOPE MEDIAN (SHEET 2 OF 3) | EB 08-036 | 01/08/09 |
| | TRANSITION: BOX MEDIAN - SINGLE SLOPE MEDIAN (SHEET 3 OF 3) | EB 08-036 | 01/08/09 |
| 606-27 | TRANSITION: WEAK POST - HPBO (MOD.) GUIDE RAIL AND MEDIAN BARRIER (ERRATA ISSUED BY EB 18-023) | EB 13-028 | 05/08/14 |

| SHEET NO. | SUBJECT | ISSUED BY | EFFECTIVE |
|-----------|--|-----------|-----------|
| 606-28 | TRANSITION: HPBO (MOD.) - SINGLE SLOPE HALF SECTION (SHEET 1 OF 3) | EB 13-028 | 05/08/14 |
| | TRANSITION: HPBO (MOD.) - SINGLE SLOPE HALF SECTION (SHEET 2 OF 3) | EB 13-028 | 05/08/14 |
| | TRANSITION: HPBO (MOD.) - SINGLE SLOPE HALF SECTION (SHEET 3 OF 3) | EB 13-028 | 05/08/14 |
| 606-29 | TRANSITION: HPBO (MOD.) MEDIAN - SINGLE SLOPE MEDIAN (SHEET 1 OF 3) (ERRATA ISSUED BY EB 14-025 & EB 18-023) | EB 13-028 | 05/08/14 |
| | TRANSITION: HPBO (MOD.) MEDIAN - SINGLE SLOPE MEDIAN (SHEET 2 OF 3) (ERRATA ISSUED BY EB 18-023) | EB 13-028 | 05/08/14 |
| | TRANSITION: HPBO (MOD.) MEDIAN - SINGLE SLOPE MEDIAN (SHEET 3 OF 3) | EB 13-028 | 05/08/14 |
| 606-31 | TRANSITION: WIDE - NORMAL WIDTH SINGLE SLOPE MEDIAN (ERRATA ISSUED BY EB 12-026) | EB 08-036 | 01/08/09 |
| 606-32 | TRANSITION: HALF-SECTION TO FULL-SECTION SINGLE SLOPE CONCRETE BARRIER | EB 13-049 | 05/08/14 |
| 606-33 | W-BEAM GUIDE RAILING (SHEET 1 OF 2) (MAINTENANCE SUPPORT) | EB 08-036 | 01/08/09 |
| | W-BEAM GUIDE RAILING (SHEET 2 OF 2) (MAINTENANCE SUPPORT) (ERRATA ISSUED BY EB 18-023) | EB 08-036 | 01/08/09 |
| 606-35 | CONCRETE BARRIER (CAST-IN-PLACE) (MAINTENANCE SUPPORT) | EB 08-036 | 01/08/09 |
| 606-36 | PRECAST CONCRETE BARRIER | EB 11-013 | 01/12/12 |
| 606-37 | MACHINE FORMED CONCRETE BARRIER | EB 08-036 | 01/08/09 |
| 606-38 | TRANSITION: BOX BEAM - W-BEAM (MAINTENANCE SUPPORT) | EB 08-036 | 01/08/09 |
| 606-40 | TRANSITION: HPBO - JERSEY SHAPE (MAINTENANCE SUPPORT) | EB 08-036 | 01/08/09 |
| 606-41 | TRANSITION: CONCRETE WALL - JERSEY MEDIAN (MAINTENANCE SUPPORT) | EB 08-036 | 01/08/09 |
| 606-42 | TRANSITION: CONCRETE BARRIER BETWEEN STANDARD (NJ) AND SINGLE SLOPE CONCRETE SHAPES | EB 08-036 | 01/08/09 |
| 606-43 | HPBO GUIDE RAILING AND TRANSITIONS (8 SHEETS) (MAINTENANCE SUPPORT) (ERRATA ISSUED BY EB 18-023) | EB 13-028 | 05/08/14 |
| 606-44 | HPBO MEDIAN BARRIER AND TRANSITIONS (5 SHEETS) (MAINTENANCE SUPPORT) (ERRATA ISSUED BY EB 18-023) | EB 13-028 | 05/08/14 |
| 607-01 | R.O.W. FENCING | EB 08-036 | 01/08/09 |
| 607-04 | CHAIN LINK FENCE WITH TOP RAIL (ERRATA ISSUED BY EB 13-042) | EB 08-036 | 01/08/09 |
| 607-05 | CHAIN LINK FENCE WITH TOP TENSION WIRE (ERRATA ISSUED BY EB 13-042) | EB 08-036 | 01/08/09 |
| 607-06 | GATES AND CHAIN LINK FENCE ADJACENT TO GATES | EB 08-036 | 01/08/09 |



U.S. CUSTOMARY STANDARD SHEET

INDEX OF SHEETS EFFECTIVE
05/01/2019
(LATEST CHANGES HIGHLIGHTED)
BOOK 2

| SHEET NO. | SUBJECT | ISSUED BY | EFFECTIVE |
|--------------------|---|-----------|-----------|
| BOOK 3 of 4 | | | |
| 608-01 | SIDEWALK CURB RAMP DETAILS (SHEET 1 OF 9) | EB 16-012 | 05/01/16 |
| | SIDEWALK CURB RAMP DETAILS (SHEET 2 OF 9) | EB 17-042 | 10/05/17 |
| | SIDEWALK CURB RAMP DETAILS (SHEET 3 OF 9) | EB 16-012 | 05/01/16 |
| | SIDEWALK CURB RAMP DETAILS (SHEET 4 OF 9) | EB 16-012 | 05/01/16 |
| | SIDEWALK CURB RAMP DETAILS (SHEET 5 OF 9) | EB 16-012 | 05/01/16 |
| | SIDEWALK CURB RAMP DETAILS (SHEET 6 OF 9) | EB 16-012 | 05/01/16 |
| | SIDEWALK CURB RAMP DETAILS (SHEET 7 OF 9) | EB 16-012 | 05/01/16 |
| | SIDEWALK CURB RAMP DETAILS (SHEET 8 OF 9) | EB 16-012 | 05/01/16 |
| 608-02 | ACCESSIBLE PARKING FOR PERSONS WITH DISABILITIES DETAILS | EB 16-012 | 05/01/16 |
| 608-03 | RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 1 OF 9) | EB 16-012 | 05/01/16 |
| | RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 2 OF 9) | EB 16-012 | 05/01/16 |
| | RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 3 OF 9) | EB 16-012 | 05/01/16 |
| | RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 4 OF 9) | EB 16-012 | 05/01/16 |
| | RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 5 OF 9) | EB 16-012 | 05/01/16 |
| | RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 6 OF 9) | EB 16-012 | 05/01/16 |
| | RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 7 OF 9) | EB 16-012 | 05/01/16 |
| | RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 8 OF 9) | EB 16-012 | 05/01/16 |
| | RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 9 OF 9) | EB 16-012 | 05/01/16 |
| 608-07 | RAISED CROSSWALK DETAILS (SHEET 1 OF 3) | EB 16-012 | 05/01/16 |
| | RAISED CROSSWALK DETAILS (SHEET 2 OF 3) | EB 16-012 | 05/01/16 |
| | RAISED CROSSWALK DETAILS (SHEET 3 OF 3) | EB 16-012 | 05/01/16 |
| 609-01 | STONE CURB AND GRANITE CURB | EB 16-019 | 09/01/16 |
| 609-02 | MISCELLANEOUS CURB DETAILS | EB 13-007 | 01/09/14 |
| 609-03 | CONCRETE CURB, CURB AND GUTTER, AND HOT MIX ASPHALT CURB | EB 08-036 | 01/08/09 |
| 609-04 | GRANITE SLOPED CURB DETAILS, TYPE S | EB 13-007 | 01/09/14 |
| 611-01 | LANDSCAPE PLANTING DETAILS (SHEET 1 OF 2) (ERRATA ISSUED BY EB 13-042) | EB 12-011 | 09/06/12 |
| | LANDSCAPE PLANTING DETAILS (SHEET 2 OF 2) | EB 12-011 | 09/06/12 |
| 619-01 | TEMPORARY CONCRETE BARRIER (SHEET 1 OF 5) (ERRATA ISSUED BY EB 14-025) | EB 09-025 | 01/07/10 |
| | TEMPORARY CONCRETE BARRIER (SHEET 2 OF 5) (ERRATA ISSUED BY EB 18-023) | EB 09-025 | 01/07/10 |
| | TEMPORARY CONCRETE BARRIER (SHEET 3 OF 5) (ERRATA ISSUED BY EB 13-042) | EB 10-034 | 01/06/11 |
| | TEMPORARY CONCRETE BARRIER (SHEET 4 OF 5) | EB 17-005 | 09/01/17 |
| | TEMPORARY CONCRETE BARRIER (SHEET 5 OF 5) | EB 17-005 | 09/01/17 |
| 619-02 | TYPE III CONSTRUCTION BARRICADES (SHEET 1 OF 2) | EB 08-036 | 01/08/09 |
| | TYPE III CONSTRUCTION BARRICADES (SHEET 2 OF 2) | EB 08-036 | 01/08/09 |
| 619-04 | PORTABLE TEMPORARY WOODEN SIGN SUPPORT | EB 08-036 | 01/08/09 |
| 619-10 | WORK ZONE TRAFFIC CONTROL GENERAL NOTES | EB 08-036 | 01/08/09 |
| 619-11 | WORK ZONE TRAFFIC CONTROL LEGENDS AND NOTES | EB 08-036 | 01/08/09 |
| 619-12 | SIGN TABLE (SHEET 1 OF 2) | EB 12-010 | 05/03/12 |
| | SIGN TABLE (SHEET 2 OF 2) | EB 12-010 | 05/03/12 |
| 619-20 | SHOULDER CLOSURE 2-LANE 2-WAY ROADWAY | EB 09-025 | 01/07/10 |
| 619-21 | SHOULDER CLOSURE 2-LANE 2-WAY ROADWAY MULTIPLE WORK LOCATIONS | EB 09-025 | 01/07/10 |
| 619-22 | SHOULDER CLOSURE EXPRESSWAY / FREEWAY | EB 08-036 | 01/08/09 |
| 619-23 | SHOULDER CLOSURE EXPRESSWAY / FREEWAY RAMP APPROACH | EB 08-036 | 01/08/09 |

| SHEET NO. | SUBJECT | ISSUED BY | EFFECTIVE |
|-----------|--|-----------|-----------|
| 619-24 | PARTIAL EXIT RAMP CLOSURE EXPRESSWAY / FREEWAY | EB 09-025 | 01/07/10 |
| 619-30 | SINGLE LANE CLOSURE MULTI LANE HIGHWAY | EB 08-036 | 01/08/09 |
| 619-31 | SINGLE LANE CLOSURE MULTI LANE DIVIDED HIGHWAY | EB 08-036 | 01/08/09 |
| 619-32 | SINGLE LANE CLOSURE MULTI LANE HIGHWAY / EXPRESSWAY / FREEWAY | EB 08-036 | 01/08/09 |
| 619-33 | SINGLE LANE CLOSURE NEAR ENTRANCE RAMP EXPRESSWAY / FREEWAY | EB 09-025 | 01/07/10 |
| 619-34 | SINGLE LANE CLOSURE NEAR EXIT RAMP EXPRESSWAY / FREEWAY | EB 09-025 | 01/07/10 |
| 619-40 | DOUBLE LANE CLOSURE EXPRESSWAY / FREEWAY | EB 08-036 | 01/08/09 |
| 619-41 | DOUBLE INTERIOR LANE CLOSURE MULTI LANE HIGHWAY | EB 08-036 | 01/08/09 |
| 619-50 | SIDEWALK DETOUR OR DIVERSION | EB 09-025 | 01/07/10 |
| 619-51 | CROSSWALK CLOSURE AND PEDESTRIAN DETOUR | EB 08-036 | 01/08/09 |
| 619-60 | FLAGGING OPERATION 2-LANE 2-WAY ROADWAY | EB 09-025 | 01/07/10 |
| 619-61 | FLAGGING OPERATION 2-LANE 2-WAY ROADWAY INTERSECTION | EB 08-036 | 01/08/09 |
| 619-62 | TEMPORARY TRAFFIC SIGNAL 2-LANE 2-WAY ROADWAY | EB 08-036 | 01/08/09 |
| 619-63 | SINGLE LANE SHIFT 2-LANE 2-WAY ROADWAY WITH CENTER TURN LANE | EB 08-036 | 01/08/09 |
| 619-64 | CENTER TURN LANE CLOSURE 2-LANE 2-WAY ROADWAY WITH CENTER TURN LANE | EB 08-036 | 01/08/09 |
| 619-65 | MULTI LANE SHIFT EXPRESSWAY / FREEWAY | EB 08-036 | 01/08/09 |
| 619-66 | ROAD CLOSURE WITH OFF SITE DETOUR 2-LANE 2-WAY ROADWAY | EB 08-036 | 01/08/09 |
| 624-01 | CONCRETE GUTTER (ERRATA ISSUED BY EB 17-041) | EB 11-013 | 01/12/12 |
| 625-01 | R.O.W. AND SURVEY MARKERS | EB 17-047 | 05/01/18 |
| 630-01 | HIGHWAY BARRIER AND HIGHWAY-RAILROAD BARRICADE | EB 08-036 | 01/08/09 |
| 632-01 | PRECAST MODULAR WALLS (SHEET 1 OF 2) | EB 08-036 | 01/08/09 |
| | PRECAST MODULAR WALLS (SHEET 2 OF 2) | EB 08-036 | 01/08/09 |



U.S. CUSTOMARY STANDARD SHEET

INDEX OF SHEETS EFFECTIVE
05/01/2019
(LATEST CHANGES HIGHLIGHTED)
BOOK 3
(THIS BOOK)

| SHEET NO. | SUBJECT | ISSUED BY | EFFECTIVE |
|-----------|---|-----------|-----------|
| | BOOK 4 of 4 | | |
| 645-01 | STANDARD SIGN BLANK DETAILS (SHEET 1 OF 2) ERRATA ISSUED BY EB 18-003 | EB 09-025 | 01/07/10 |
| | STANDARD SIGN BLANK DETAILS (SHEET 2 OF 2) ERRATA ISSUED BY EB 18-003 | EB 09-025 | 01/07/10 |
| 645-02 | ROUTE MARKER ASSEMBLIES | EB 09-025 | 01/07/10 |
| 645-03 | POSITIONING OF TRAFFIC SIGNS (SHEET 1 OF 2) | EB 09-025 | 01/07/10 |
| | POSITIONING OF TRAFFIC SIGNS (SHEET 2 OF 2) | EB 09-025 | 01/07/10 |
| 645-05 | TOURIST, BUSINESS, AND RAMP SERVICE SIGNS (SHEET 1 OF 2) | EB 09-025 | 01/07/10 |
| | TOURIST, BUSINESS, AND RAMP SERVICE SIGNS (SHEET 2 OF 2) | EB 09-025 | 01/07/10 |
| 645-06 | TOURIST ORIENTED BUSINESS SIGNS (SHEET 1 OF 2) | EB 09-025 | 01/07/10 |
| | TOURIST ORIENTED BUSINESS SIGNS (SHEET 2 OF 2) | EB 09-025 | 01/07/10 |
| 645-07 | SPECIFIC SERVICES SIGNS (SHEET 1 OF 2) (ERRATA ISSUED BY EB 12-026) | EB 09-025 | 01/07/10 |
| | SPECIFIC SERVICES SIGNS (SHEET 2 OF 2) | EB 08-036 | 01/08/09 |
| 645-09 | SIGN PANEL DETAILS FOR GUIDE, INFORMATION, AND OTHER SIGNS (ERRATA ISSUED BY EB 13-042 & 18-023) | EB 12-040 | 05/02/13 |
| 645-10 | MULTIPLE POST SIGN INSTALLATION USING TYPE B SIGN POSTS (ERRATA ISSUED BY EB 12-026) | EB 09-025 | 01/07/10 |
| 645-11 | BI-DIRECTIONAL BREAKAWAY BASE AND HINGE ASSEMBLY | EB 09-025 | 01/07/10 |
| 645-12 | OMNI-DIRECTIONAL BREAKAWAY BASE AND HINGE ASSEMBLY | EB 09-025 | 01/07/10 |
| 645-14 | POLE MOUNTED SIGNS (ERRATA ISSUED BY EB 14-025) | EB 08-045 | 05/07/09 |
| 646-11 | REFERENCE MARKER DETAILS (ERRATA ISSUED BY EB 14-025) | EB 11-006 | 09/01/11 |
| 646-12 | DELINEATOR MOUNTING ON CONCRETE MEDIAN BARRIER DETAILS | EB 10-020 | 01/06/11 |
| 646-13 | STANDARD AND LARGE DELINEATOR PANEL DETAILS | EB 10-020 | 01/06/11 |
| 646-14 | STANDARD DELINEATOR BRACKET AND FASTENER DETAILS | EB 10-020 | 01/06/11 |
| 646-15 | DELINEATOR SNOWPLOWING MARKER AND SUPPLEMENTARY SNOWPLOWING MARKER DETAILS AND NOTES | EB 11-006 | 09/01/11 |
| 646-16 | REFERENCE MARKER LARGE DELINEATOR SNOWPLOWING AND SUPPLEMENTARY SNOWPLOWING MARKER LAYOUT ON FREEWAYS AND EXPRESSWAYS | EB 10-020 | 01/06/11 |
| 649-02 | MILLED-INAUDIBLE ROADWAY DELINEATORS | EB 13-040 | 01/09/14 |
| 649-03 | CENTERLINE AUDIBLE ROADWAY DELINEATORS | EB 13-040 | 01/09/14 |
| 649-04 | SECONDARY HIGHWAY AUDIBLE ROADWAY DELINEATORS | EB 16-030 | 01/01/17 |
| 655-01 | RECTANGULAR GRATES | EB 08-036 | 01/08/09 |
| 655-02 | PARALLEL BAR FRAMES AND GRATES (ERRATA ISSUED BY EB 14-025) | EB 08-049 | 05/07/09 |
| 655-03 | CAST MANHOLE FRAMES, GRATES AND COVERS | EB 08-049 | 05/07/09 |
| 655-04 | RETICULINE GRATES (ERRATA ISSUED BY EB 16-008 & EB 18-003) | EB 12-031 | 01/10/13 |
| 655-05 | CAST FRAMES AND CURB BOXES AND WELDED FRAMES (ERRATA ISSUED BY EB 13-042 & EB 18-023) | EB 09-025 | 01/07/10 |
| 655-06 | PROOF LOADED CAST STEEL OR IRON MANHOLE FRAMES, GRATES AND COVERS (ERRATA ISSUED BY EB 14-025) | EB 08-036 | 01/08/09 |
| 655-07 | WELDED FRAMES AND PROOF LOADED CAST STEEL OR IRON FRAMES AND CURB BOXES (ERRATA ISSUED BY EB 16-008 & 18-023) | EB 08-049 | 05/07/09 |
| 655-08 | TELESCOPING MANHOLE CASTING AND RING | EB 08-036 | 01/08/09 |
| 663-01 | WATER MAIN PIPE INSTALLATION DETAILS (ERRATA ISSUED BY EB 18-003) | EB 13-038 | 01/09/14 |
| 663-02 | WATER MAIN HORIZONTAL THRUST RESTRAINT DETAILS | EB 11-025 | 05/03/12 |
| 663-03 | WATER MAIN THRUST RESTRAINT DETAILS | EB 11-025 | 05/03/12 |
| 663-04 | WATER MAIN UTILITY CROSSING RELOCATION DETAILS | EB 08-036 | 01/08/09 |
| 663-05 | WATER MAIN HYDRANT AND VALVE DETAILS | EB 08-036 | 01/08/09 |
| 663-06 | WATER MAIN HYDRANT FENDER DETAILS | EB 08-036 | 01/08/09 |
| 663-07 | WATER MAIN SERVICE CONNECTION DETAILS | EB 08-036 | 01/08/09 |
| 664-01 | SANITARY SEWER MAIN PIPE INSTALLATION DETAILS (ERRATA ISSUED BY EB 18-003) | EB 13-038 | 01/09/14 |
| 670-01 | LAMPPOST FOUNDATIONS | EB 08-036 | 01/08/09 |
| 670-02 | LIGHT STANDARD DETAILS | EB 08-036 | 01/08/09 |
| 670-03 | DAVIT ARM, WOOD POLE BRACKET ARM AND DEEP FOUNDATIONS (ERRATA ISSUED BY EB 12-026) | EB 08-036 | 01/08/09 |

| SHEET NO. | SUBJECT | ISSUED BY | EFFECTIVE |
|-----------|---|-----------|-----------|
| 680-01 | TRAFFIC SIGNAL POLE FOUNDATIONS | EB 17-027 | 01/01/18 |
| 680-02 | PRECAST STANDARD RECTANGULAR PULLBOXES, FRAMES AND COVERS | EB 11-013 | 01/12/12 |
| 680-03 | STANDARD CIRCULAR PULLBOXES, FRAMES AND COVERS | EB 11-013 | 01/12/12 |
| 680-04 | PULLBOX, CONDUIT AND GROUND ROD INSTALLATION DETAILS | EB 18-041 | 01/01/18 |
| 680-05 | BASE - AND POLE - MOUNTED CABINET INSTALLATION DETAILS | EB 18-041 | 01/01/18 |
| 680-06 | STANDARD TRAFFIC SIGNAL POLES (SHEET 1 OF 2) | EB 08-036 | 01/08/09 |
| | STANDARD TRAFFIC SIGNAL POLES (SHEET 2 OF 2) | EB 08-036 | 01/08/09 |
| 680-07 | SPAN WIRE MOUNTED TRAFFIC SIGNAL INSTALLATION DETAILS | EB 13-045 | 05/08/14 |
| 680-08 | MAST ARM AND POLE MOUNTED TRAFFIC SIGNAL INSTALLATION DETAILS | EB 18-041 | 01/01/18 |
| 680-10 | PEDESTRIAN SIGNALS AND FLASHING BEACON INSTALLATION DETAILS | EB 08-036 | 01/08/09 |
| 680-11 | SIGNAL HEAD ASSEMBLY DETAILS | EB 13-045 | 05/08/14 |
| 680-12 | SINGLE SPAN WIRE MOUNTED SIGN INSTALLATION DETAILS | EB 18-041 | 01/01/18 |
| 680-13 | DUAL SPAN WIRE AND MAST ARM SIGN INSTALLATION DETAILS | EB 18-041 | 01/01/18 |
| 680-14 | INDUCTANCE LOOP VEHICLE DETECTOR INSTALLATION DETAILS | EB 18-041 | 01/01/18 |
| 680-15 | MAGNETIC VEHICLE DETECTOR INSTALLATION DETAILS (DISAPPROVED) | EB 18-041 | 01/01/18 |
| 680-16 | WOOD POLE DETAILS | EB 18-041 | 01/01/18 |
| 680-17 | UTILITY CLEARANCES TOO TRAFFIC SIGNALS | EB 18-041 | 01/01/18 |
| 685-01 | PAVEMENT MARKING DETAILS (SHEET 1 OF 9) | EI 18-008 | 01/01/19 |
| | PAVEMENT MARKING DETAILS (SHEET 2 OF 9) | EB 12-036 | 05/03/13 |
| | PAVEMENT MARKING DETAILS (SHEET 3 OF 9) | EB 12-036 | 05/03/13 |
| | PAVEMENT MARKING DETAILS (SHEET 4 OF 9) | EB 12-036 | 05/03/13 |
| | PAVEMENT MARKING DETAILS (SHEET 5 OF 9) | EB 12-036 | 05/03/13 |
| | PAVEMENT MARKING DETAILS (SHEET 6 OF 9) (ERRATA ISSUED BY EB 13-042) | EB 12-036 | 05/03/13 |
| | PAVEMENT MARKING DETAILS (SHEET 7 OF 9) (ERRATA ISSUED BY EB 17-041) | EB 12-036 | 05/03/13 |
| | PAVEMENT MARKING DETAILS (SHEET 8 OF 9) (ERRATA ISSUED BY EB 17-041) | EB 12-036 | 05/03/13 |
| | PAVEMENT MARKING DETAILS (SHEET 9 OF 9) (ERRATA ISSUED BY EB 13-041) | EB 12-036 | 05/03/13 |



**Department of
Transportation**

U.S. CUSTOMARY STANDARD SHEET

INDEX OF SHEETS EFFECTIVE
05/01/2019
(LATEST CHANGES HIGHLIGHTED)
BOOK 4

GENERAL NOTES:

1. THESE SHEETS ARE IN ACCORDANCE WITH THE AMERICANS WITH DISABILITIES ACT (ADA), AND THE REQUIREMENTS OF THE 2011 PROPOSED ACCESSIBILITY GUIDELINES FOR PEDESTRIAN FACILITIES IN THE PUBLIC RIGHT OF WAY (PROWAG).
2. DIMENSIONS SHOWN IN THE DETAILS AS MINIMUMS AND MAXIMUMS ARE THE LIMITS FOR DESIGN AND FIELD LAYOUT. FACILITIES SHALL NOT BE CONSTRUCTED WITH VALUES OUTSIDE THE LIMITS FOR WORK ACCEPTANCE. SEE TABLE "DESIGN ELEMENT TOLERANCES" ON THIS SHEET. FURTHER INFORMATION IS PROVIDED ON "CRITICAL ELEMENTS FOR THE DESIGN, LAYOUT, AND ACCEPTANCE OF PEDESTRIAN FACILITIES" AVAILABLE ON THE NYS DOT HIGHWAY DESIGN MANUAL CHAPTER 18 WEBSITE.
3. NOT ALL FACILITIES CAN BE CONSTRUCTED TO MEET THE DESIGN STANDARDS. FACILITIES THAT CANNOT BE CONSTRUCTED TO MEET THE DESIGN STANDARDS SHALL BE CONSTRUCTED TO MEET THE STANDARDS TO THE GREATEST EXTENT PRACTICABLE. NONSTANDARD FEATURES SHALL BE JUSTIFIED PER HIGHWAY DESIGN MANUAL CHAPTER 2, EXHIBIT 2-15A.
4. TO CHECK FIELD LAYOUT AND TO VERIFY WORK ACCEPTANCE, ALL SLOPES AND GRADES WILL BE MEASURED WITH A 4 FOOT LONG DIGITAL LEVEL USING AT LEAST TWO READINGS. WHERE THE READINGS VARY, THE MEASUREMENTS WILL BE AVERAGED. GRADE (RUNNING SLOPE) WILL BE MEASURED ALONG THE CENTERLINE AND OFFSET 12" TO 18" FROM THE CENTERLINE. CROSS SLOPES WILL BE MEASURED PERPENDICULAR TO CENTERLINE AT 5' TO 10' INTERVALS.
5. GRADES (RUNNING SLOPES) ARE MEASURED IN THE DIRECTION OF PEDESTRIAN TRAVEL. CROSS SLOPES ARE MEASURED PERPENDICULAR TO THE DIRECTION OF PEDESTRIAN TRAVEL.
6. JOINTS BETWEEN SIDEWALKS, CURB RAMPS, TURNING SPACES AND ROADWAYS SHALL BE FLUSH AND FREE FROM ABRUPT VERTICAL CHANGES GREATER THAN 1/4". VERTICAL SURFACE DISCONTINUITIES BETWEEN 1/4" AND 1/2" SHALL BE BEVELED WITH A SLOPE NOT STEEPER THAN 1:2. THE BEVEL SHALL BE APPLIED ACROSS THE ENTIRE JOINT. SEE DETAIL ON SHEET 2 OF 9.
7. SIDEWALKS ARE CONNECTED TO ROADWAYS BY EITHER BLENDED TRANSITIONS OR CURB RAMPS. BLENDED TRANSITIONS ARE CONNECTIONS BETWEEN THE SIDEWALK LEVEL AND THE ROADWAY LEVEL THAT HAVE A MAXIMUM GRADE (RUNNING SLOPE) OF 5%, AND TRANSITIONS GREATER THAN 5% ARE CONSIDERED CURB RAMPS.
8. CURB RAMPS AND BLENDED TRANSITIONS MAY REQUIRE THE INSTALLATION OF DETECTABLE WARNINGS. SEE ADDITIONAL "DETECTABLE WARNING NOTES" ON THIS SHEET, AND DETAILS ON SHEET 2 OF 9 FOR DIMENSIONS, ORIENTATION AND INSTALLATION.
9. VERTICAL ALIGNMENT SHALL BE GENERALLY PLANAR. GRADE BREAKS WITHIN THE PEDESTRIAN ACCESS ROUTE SHALL BE PERPENDICULAR TO THE DIRECTION OF TRAVEL AND SHALL NOT BE ROUNDED.
10. MATERIAL DEPTHS SHOWN ON THESE SHEETS ARE TYPICAL MINIMUM VALUES AND MAY BE DIFFERENT IN THE CONTRACT DOCUMENTS.
11. SIDEWALK GRADE (RUNNING SLOPE) SHALL NOT BE DESIGNED TO EXCEED 4.5%, EXCEPT WHEN MATCHING INTO EXISTING SIDEWALK OR WHEN THE HIGHWAY GRADE IS STEEPER. WHEN HIGHWAY GRADE IS GREATER THAN 5%, THE SIDEWALK GRADE SHALL NOT EXCEED THE HIGHWAY GRADE.
12. THE CROSS SLOPE OF PEDESTRIAN ACCESS ROUTES SHALL BE 1.5% MAXIMUM FOR DESIGN AND LAYOUT, AND 2% MAXIMUM FOR WORK ACCEPTANCE. THE FOLLOWING EXCEPTIONS ARE ALLOWED:
 - A. WHERE PEDESTRIAN STREET CROSSINGS ARE PROVIDED AT INTERSECTIONS WITHOUT YIELD OR STOP CONTROL OR WHERE THERE IS ANY TRAFFIC SIGNAL WITHOUT A FLASHING RED, THE CROSS SLOPE OF A PEDESTRIAN ACCESS ROUTE CONTAINED WITHIN A STREET CROSSING SHALL BE 4.5% MAXIMUM FOR DESIGN AND LAYOUT, AND 5% MAXIMUM FOR WORK ACCEPTANCE.
 - B. WHERE MIDBLOCK PEDESTRIAN STREET CROSSINGS ARE PROVIDED, THE CROSS SLOPE OF A PEDESTRIAN ACCESS ROUTE CONTAINED WITHIN A MIDBLOCK STREET CROSSING SHALL BE PERMITTED TO EQUAL THE STREET OR HIGHWAY GRADE.
13. THE MINIMUM CLEAR WIDTH FOR PEDESTRIAN ACCESS ROUTES IS 4'-0", EXCLUSIVE OF THE CURB. WHEN WALKWAY WIDTHS ARE LESS THAN 5'-0", 5'-0" x 5'-0" PASSING SPACES (SHOWN IN DETAIL A OR B), OR A FEATURE OF EQUAL OR GREATER DIMENSIONS (E.G., DRIVEWAYS) THAT MEET THE SLOPE CRITERIA, SHALL BE PROVIDED AT A MAXIMUM INTERVAL OF 200'. EXISTING DRIVEWAYS AND STREET CROSSING MAY ALSO SERVE AS PASSING SPACES.
14. THE BUFFER ZONE IS A PHYSICAL DISTANCE SEPARATING THE PEDESTRIAN ACCESS ROUTE FROM THE VEHICLE TRAVELED WAY. THE BUFFER ZONE MAY BE PLANTED OR PAVED. WHERE THE BUFFER ZONE WIDTH, EXCLUSIVE OF CURB, IS LESS THAN 3'-0" THE SURFACE SHOULD BE PAVED OR CONSTRUCTED WITH HARDSCAPE MATERIALS.
15. THE MAXIMUM RECOMMENDED CROSS SLOPE OF A TURF BUFFER ZONE OR SLOPE TRANSITION BEHIND SIDEWALK IS 25%. BUFFER ZONES WITH A CROSS SLOPE GREATER THAN 25% SHOULD BE PAVED, PLANTED OR CONSTRUCTED WITH HARDSCAPE MATERIALS.
16. WHEN CROSSING DRIVEWAYS, THE WORK SHALL BE IN CONFORMANCE WITH STANDARD SHEET 608-03.
17. FOR PEDESTRIAN SIGNALS AND PEDESTRIAN PUSH BUTTONS, REFER TO STANDARD SHEET 680-10 FOR DETAILS.
18. WHERE EXISTING ROADWAYS ARE SAWCUT TO INSTALL CURBING AND/OR SIDEWALK, THE ROADWAY SHOULD BE SAWCUT AT LEAST 2'-0" FROM THE PROPOSED CURB LINE TO ALLOW FOR ADEQUATE COMPACTION OF ASPHALT. IF SAWCUT IS LESS THAN 2'-0" FROM PROPOSED CURB LINE, THEN THE ROADWAY SHALL BE REBUILT USING CLASS C CONCRETE. SEE DETAILS ON SHEET 9 OF 9.

CURB RAMP NOTES:


19. THE MINIMUM WIDTH OF A CURB RAMP SHALL BE 4'-0".
20. THE GRADE (RUNNING SLOPE) OF A CURB RAMP SHALL BE A MINIMUM OF 5%. THE GRADE FOR DESIGN AND LAYOUT SHALL BE A MAXIMUM OF 7.5%. THE GRADE FOR ADA ACCESSIBILITY AND WORK ACCEPTANCE SHALL BE A MAXIMUM OF 8.3%.
21. WHERE EXISTING CONDITIONS DO NOT ALLOW THE CONSTRUCTION OF A CURB RAMP WITH A GRADE (RUNNING SLOPE) OF 8.3% OR LESS, THE RAMP LENGTH SHALL NOT BE REQUIRED TO EXCEED 15'-1" FOR DESIGN AND FIELD LAYOUT. THE RAMP LENGTH SHALL NOT BE REQUIRED TO EXCEED 15'-0" FOR WORK ACCEPTANCE.
22. THE CROSS SLOPE OF THE CURB RAMP SHALL BE AS FLAT AS POSSIBLE AND STILL PROVIDE POSITIVE DRAINAGE. THE CROSS SLOPE OF A CURB RAMP SHALL BE 1.5% MAXIMUM FOR DESIGN AND LAYOUT, AND 2% MAXIMUM FOR WORK ACCEPTANCE. SEE NOTE 12 FOR EXCEPTIONS. WHERE THE EXISTING ROADWAY GRADE EXCEEDS 2%, THE CURB RAMP MAY BE WARPED ACCORDING TO THE DETAIL ON SHEET 8 OF 9 TO TIE INTO THE DROP CURB.
23. RAMP SIDE OPTIONS ARE DETAILED ON SHEET 3 OF 9 FOR USE WITHIN THE BUFFER ZONE. WHERE A PEDESTRIAN CIRCULATION PATH CROSSES THE CURB RAMP, FLARED SIDES SHALL BE INSTALLED WITH A MAXIMUM SLOPE OF 9.5% FOR DESIGN AND LAYOUT, AND 10% MAXIMUM FOR WORK ACCEPTANCE. THE SLOPE OF FLARED SIDES IS MEASURED PARALLEL TO THE CURB LINE.
24. THE BACKSIDE OF A PARALLEL RAMP SHOULD BE GRADED TO A MAXIMUM SLOPE OF 25% TO MATCH EXISTING TERRAIN, UNLESS OTHERWISE SHOWN IN THE CONTRACT DOCUMENTS. WHERE GRADING IS NOT FEASIBLE DUE TO LIMITED ROW OR PHYSICAL CONSTRAINTS, A BACK CURB MAY BE INSTALLED. SEE DETAILS ON SHEET 3 OF 9 AND SHEET 9 OF 9.
25. DEPARTMENT PREFERENCE IS TO INSTALL TWO CURB RAMPS AT A STREET CORNER THAT SERVES BOTH CROSSINGS. WHERE EXISTING PHYSICAL CONSTRAINTS PREVENT TWO CURB RAMPS FROM BEING INSTALLED AT A STREET CORNER THAT SERVES BOTH CROSSINGS, A SINGLE DIAGONAL CURB RAMP WILL BE PERMITTED TO SERVE BOTH PEDESTRIAN STREET CROSSINGS.

TURNING SPACE AND CLEAR SPACE NOTES:


26. WHERE A CHANGE IN DIRECTION IS REQUIRED TO UTILIZE A CURB RAMP, A TURNING SPACE SHALL BE PROVIDED AT THE BASE OR THE TOP OF CURB RAMP AS APPLICABLE. TURNING SPACES SHALL BE PERMITTED TO OVERLAP CLEAR SPACES.
27. WHERE THERE ARE NO VERTICAL CONSTRAINTS AT THE BACK OF SIDEWALK, (E.G., VERTICAL CURB, BUILDINGS, FENCES) THE TURNING SPACE DIMENSIONS SHALL BE 4'-0" x 4'-0" MINIMUM. WHERE THE TURNING SPACE IS CONSTRAINED AT THE BACK OF SIDEWALK, THE TURNING SPACE SHALL BE 4'-0" x 5'-0" MINIMUM. THE 5'-0" DIMENSION SHALL BE PROVIDED PERPENDICULAR TO THE CONSTRAINT.
28. TURNING SPACES SHALL NOT BE DESIGNED WITH CROSS SLOPE GREATER THAN 1.5% IN ANY DIRECTION, WHILE PROVIDING POSITIVE DRAINAGE. THE MAXIMUM CROSS SLOPE FOR WORK ACCEPTANCE IS 2.0%. A NONSTANDARD FEATURE JUSTIFICATION IS REQUIRED WHERE TURNING SPACES EXCEED 2.0% IN ANY DIRECTION.
29. BEYOND THE BOTTOM GRADE BREAK, A CLEAR SPACE OF 4'-0" x 4'-0" MINIMUM SHALL BE PROVIDED WITHIN THE WIDTH OF THE PEDESTRIAN CROSSWALK, AND OUTSIDE THE PARALLEL VEHICLE TRAVEL LANE. THE CLEAR SPACE MAY OVERLAP TURNING SPACES, DETECTABLE WARNING SURFACES, AND DROP CURBS.

DETECTABLE WARNING NOTES:

30. DETECTABLE WARNING SURFACES SHALL BE PROVIDED AT THE FOLLOWING LOCATIONS ON PEDESTRIAN ACCESS ROUTES:
 - A. CURB RAMPS AND BLENDED TRANSITIONS AT PEDESTRIAN STREET CROSSINGS.
 - B. PEDESTRIAN REFUGE ISLANDS (WHERE THE LENGTH OF THE PEDESTRIAN ACCESS ROUTE ACROSS THE REFUGE ISLAND IS GREATER THAN OR EQUAL TO 6 FEET).
 - C. PEDESTRIAN AT-GRADE RAIL CROSSINGS NOT LOCATED WITHIN A STREET OR HIGHWAY.
31. DETECTABLE WARNING SURFACES SHALL BE PROVIDED WHERE THE PEDESTRIAN ACCESS ROUTE CROSSES DRIVEWAYS WITH SIGNAL, YIELD OR STOP CONTROL. DETECTABLE WARNING SURFACES SHALL NOT BE PROVIDED AT CROSSINGS OF UNCONTROLLED DRIVEWAY APRONS.
32. SOME DETECTABLE WARNING PRODUCTS REQUIRE A CONCRETE BORDER FOR PROPER INSTALLATION. IF REQUIRED, THE BORDER SHALL NOT EXCEED 2". WHERE THE BACK OF CURB EDGE IS TOOLED TO PROVIDE A RADIUS, THE BORDER DIMENSION SHALL BE MEASURED FROM THE INSIDE EDGE OF THE CURB RADIUS.
33. THE DETAILS PROVIDED ARE NOT DRAWN TO SCALE. THE QUANTITY OF DOMES DEPICTED ON THE DETECTABLE WARNING UNIT IS FOR ILLUSTRATION ONLY. THE SIZE OF THE DETECTABLE WARNING FIELD SHALL BE 24" MINIMUM IN THE DIRECTION OF TRAVEL AND SHALL EXTEND THE FULL WIDTH OF THE CURB RAMP OR FLUSH SURFACE, EXCLUDING ANY FLARED SIDES. THE WIDTH OF THE DETECTABLE WARNING FIELD INCLUDES A CONCRETE BORDER, IF PROVIDED.
34. ON SLOPES OF 5% OR GREATER, THE ROWS OF DOMES SHALL BE ALIGNED TO BE PERPENDICULAR OR RADIAL TO THE LOWER GRADE BREAK ON THE RAMP RUN. WHERE DOMES ARE ARRAYED RADially THEY MAY DIFFER IN DOME DIAMETER AND CENTER-TO-CENTER SPACING WITHIN THE RANGES SPECIFIED ON SHEET 2. ON SLOPES LESS THAN 5%, DOME ORIENTATION IS LESS CRITICAL AND MAY DIFFER FROM PERPENDICULAR OR RADIAL ALIGNMENT TO THE GRADE BREAK.
35. THE DETECTABLE WARNING FIELD SHALL BE THE COLOR SPECIFIED IN THE CONTRACT DOCUMENTS OR MEET THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS. DETECTABLE WARNING SURFACES SHALL CONTRAST VISUALLY WITH ADJACENT GUTTER, STREET OR HIGHWAY, OR PEDESTRIAN ACCESS ROUTE SURFACE, EITHER LIGHT-ON-DARK OR DARK-ON-LIGHT.



DETAIL "A"
ACCESSIBLE PASSING SPACE TRANSITION
ONE SIDE TAPERS




DETAIL "B"
ACCESSIBLE PASSING SPACE TRANSITION
BOTH SIDES TAPER

| DESIGN ELEMENT TOLERANCES | | |
|---|-------------------------------|---------------------------|
| ELEMENT | DESIGN AND FIELD LAYOUT LIMIT | LIMIT FOR WORK ACCEPTANCE |
| SIDEWALK CROSS SLOPE - SEE NOTE 12 | 1.5% MAX. | 2.0% MAX. |
| SIDEWALK GRADE (RUNNING SLOPE) - SEE NOTE 11 | 4.5% MAX. | 5.0% MAX. |
| CURB RAMP GRADE (RUNNING SLOPE) - SEE NOTE 21 | 7.5% MAX. | 8.3% MAX. |
| BLENDED TRANSITION GRADE (RUNNING SLOPE) - SEE NOTE 7 | 4.5% MAX. | 5.0% MAX. |


ALL VALUES SHOWN ON THE 608-01 STANDARD SHEETS REFER TO DESIGN AND FIELD LAYOUT LIMITS.

FOR ADDITIONAL REQUIREMENTS AND TOLERANCES, SEE "CRITICAL ELEMENTS FOR THE DESIGN, LAYOUT, AND CONSTRUCTION OF PEDESTRIAN FACILITIES" AVAILABLE ON THE NYS DOT HIGHWAY DESIGN MANUAL CHAPTER 18 WEBSITE.


| | |
|---|-------------------------------------|
| | Department of Transportation |
| | U.S. CUSTOMARY STANDARD SHEET |
| SIDEWALK AND CURB RAMP DETAILS (SHEET 1 OF 9) | |
| APPROVED MARCH 07, 2016 | ISSUED UNDER EB 16-012 |
| /S/ RICHARD W. LEE, P.E. DEPUTY CHIEF ENGINEER (DESIGN) | 608-01 |




OPTION 1




OPTION 4




| TRUNCATED DOME DIMENSIONS | | |
|---------------------------|---------------------|-----------|
| DIM. | MIN. (IN) | MAX. (IN) |
| A | 1.6" | 2.4" |
| B | 0.65" | 1.5" |
| C | 50% - 65% OF D DIM. | |
| D | 0.9" | 1.4" |




DETECTABLE WARNING SURFACE (DWS) TRUNCATED DOME DETAILS




OPTION 2



OPTION 6



VERTICAL SURFACE DISCONTINUITIES
SEE NOTE 6 ON SHEET 1 OF 9



OPTION 3

NOTE: OPTION 5 HAS BEEN REMOVED

DETECTABLE WARNING SURFACE (DWS) PLACEMENT OPTION DETAILS


NOTE:
ALL NOTES REFERENCED ON THIS SHEET CAN BE FOUND ON STANDARD SHEET 608-01, SHEET 1 OF 9.

NEW YORK STATE OF OPPORTUNITY. Department of Transportation


U.S. CUSTOMARY STANDARD SHEET

SIDEWALK AND CURB RAMP DETAILS (SHEET 2 OF 9)


APPROVED OCTOBER 05, 2017 /S/ RICHARD D. WILDER, P.E. DEPUTY CHIEF ENGINEER (DESIGN) ISSUED UNDER EB 17-042 608-01




OPTION A: FLARED CONCRETE




OPTION B: GRADED EARTH




OPTION A: GRADED EARTH AND TURF



OPTION C: RETURN CURB



OPTION D: UNCURBED INTERSECTION




OPTION B: BACK CURB


PARALLEL RAMP BACK TREATMENTS

RAMP SIDE CONFIGURATIONS


NOTE:
ALL NOTES REFERENCED ON THIS SHEET CAN BE FOUND ON STANDARD SHEET 608-01, SHEET 1 OF 9.

| | | | |
|---|--|---|--|
|  NEW YORK STATE OF OPPORTUNITY. | | Department of Transportation | |
| U.S. CUSTOMARY STANDARD SHEET | | | |
| SIDEWALK AND CURB RAMP DETAILS (SHEET 3 OF 9) | | | |
| APPROVED MARCH 07, 2016 | | ISSUED UNDER EB 16-012 | |
| /S/ RICHARD W. LEE, P.E. DEPUTY CHIEF ENGINEER (DESIGN) | | 608-01 | |


STANDARD SHEETS (USC), May 01, 2019




CURB RAMP CONFIGURATION: TYPE 1




CURB RAMP CONFIGURATION: TYPE 4



CURB RAMP CONFIGURATION: TYPE 2




CURB RAMP CONFIGURATION: TYPE 5




CURB RAMP CONFIGURATION: TYPE 3


NOTE:
 ALL NOTES REFERENCED ON THIS SHEET CAN BE FOUND ON STANDARD SHEET 608-01, SHEET 1 OF 9.

| | | | |
|---|--|--|--|
|  NEW YORK STATE OF OPPORTUNITY. | | Department of Transportation | |
| U.S. CUSTOMARY STANDARD SHEET | | | |
| SIDEWALK AND CURB RAMP DETAILS (SHEET 4 OF 9) | | | |
| APPROVED MARCH 07, 2016 | | ISSUED UNDER EB 16-012 | |
| /S/ RICHARD W. LEE, P.E. DEPUTY CHIEF ENGINEER (DESIGN) | | 608-01 | |


FILE NAME = DRAFT_608-0104.dgn
 DATE/TIME = 08-MAR-2016 13:21
 USER = Jmontgomery



CURB RAMP CONFIGURATION: TYPE 6




CURB RAMP CONFIGURATION: TYPE 8




CURB RAMP CONFIGURATION: TYPE 7


NOTE:
ALL NOTES REFERENCED ON THIS SHEET CAN BE FOUND ON STANDARD SHEET 608-01, SHEET 1 OF 9.

FILE NAME = DRAFT_608-0105.dgn
DATE/TIME = 08-MAR-2016 13:25
USER = .montgomery


| | | | |
|--|--|-------------------------------------|--|
|  NEW YORK STATE OF OPPORTUNITY. | | Department of Transportation | |
| U.S. CUSTOMARY STANDARD SHEET | | | |
| SIDEWALK AND CURB RAMP DETAILS (SHEET 5 OF 9) | | | |
| APPROVED MARCH 07, 2016 | | ISSUED UNDER EB 16-012 | |
| /S/ RICHARD W. LEE, P.E. DEPUTY CHIEF ENGINEER (DESIGN) | | 608-01 | |



**CURB RAMP CONFIGURATION: TYPE 9
MID BLOCK CROSSING OR T INTERSECTION**



**CURB RAMP CONFIGURATION: TYPE 11
MID BLOCK CROSSING OR T INTERSECTION**



**CURB RAMP CONFIGURATION: TYPE 10
MID BLOCK CROSSING OR T INTERSECTION**

NOTE:
ALL NOTES REFERENCED ON THIS SHEET CAN BE FOUND ON STANDARD SHEET 608-01, SHEET 1 OF 9.



U.S. CUSTOMARY STANDARD SHEET

**SIDEWALK AND CURB RAMP DETAILS
(SHEET 6 OF 9)**



APPROVED MARCH 07, 2016

ISSUED UNDER EB 16-012


/S/ RICHARD W. LEE, P.E.


608-01

DEPUTY CHIEF ENGINEER
(DESIGN)




NOTE:
ALL NOTES REFERENCED ON THIS SHEET CAN BE FOUND ON STANDARD SHEET 608-01, SHEET 1 OF 9.


| | |
|---|------------------------|
|  Department of Transportation | |
| U.S. CUSTOMARY STANDARD SHEET | |
| SIDEWALK AND CURB RAMP DETAILS (SHEET 7 OF 9) | |
| APPROVED MARCH 07, 2016 | ISSUED UNDER EB 16-012 |
| /S/ RICHARD W. LEE, P.E. DEPUTY CHIEF ENGINEER (DESIGN) | 608-01 |



DETECTABLE WARNINGS AT RAILROAD CROSSING




DETECTABLE WARNINGS AT PEDESTRIAN REFUGE ISLANDS
NON-ELEVATED CROSSING




CURB RAMP CROSS SLOPE TRANSITION

REFER TO NOTE 22 ON SHEET 1 OF 9 FOR CROSS SLOPE REQUIREMENTS




COUNTER SLOPE CONDITION 1

$A = |G2 - G1|$
ALGEBRAIC DIFFERENCE BETWEEN ROADWAY CROSS SLOPE AND CURB RAMP GRADE IS LESS THAN 12.5%.



COUNTER SLOPE CONDITION 2

$A = |G2 - G1|$
ALGEBRAIC DIFFERENCE BETWEEN ROADWAY SLOPE AND CURB RAMP GRADE IS GREATER THAN 12.5%. TRANSITION STRIP REQUIRED (MAX. GRADE 4.5%)



TRANSITION BETWEEN CURB RAMP AND EXISTING SIDEWALK

USE FOR CROSS SLOPE AND WIDTH TRANSITIONS

NOTE:

ALL NOTES REFERENCED ON THIS SHEET CAN BE FOUND ON STANDARD SHEET 608-01, SHEET 1 OF 9.



U.S. CUSTOMARY STANDARD SHEET

SIDEWALK AND CURB RAMP DETAILS
(SHEET 8 OF 9)


APPROVED MARCH 07, 2016

/S/ RICHARD W. LEE, P.E.
DEPUTY CHIEF ENGINEER
(DESIGN)


ISSUED UNDER EB 16-012

608-01


STANDARD SHEETS (USC), May 01, 2019




TYPICAL SIDEWALK CROSS SECTION
NO CURB WITH BUFFER ZONE
IN A FILL SECTION




TYPICAL SIDEWALK CROSS SECTION
NO CURB WITH BUFFER ZONE
IN A CUT SECTION




PAVEMENT RECONSTRUCTION OPTION A:
HOT MIX ASPHALT
SEE NOTE 18




TYPICAL SIDEWALK CROSS SECTION
CURBED WITH BUFFER ZONE




TYPICAL SIDEWALK CROSS SECTION
CURBED WITHOUT BUFFER ZONE



PAVEMENT RECONSTRUCTION OPTION B:
PORTLAND CEMENT CONCRETE
SEE NOTE 18




BACK OF CURB DETAIL
USE IN CUT SECTIONS WITH LIMITED
RIGHT-OF-WAY OR STEEP SLOPES








BACK OF CURB DETAIL
USE ON FILL SECTIONS WITH
LIMITED RIGHT-OF-WAY

NOTE:
ALL NOTES REFERENCED ON THIS SHEET CAN BE FOUND ON STANDARD SHEET 608-01, SHEET 1 OF 9.

FILE NAME = DRAFT_608-0109.dgn
DATE/TIME = 08-MAR-2016 13:51
USER = .montgomery

| | |
|---|------------------------|
|  Department of Transportation | |
| U.S. CUSTOMARY STANDARD SHEET | |
| SIDEWALK AND CURB RAMP DETAILS (SHEET 9 OF 9) | |
| APPROVED MARCH 07, 2016 | ISSUED UNDER EB 16-012 |
| /S/ RICHARD W. LEE, P.E. DEPUTY CHIEF ENGINEER (DESIGN) | 608-01 |



NOTES:

- THIS SHEET IS INTENDED TO DEPICT THE DIMENSIONAL REQUIREMENTS OF TYPICAL ACCESSIBLE PARKING LOT SPACES. THE SIDEWALK, CURBING, AND PAVEMENT MATERIALS SHALL BE AS SPECIFIED ELSEWHERE IN THE CONTRACT DOCUMENTS.
- MINIMUM NUMBER OF ACCESSIBLE SPACES:

| TOTAL SPACES IN LOT | MINIMUM NUMBER OF ACCESSIBLE SPACES | TOTAL SPACES IN LOT | MINIMUM NUMBER OF ACCESSIBLE SPACES |
|---------------------|-------------------------------------|---------------------|--|
| 1 TO 25 | 1 | 201 TO 300 | 7 |
| 26 TO 50 | 2 | 301 TO 400 | 8 |
| 51 TO 75 | 3 | 401 TO 500 | 9 |
| 75 TO 100 | 4 | 501 TO 1,000 | 2% OF TOTAL |
| 101 TO 150 | 5 | 1,001 AND OVER | 20, PLUS ONE FOR EACH 100, OR FRACTION THEREOF, OVER 1,000 |
| 151 TO 200 | 6 | | |

EXCEPTION: PARKING AREAS ON THE PREMISES OF, OR IMMEDIATELY ADJACENT TO, MEDICAL SERVICES FACILITIES PROVIDING TREATMENT FOR MOBILITY IMPAIRED PERSONS AND OTHER SIMILAR LOCATIONS MAY REQUIRE A GREATER NUMBER OF ACCESSIBLE PARKING SPACES THAN INDICATED ABOVE. REFER TO THE APPLICABLE ACCESSIBILITY STANDARD.

- LOCATION - PARKING SPACES FOR USE BY PERSONS WITH DISABILITIES SHALL BE IN THE SPACES CLOSEST TO THE NEAREST ACCESSIBLE BUILDING OR FACILITY ENTRANCE ON AN ACCESSIBLE ROUTE.
- DIMENSIONS - ACCESSIBLE PARKING SPACES SHALL BE AT LEAST 8' WIDE AND SHALL HAVE AN ADJACENT ACCESS AISLE 8' WIDE MEASURED PERPENDICULAR TO THE STALL STRIPE TO ACCOMMODATE VANS WITH LIFTS.
- COMMON ACCESS AISLES FOR 90° PARKING - TWO ACCESSIBLE PARKING SPACES MAY SHARE A COMMON ACCESS AISLE. FOR ACUTE ANGLED PARKING, SUCH AS 60° PARKING, OR WHERE ONE WAY DRIVEWAY AISLES WOULD PREVENT VANS WITH PASSENGER SIDE LIFTS FROM BACKING INTO ACCESSIBLE SPACES, AN ACCESSIBLE ACCESS AISLE MUST BE PROVIDED FOR EACH ACCESSIBLE PARKING SPACE. WIDTH OF ACCESS AISLES AND PARKING SPACES ARE MEASURED PERPENDICULAR TO THE STRIPING.
- SIGNING - EACH ACCESSIBLE PARKING SPACE SHALL BE MARKED BY PERMANENTLY INSTALLED GROUND MOUNTED SIGNS WHICH DISPLAY THE INTERNATIONAL SYMBOL FOR ACCESS. EACH ACCESS AISLE SHALL BE MARKED BY PERMANENTLY INSTALLED GROUND MOUNTED SIGNS INDICATING THAT STOPPING IS NOT PERMITTED IN THE AISLE. SIGNS SHALL NOT BLOCK THE ACCESSIBLE CLEAR WIDTH OF ADJACENT WALKWAYS. SIGNS LOCATED WHERE THEY MAY BE HIT BY VEHICLES BEING PARKED SHALL BE INSTALLED AS SHOWN IN THE POST BASE DETAIL. THE BOTTOMS OF THE SIGNS LOCATED ON POSTS INSTALLED IN PAVED AREAS SHALL BE 7' MINIMUM ABOVE THE WALKWAY SURFACE. THE BOTTOMS OF SIGNS LOCATED IN UNPAVED AREAS SHALL BE 7' MINIMUM ABOVE THE PAVEMENT SURFACE.

- SURFACE SLOPES - SLOPES AT ACCESSIBLE PARKING SPACES, ACCESS AISLES, AND ADJOINING WALKWAYS SHALL NOT EXCEED 1.5% MAXIMUM IN ANY DIRECTION FOR DESIGN AND LAYOUT, AND 2.0% MAXIMUM FOR WORK ACCEPTANCE, WHILE PROVIDING POSITIVE DRAINAGE.
- OVERHEAD CLEARANCE - VEHICLE ACCESS ROUTES TO AND FROM ACCESSIBLE PARKING SPACES, INCLUDING IN GARAGES AND OPEN PARKING STRUCTURES, SHALL HAVE A MINIMUM VERTICAL CLEARANCE OF 8'-2".
- PAVEMENT MARKING COLORS - REQUIRED ACCESSIBLE PARKING SPACE AND ACCESS AISLE STRIPING AND OTHER OPTIONAL PAVEMENT MARKINGS, SUCH AS THE INTERNATIONAL ACCESS SYMBOL, SHALL BE PAINTED WHITE OR BLUE.
- REFER TO STANDARD SHEETS 608-01 TITLED "SIDEWALK AND CURB RAMP DETAILS" FOR CURB RAMP REQUIREMENTS. DETECTABLE WARNING SURFACES ARE NOT REQUIRED.
- A SMOOTH, FLUSH TRANSITION MUST BE PROVIDED BETWEEN ALL PEDESTRIAN WALKWAYS, ACCESSIBLE PARKING SPACES AND AISLES.
- WHERE A CHANGE IN DIRECTION IS REQUIRED TO UTILIZE A CURB RAMP, A TURNING SPACE 4'-0" x 4'-0" MINIMUM SHALL BE PROVIDED AT THE BASE OR THE TOP OF CURB RAMP, AS APPLICABLE. THE CROSS SLOPE OF TURNING SPACES SHALL NOT EXCEED 1.5% IN ANY DIRECTION FOR DESIGN AND LAYOUT, AND 2.0% FOR WORK ACCEPTANCE, WHILE PROVIDING POSITIVE DRAINAGE.

NEW YORK
STATE OF
OPPORTUNITY.

**Department of
Transportation**

U.S. CUSTOMARY STANDARD SHEET

ACCESSIBLE PARKING FOR PERSONS
WITH DISABILITIES DETAILS

APPROVED MARCH 07, 2016

ISSUED UNDER EB 16-012

/S/ RICHARD W. LEE, P.E.
DEPUTY CHIEF ENGINEER
(DESIGN)

608-02

DEFINITION OF TERMS:

DRIVEWAY - EVERY ENTRANCE OR EXIT USED BY VEHICULAR TRAFFIC TO AND FROM LANDS OR BUILDINGS ABUTTING A HIGHWAY.

RESIDENTIAL DRIVEWAY - A DRIVEWAY SERVING FOUR OR FEWER PRIVATE HOMES OR AN APARTMENT BUILDING FOR FOUR OR FEWER FAMILY UNITS.

COMMERCIAL DRIVEWAY - A DRIVEWAY SERVING A COMMERCIAL ESTABLISHMENT, INDUSTRY, GOVERNMENTAL OR EDUCATIONAL INSTITUTION, PRIVATE UTILITY, HOSPITAL, CHURCH, APARTMENT BUILDING, OR OTHER COMPARABLE TRAFFIC GENERATOR.

MAJOR COMMERCIAL DRIVEWAY - ANY COMMERCIAL DRIVEWAY WHERE THE ACTUAL OR ANTICIPATED TRAFFIC VOLUME ON A TYPICAL DAY IS DEFINED BY THE DRIVEWAY POLICY AS DEFINED IN THE HIGHWAY DESIGN MANUAL (HDM) CHAPTER 5 APPENDIX 5A.

MINOR COMMERCIAL DRIVEWAY - ANY COMMERCIAL DRIVEWAY WHERE THE ACTUAL OR ANTICIPATED TRAFFIC VOLUMES ON A TYPICAL DAY ARE LESS THAN THE VALUES STIPULATED FOR A MAJOR COMMERCIAL DRIVEWAY.

FIELD ENTRANCE - A DRIVEWAY SERVING A FARMYARD, CULTIVATED OR UNCULTIVATED FIELD, TIMBERLAND, OR UNDEVELOPED LAND NOT USED FOR INDUSTRIAL, COMMERCIAL, OR RESIDENTIAL PURPOSES.

URBAN / RURAL - THE AREA CHARACTER BASED ON NYSDOT HIGHWAY DESIGN MANUAL CHAPTER 2, SECTION 2.4.

DRIVEWAY OFFSET - THE DISTANCE IN FEET MEASURED FROM THE INSIDE EDGE OF THE OUTERMOST TRAVEL LANE, OR TURNING LANE, TO THE HIGHWAY EDGE OF PAVEMENT. THE DISTANCE IS EQUAL TO THE WIDTH OF THE OUTERMOST LANE AND THE WIDTH OF THE PAVED SHOULDER, OR CURB OFFSET.

HIGHWAY EDGE OF PAVEMENT - THE OUTSIDE EDGE OF THE PAVED HIGHWAY SURFACE.

SHOULDER WIDTH - THE WIDTH IN FEET OF PAVED SHOULDER INCLUDING A PARKING LANE, BIKE LANE, CURB OFFSET, OR OTHER PAVED AREA OUTSIDE OF THE TRAVEL LANE.

MINIMUM PAVING LIMIT (MPL) - THE MINIMUM DISTANCE IN FEET MEASURED ALONG THE CENTERLINE OF A DRIVEWAY FROM THE OUTSIDE EDGE OF THE OUTERMOST TRAVEL LANE THAT A DRIVEWAY MUST BE PAVED (INCLUDES THE SHOULDER WIDTH).

PAVEMENT LENGTH (PL) - THE DISTANCE IN FEET MEASURED ALONG THE CENTERLINE OF A DRIVEWAY FROM THE HIGHWAY EDGE OF PAVEMENT TO THE END OF PROPOSED DRIVEWAY PAVEMENT.

TRANSITION LENGTH (TL) - THE DISTANCE IN FEET MEASURED ALONG THE CENTERLINE OF A DRIVEWAY BEYOND THE DRIVEWAY PAVEMENT LENGTH (PL) TO THE END OF PROPOSED DRIVEWAY WORK. THE TRANSITION LENGTH (TL) IS TYPICALLY USED FOR GRADING, LAYOUT, OR TRANSITION REASONS. THE TRANSITION LENGTH (TL) ONLY APPLIES TO DRIVEWAYS THAT ARE UNPAVED.

BUFFER ZONE - A PHYSICAL DISTANCE SEPARATING THE PEDESTRIAN ACCESS ROUTE AND THE VEHICLE TRAVELED WAY. THE BUFFER ZONE BUFFERS PEDESTRIANS FROM TRAFFIC AND PROVIDES SPACE FOR SNOW STORAGE, UTILITIES, PLANTS, AND OTHER STREET APPURTENANCES. THE BUFFER ZONE MAY BE PLANTED OR PAVED.

SHARED-USE-PATH (SUP) - A BICYCLE AND PEDESTRIAN FACILITY, TYPICALLY WITHIN THE RIGHT-OF-WAY, SEPARATED FROM MOTORIZED VEHICULAR TRAFFIC BY A BUFFER ZONE OR BARRIER. REFER TO HIGHWAY DESIGN MANUAL CHAPTER 17 AND AASHTO GUIDE FOR THE DEVELOPMENT OF BICYCLE FACILITIES FOR GUIDANCE ON BUFFER ZONE WIDTH AND SEPARATION OF SHARED USE PATHS FROM ROADWAYS.

SIDEWALK - A SMOOTH, STABLE AND SLIP RESISTANT EXTERIOR PATHWAY INTENDED FOR PEDESTRIAN USE ALONG A VEHICULAR WAY SEPARATED WITH A CURB OFFSET.

HMA - HOT MIX ASPHALT

PCC - PORTLAND CEMENT CONCRETE

GENERAL NOTES FOR DRIVEWAY STANDARD SHEETS:

- THE DRIVEWAY STANDARD SHEETS APPLY TO FIELD ENTRANCES, RESIDENTIAL DRIVEWAYS AND MINOR COMMERCIAL DRIVEWAYS. FIELD ENTRANCES AND RESIDENTIAL DRIVEWAYS ACCOMMODATE AN AASHTO PASSENGER CAR DESIGN VEHICLE. MINOR COMMERCIAL DRIVEWAYS ACCOMMODATE AN AASHTO SINGLE UNIT TRUCK DESIGN VEHICLE.
 - DRIVEWAY WORK PERFORMED OFF THE RIGHT-OF-WAY REQUIRES AN EASEMENT OR A DRIVEWAY RELEASE. A DRIVEWAY RELOCATION WILL REQUIRE A TEMPORARY EASEMENT MAP.
 - IF COMMERCIAL PROPERTY DEVELOPMENT PLANS INVOLVE NEW OR MODIFIED ACCESS TO A STATE HIGHWAY A COMMERCIAL HIGHWAY WORK PERMIT APPLICATION (FORM PERM 33-COM) MUST BE FILLED OUT AND SUBMITTED TO THE REGIONAL PERMIT COORDINATOR.
 - SEE THE DRIVEWAY TABLE IN THE CONTRACT PLANS FOR SPECIFIC DRIVEWAY LOCATIONS, WIDTHS ("W"), CORNER ANGLES, LENGTHS ("L"), MATERIAL, AND ENTRANCE TYPE.
 - DETECTABLE WARNING SURFACES SHALL BE PROVIDED WHERE THE PEDESTRIAN ACCESS ROUTE CROSSES DRIVEWAYS WITH SIGNAL, YIELD OR STOP CONTROL. DETECTABLE WARNING SURFACES SHALL NOT BE PROVIDED AT CROSSINGS OF UNCONTROLLED DRIVEWAY APRONS.
 - THE TAPER METHOD IS GENERALLY NOT RECOMMENDED FOR DRIVEWAYS WITH A DRIVEWAY OFFSET LESS THAN 16 FEET, UNLESS IT CAN BE FIELD VERIFIED THAT THE DRIVEWAY ENTRANCE WIDTH WILL ACCOMMODATE THE VEHICLES THAT USE THE DRIVEWAY ON A REGULAR BASIS.
 - TYPE 3 AND TYPE 4 DRIVEWAY ENTRANCES CAN BE USED WITHOUT CURB IF A TAPER STYLE ENTRANCE BETTER MATCHES THE HIGHWAY CORRIDOR AESTHETICS OR SPECIFIC SITE CONDITIONS THAN A RADIUS STYLE ENTRANCE.
 - UP TO 10" OF HMA MAY BE REQUIRED FOR HEAVY TRUCKS PER CONTRACT DOCUMENTS.
 - UP TO 9" OF PCC MAY BE REQUIRED FOR HEAVY TRUCKS PER CONTRACT DOCUMENTS.
 - UP TO 12" OF SUBBASE MAY BE REQUIRED FOR HEAVY TRUCKS PER CONTRACT DOCUMENTS.
 - THE DETAILS SHOW THE PAVEMENT LENGTH ("PL") EXTENDING TO THE MINIMUM PAVING LIMIT ("MPL"). HOWEVER, THE "PL" CAN EXTEND BEYOND THE "MPL" AS SPECIFIED IN THE CONTRACT DOCUMENTS.
 - A DRIVEWAY TIP-UP SECTION SHOULD EXTEND TO A LOGICAL TERMINI (EXAMPLE: SIDEWALK EDGE, WHERE THE DRIVEWAY GRADE MATCHES EXISTING GROUND, OR LAYOUT POINT). FOR REFERENCE, A REASONABLE LENGTH FOR TAPERING THE TIP-UP SECTION BACK TO THE EDGE OF DRIVEWAY IS 3 TO 4 TIMES THE LENGTH OF CURB DROP. THE TIP-UP SECTION IS NOT PART OF THE DRIVEWAY OPENING WIDTH. REFER TO NYSDOT STANDARD SHEET 609-02 "MISCELLANEOUS CURB DETAILS" FOR THE CURB TRANSITION.
 - TO DETERMINE THE LIMITS OF SHOULDER RECONSTRUCTION, REFER TO THE DRIVEWAY OPENING TABLES ON SHEET 4 FOR NO SHOULDER (0' OFFSET).
 - FOR PCC SHOULDERS, SEE STANDARD SHEET 502-02 FOR LONGITUDINAL JOINT TIE DETAILS.
 - DIMENSIONS AND ANGLES MAY BE INTERPOLATED FOR VALUES OTHER THAN THOSE SHOWN IN THE TABLES.
 - THE SHOULDER PAVEMENT THICKNESSES SHOWN ARE DEFAULT VALUES UNLESS OTHERWISE SHOWN IN THE PLANS. MATERIALS SHALL BE AS SPECIFIED IN THE CONTRACT DOCUMENTS.
- WIDTH / LENGTH:**
- WHERE THERE ARE CONSTRAINTS THAT PREVENT THE CONSTRUCTION OF THE DRIVEWAY OPENING USING EITHER OF THE LAYOUT METHODS, THE ENGINEER MAY SPECIFY A SMALL CORNER CURB RADIUS OF 2' (OR A "1/2 BULL NOSE" CURB ALONG LOW SPEED HIGHWAYS), PROVIDED THE DRIVEWAY OPENING MEETS THE REQUIREMENTS OF THE "DRIVEWAY OPENING" TABLES ON SHEET 4.
 - FOR RESIDENTIAL DRIVEWAYS, THE MINIMUM PAVING LIMIT SHALL BE 10' FROM THE OUTSIDE EDGE OF TRAVEL LANE OR 2' BEHIND ANY SIDEWALK, IF PRESENT, WHICHEVER IS GREATER. FOR MINOR COMMERCIAL DRIVEWAYS, THE MINIMUM PAVING LIMIT SHALL BE 30' FROM THE OUTSIDE EDGE OF TRAVEL LANE, OR 2' BEHIND ANY SIDEWALK, IF PRESENT, OR EXTEND TO THE RIGHT-OF-WAY LINE, WHICHEVER IS GREATER. THE PAVING LIMIT MAY EXTEND BEYOND THE MINIMUM PAVING LIMIT FOR NEW DRIVEWAYS AND TO TRANSITION TO EXISTING PAVED DRIVEWAYS. THE PAVING LIMIT WILL BE NOTED IN THE DRIVEWAY TABLE OF THE CONTRACT PLANS.
 - FOR GRADING AND CONSTRUCTION REQUIREMENTS OF TRANSITIONS FROM PLACED HMA TO EXISTING HMA DRIVEWAYS, REFER TO DETAIL 9 - "TIE-IN TO EXISTING DRIVEWAYS" ON SHEET 9, AND TABLE 3 - "DRIVEWAY MATERIALS AND THICKNESS" ON SHEET 2.
 - FOR PCC DRIVEWAYS, REFER TO THE 502 SERIES STANDARD SHEETS FOR METAL REINFORCEMENT, JOINT TIES, SAWING AND SEALING, ETC.
 - A 5' MINIMUM BUFFER ZONE SHALL BE USED UNLESS OTHERWISE SPECIFIED IN THE CONTRACT DOCUMENTS.

SITE CONDITIONS (SIDEWALK / CURB):

- ANY PCC SIDEWALK WHICH CROSSES A DRIVEWAY SHALL HAVE A MINIMUM THICKNESS OF 6" AND INCLUDE STEEL MESH REINFORCEMENT WITH 3" OF TOP COVER.
- FOR GRADE CHANGES REFER TO THE DRIVEWAY PROFILES ON SHEET 8. VERTICAL CURVES ARE RECOMMENDED TO CONNECT TANGENTS. SEE TABLE 5 - "MINIMUM LENGTH OF VERTICAL CURVE" ON SHEET 2 FOR TYPICAL VERTICAL CURVE LENGTHS "L".
- WHERE THE EXISTING GRADE OF THE DRIVEWAY PROFILE IS LESS THAN OR EQUAL TO 2%, MATCH THE CROSS SLOPE OF THE SIDEWALK TO THE EXISTING DRIVEWAY PROFILE GRADE.
- WHERE THE EXISTING GRADE OF THE DRIVEWAY PROFILE EXCEEDS 2% SAWCUT THE DRIVEWAY AND RECONSTRUCT A MINIMUM OF 2' ON BOTH SIDES OF THE SIDEWALK, TO TRANSITION FROM THE EXISTING GRADE OF THE DRIVEWAY PROFILE TO THE SIDEWALK CROSS SLOPE.
- TO PREVENT DRIVEWAY GRADES FROM EXCEEDING THE VALUES IN TABLE 2 - "MAXIMUM DRIVEWAY SLOPE" ON SHEET 2, IT MAY BE NECESSARY TO DEPRESS THE SIDEWALK ACROSS THE DRIVEWAY. SIDEWALK RAMPS SHALL HAVE THE LEAST RUNNING SLOPE POSSIBLE, WITH A MAXIMUM DESIGN AND LAYOUT SLOPE OF 7.5%. THE RUNNING SLOPE FOR WORK ACCEPTANCE SHALL BE A MAXIMUM OF 8.3%. WHERE EXISTING CONDITIONS DO NOT ALLOW THE CONSTRUCTION OF A SIDEWALK RAMP AT 8.3% OR LESS RUNNING SLOPE, THE RAMP LENGTH SHALL NOT BE REQUIRED TO EXCEED 15'-1" FOR DESIGN AND LAYOUT. THE RAMP LENGTH SHALL NOT BE REQUIRED TO EXCEED 15'-0" FOR WORK ACCEPTANCE.
- WHERE DRAINAGE IS CARRIED ALONG THE CURB, CONSTRUCT THE DRIVEWAY WITH A SHORT UPGRADE TO PREVENT RUNOFF FROM PONDING AT THE DRIVEWAY ENTRANCE (FLAT DRIVEWAY) OR RUNNING DOWN THE DRIVEWAY (DOWNHILL DRIVEWAY SLOPE). IF CONDITIONS MAKE THE ADDITION OF A SHORT UPGRADE IMPRACTICAL, USE 1" CURB REVEAL AND CONTINUE CURB ACROSS THE DRIVEWAY OPENING. TYPICALLY, CURB REVEAL WILL NOT BE CONSTRUCTED IN RURAL AREAS. IF CURB REVEAL IS SPECIFIED FOR A SPECIFIC DRIVEWAY, IT WILL BE NOTED IN THE DRIVEWAY TABLE OF THE CONTRACT PLANS IN THE 'COMMENTS' COLUMN.

ENTRANCE TYPE:

- THE ENGINEER MAY INTERCHANGE TYPE 1, TYPE 3 AND TYPE 4 RESIDENTIAL DRIVEWAYS TO BETTER MATCH THE EXISTING ENTRANCE TYPES ALONG THE HIGHWAY CORRIDOR WHILE CONSIDERING AVAILABLE SPACE, CONSTRUCTABILITY, SAFETY, AND FUNCTIONALITY. THE DRIVEWAY TYPE SHALL COMPLY WITH TABLE 4 - "DRIVEWAY ENTRANCE TYPE SELECTION" ON SHEET 2.
- FOR DRIVEWAYS WITH VARYING WIDTHS AND/OR CURVED ALIGNMENTS, DETERMINE THE DRIVEWAY WIDTH AND CORNER ANGLE 20'-0" FROM THE EDGE OF TRAVEL LANE.
- FOR A ONE-WAY DRIVEWAY ENTRANCE OR EXIT, THE DRIVEWAY ENTRANCE WIDENING IS ONLY NECESSARY ON ONE SIDE OF THE DRIVEWAY TO ACCOMMODATE THE SHARPER TURNING MOVEMENT. ONE-WAY DRIVEWAYS WILL BE IDENTIFIED ON THE DRIVEWAY TABLE OF THE CONTRACT PLANS UNDER 'COMMENTS'. FOR CURBED HIGHWAYS, A SMALL CORNER CURB RADIUS OF 2' (OR '1/2 BULLNOSE' CURB ALONG LOW SPEED HIGHWAYS) SHALL BE CONSTRUCTED TO ELIMINATE A SHARP CORNER BEND IN THE CURB LINE (WHICH IS SAFER FOR SNOWPLOW OPERATIONS).

MATERIAL:

- FOR DRIVEWAY MATERIAL REQUIREMENTS, USE TABLE 3 - "DRIVEWAY MATERIALS AND THICKNESS" ON SHEET 2.
- FOR FIELD ENTRANCES, THE MATERIAL WITHIN THE PAVEMENT LENGTH ("PL") CAN CONSIST OF GRAVEL OR STONE AND BE CONNECTED TO THE EDGE OF THE HIGHWAY SHOULDER WITHOUT REMOVING ANY OF THE EXISTING SHOULDER MATERIAL.


DESIGN ELEMENT TOLERANCES

| ELEMENT | DESIGN AND FIELD LAYOUT LIMIT | LIMIT FOR WORK ACCEPTANCE |
|---|-------------------------------|---------------------------|
| SIDEWALK CROSS SLOPE - SEE NOTE 12 | 1.5% MAX. | 2.0% MAX. |
| SIDEWALK GRADE (RUNNING SLOPE) - SEE NOTE 11 | 4.5% MAX. | 5.0% MAX. |
| CURB RAMP GRADE (RUNNING SLOPE) - SEE NOTE 21 | 7.5% MAX. | 8.3% MAX. |
| BLENDED TRANSITION GRADE (RUNNING SLOPE) - SEE NOTE 7 | 4.5% MAX. | 5.0% MAX. |

NOTES REFERENCED IN THE TABLE ABOVE CAN BE FOUND ON STANDARD SHEET 608-01 SHEET 1 OF 9.

ALL VALUES SHOWN ON THE 608-03 STANDARD SHEETS REFER TO DESIGN AND FIELD LAYOUT LIMITS.

FOR ADDITIONAL REQUIREMENTS AND TOLERANCES, SEE "CRITICAL ELEMENTS FOR THE DESIGN, LAYOUT, AND CONSTRUCTION OF PEDESTRIAN FACILITIES" AVAILABLE ON THE NYSDOT HIGHWAY DESIGN MANUAL CHAPTER 18 WEBSITE.

| | | | |
|---|--|---|--|
|  NEW YORK STATE OF OPPORTUNITY. | | Department of Transportation | |
| U.S. CUSTOMARY STANDARD SHEET | | | |
| RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 1 OF 9) | | | |
| APPROVED MARCH 07, 2016 | | ISSUED UNDER EB 16-012 | |
| /S/ RICHARD W. LEE, P.E. DEPUTY CHIEF ENGINEER (DESIGN) | | 608-03 | |

| DRIVEWAY CLASSIFICATION | PERMISSIBLE RANGE OF WIDTHS (FT.) WITHIN 30 FT. OF TRAVELED WAY FOR ROADS POSTED 40 MPH OR LESS | PERMISSIBLE RANGE OF WIDTHS (FT.) WITHIN 30 FT. OF TRAVELED WAY FOR ROADS POSTED 45 MPH OR MORE |
|---|---|---|
| RESIDENTIAL LESS THAN 50 FT. IN LENGTH MEASURED ALONG THE CENTERLINE | 9 TO 12 | 10 TO 24 |
| RESIDENTIAL GREATER THAN 50 FT. IN LENGTH MEASURED ALONG THE CENTERLINE | 9 TO 12 | 10 TO 14 |
| MINOR COMMERCIAL SHARED TWO-WAY DRIVEWAY | 22 TO 30 | 28 TO 35 |
| MINOR COMMERCIAL DIVIDED OR ONE-WAY DRIVEWAY | 12 TO 24 | 12 TO 24 |
| MINOR COMMERCIAL MULTI-LANE DRIVEWAY | 12 TO 15 EACH LANE | 14 TO 16 EACH LANE |

| ROADWAY CLASSIFICATION | MINOR COMMERCIAL DRIVEWAY | RESIDENTIAL DRIVEWAY |
|------------------------|---------------------------|----------------------|
| RURAL | 10% | 12% |
| URBAN | 6% | 8% |

| PROPOSED OR EXISTING DRIVE | WITHIN DRIVEWAY PAVEMENT LENGTH ("PL") | | | WITHIN TRANSITION LENGTH ("TL") | | |
|----------------------------|--|---------------------------------|--------------------------------------|--|---------------------------------|--------------------------------------|
| | MATERIAL | THICKNESS FOR RESIDENTIAL (IN.) | THICKNESS FOR MINOR COMMERCIAL (IN.) | MATERIAL | THICKNESS FOR RESIDENTIAL (IN.) | THICKNESS FOR MINOR COMMERCIAL (IN.) |
| DIRT, GRASS, OR GRAVEL | HMA | 3 | 4 | SUBBASE COURSE, EXCAVATE AS NECESSARY | 6 | 9 |
| | SUBBASE COURSE | 6 | 8 | | | |
| STONE | HMA | 3 | 4 | STONE, EXCAVATE AS NECESSARY | 8 | 11 |
| | SUBBASE COURSE | 6 | 8 | | | |
| HMA (RESURFACING) | HMA | 1½ | 1½ | NOT APPLICABLE - ALL WORK ON AN EXISTING PAVED DRIVEWAY IS WITHIN THE DRIVEWAY PAVEMENT LENGTH | | |
| | TRUE AND LEVELING COURSE | AS NECESSARY | AS NECESSARY | | | |
| HMA (RECONSTRUCTION) | HMA | 3 | 4 (SEE NOTE 8) | NOT APPLICABLE - ALL WORK ON AN EXISTING PAVED DRIVEWAY IS WITHIN THE DRIVEWAY PAVEMENT LENGTH | | |
| | SUBBASE COURSE | 6 | 8 (SEE NOTE 10) | | | |
| PCC | PCC | 6 | 6 (SEE NOTE 9) | NOT APPLICABLE - ALL WORK ON AN EXISTING PAVED DRIVEWAY IS WITHIN THE DRIVEWAY PAVEMENT LENGTH | | |
| | SUBBASE COURSE | 6 | 8 (SEE NOTE 10) | | | |


| DRIVEWAY ENTRANCE TYPE | ENTRANCE WIDENING METHOD | CONDITIONS FOR USE | | | | | | |
|------------------------|--------------------------|----------------------------------|--------------|--------------------------------|---------------------------------|--|---------------------------------|---|
| | | DRIVEWAY CLASSIFICATION (NOTE 1) | CORNER ANGLE | TRAVEL LANE AND SHOULDER WIDTH | CURB | SIDEWALK | HIGHWAY DESIGN SPEED | RECOMMENDED USE |
| TYPE 1 | RADIUS | RESIDENTIAL OR MINOR COMMERCIAL | 60° TO 120° | ANY | USE WITH OR WITHOUT CURB | USE WITHOUT SIDEWALK | ANY SPEED | RECOMMENDED FOR ALL LOCATIONS (EXCEPT FOR MINOR COMMERCIAL WITH CURB) |
| TYPE 2 | RADIUS | MINOR COMMERCIAL ONLY | 60° TO 120° | ANY | USE ONLY WITH CURB | USE WITH OR WITHOUT SIDEWALK | ANY SPEED | RECOMMENDED ONLY FOR MINOR COMMERCIAL WITH CURB |
| TYPE 3 | TAPER | RESIDENTIAL OR MINOR COMMERCIAL | 80° TO 100° | 16' OR GREATER (SEE NOTE 6) | USE ONLY WITH CURB (SEE NOTE 7) | USE ONLY WITH SIDEWALK OFFSET A MIN. OF 2' FROM THE EDGE OF PAVEMENT OR WITHOUT SIDEWALK | ONLY LOW SPEED (45 MPH OR LESS) | ALTERNATIVE ENTRANCE TYPE (TYPICALLY FOR URBAN AREA USE) |
| TYPE 4 | TAPER | RESIDENTIAL OR MINOR COMMERCIAL | 80° TO 100° | 16' OR GREATER (SEE NOTE 6) | USE ONLY WITH CURB (SEE NOTE 7) | USE ONLY WITH SIDEWALK LESS THAN 2' FROM OR ADJACENT TO THE EDGE OF PAVEMENT | ONLY LOW SPEED (45 MPH OR LESS) | ALTERNATIVE ENTRANCE TYPE (TYPICALLY FOR URBAN AREA USE) |

TABLE 4 ONLY APPLIES TO RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS, FOR OTHER DRIVEWAY CLASSIFICATIONS (MAJOR COMMERCIAL, FIELD ENTRANCE, ETC.), REFER TO THE NYS DOT HIGHWAY DESIGN MANUAL CHAPTER 5, APPENDIX 5A "POLICY AND STANDARDS FOR THE DESIGN OF ENTRANCES TO STATE HIGHWAYS".

| CHANGES IN GRADE A = G2 - G1 | CREST, L _c (FT.) | SAG, L _s (FT.) |
|-----------------------------------|--------------------------------|------------------------------|
| 4-6% | 5 | 6 |
| 6-8% | 5 | 7 |
| 8-10% | 6 | 8 |
| 10-12% | 6 | 8 |
| 12-14% | 7 | 8 |
| 14-16% | 7 | 8 |
| 16-18% | 8 | 8 |
| 18-20% | 8 | 8 |

LENGTH OF VERTICAL CURVE BASED ON 35' CURVE RADIUS AND THE AASHTO PASSENGER VEHICLE AND SINGLE UNIT TRUCK CLEARANCES.

NOTE:
ALL GENERAL NOTES AND ABBREVIATIONS REFERENCED ON THIS SHEET CAN BE FOUND ON STANDARD SHEET 608-03, SHEET 1 OF 9.

| | |
|---|---|
|  NEW YORK STATE OF OPPORTUNITY. | Department of Transportation |
| U.S. CUSTOMARY STANDARD SHEET | |
| RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 2 OF 9) | |
| APPROVED MARCH 07, 2016 | ISSUED UNDER EB 16-012 |
| /S/ RICHARD W. LEE, P.E. DEPUTY CHIEF ENGINEER (DESIGN) | 608-03 |

DRIVEWAY OPENING LAYOUT:

THERE ARE TWO RECOMMENDED DRIVEWAY OPENING WIDENING METHODS: (1.) THE RADIUS METHOD, WHICH UTILIZES A CIRCULAR ARC TO WIDEN THE DRIVEWAY, AND (2.) THE TAPER METHOD, WHICH UTILIZES A STRAIGHT TAPER WIDENING OUT AT AN ESTABLISHED FLARE RATE.

THE RADIUS METHOD IS THE TYPICAL METHOD, ALTHOUGH THE TAPER METHOD IS A REASONABLE ALTERNATIVE FOR URBAN AREAS AND OTHER AREAS WHERE IT MIGHT BETTER MATCH THE HIGHWAY CORRIDOR AESTHETICS AND FUNCTIONALITY. SEE TABLE 4 - 'DRIVEWAY ENTRANCE TYPE SELECTION' ON SHEET 2 FOR ADDITIONAL VARIABLES CONCERNING THE SELECTION OF A DRIVEWAY OPENING WIDENING METHOD.

RADIUS METHOD OF LAYOUT:

- STEP 1. LOCATE AN OFFSET LINE 11' PARALLEL FROM THE INSIDE EDGE OF THE OUTERMOST TRAVEL LANE.
- STEP 2. SCRIBE A LINE PARALLEL TO THE OFFSET LINE, OFFSET "R" FEET (SEE TABLE 6).
- STEP 3. SCRIBE A LINE PARALLEL TO THE EDGE OF DRIVEWAY (NEAR SIDE), OFFSET "R" FEET.
- STEP 4. FIND THE CENTER POINT OF THE CORNER RADIUS ARC, WHICH IS LOCATED AT THE INTERSECTION OF THE LINES FROM STEPS 2 AND 3.
- STEP 5. FROM THE CENTER POINT, SCRIBE AN ARC WITH RADIUS "R", WHICH IS TANGENT TO BOTH THE OFFSET LINE AND THE EDGE OF DRIVEWAY. THE ARC SHOULD INTERSECT THE LINES AT THE DISTANCES "X" LISTED IN TABLE 7. DISTANCES IN TABLE 7 ARE AS MEASURED FROM THE INTERSECTION POINT OF THE OFFSET LINE (NOT THE EDGE OF TRAVEL LANE) AND THE PROJECTED EDGE OF DRIVEWAY TO EITHER OF THE ARC TANGENT POINTS (SAME DISTANCE ALONG THE OFFSET LINE OR ALONG THE PROJECTED EDGE OF DRIVEWAY).
- STEP 6. FIND THE DRIVEWAY OPENING LIMIT POINT WHICH IS WHERE THE ARC INTERSECTS THE HIGHWAY EDGE OF PAVEMENT.
- STEP 7. REPEAT STEPS 1 - 6 FOR THE OTHER SIDE OF THE DRIVEWAY OPENING.

FIELD LAYOUT NOTES:

FOR THE RADIUS METHOD OF LAYOUT, IF OBSTRUCTIONS HINDER THE ABILITY TO SCRIBE THE CORNER ANGLE ARC FROM THE CENTER POINT, LOCATE POINTS ALONG THE ARC BY USING "Y" VALUES FROM TABLES 9 THROUGH 11 ON SHEET 4 AT VARIOUS DRIVEWAY OFFSETS ("Y" IS MEASURED FROM THE PROJECTED EDGE OF DRIVEWAY TO THE ARC).

TAPER METHOD OF LAYOUT:

TAPER METHOD OF LAYOUT IS NOT RECOMMENDED FOR DRIVEWAYS WITH CORNER ANGLES LESS THAN 80° OR GREATER THAN 100°, NOR IS IT RECOMMENDED FOR DRIVEWAYS WITH A DRIVEWAY OFFSET (OUTER TRAVEL LANE + PAVED SHOULDER) LESS THAN 16', UNLESS IT CAN BE FIELD VERIFIED THAT THE DRIVEWAY ENTRANCE WIDTH WILL ACCOMMODATE THE VEHICLES THAT USE THE DRIVEWAY ON A REGULAR BASIS.

- STEP 1. SCRIBE A LINE (LAYOUT LINE) OFFSET THE APPROPRIATE 'LAYOUT DISTANCE' (SEE TABLE 8) FROM THE INSIDE EDGE OF THE OUTERMOST TRAVEL LANE.
- STEP 2. LOCATE THE TAPER LAYOUT POINT, WHICH IS AT THE INTERSECTION OF THE EDGE OF DRIVEWAY AND THE LAYOUT LINE.
- STEP 3. SCRIBE A 1:T' (SEE TABLE 8) TAPER FROM THE LAYOUT POINT TO THE EDGE OF PAVEMENT (WITH 'T' BEING PERPENDICULAR TO THE EDGE OF TRAVEL LANE).
- STEP 4. FIND THE DRIVEWAY OPENING LIMIT POINT WHICH IS WHERE THE TAPER INTERSECTS THE EDGE OF PAVEMENT.
- STEP 5. REPEAT STEPS 1 - 4 FOR THE OTHER SIDE OF THE DRIVEWAY OPENING.

ALTERNATE TAPER METHOD OF LAYOUT:

FOLLOW THE STEPS AS PER THE ABOVE TAPER LAYOUT METHOD, EXCEPT FOR STEPS 3 AND 4. LOCATE THE DRIVEWAY OPENING LIMIT BY USING THE APPROPRIATE "Y" VALUE FROM EITHER TABLE 12 OR 13 ON SHEET 4. "Y" IS THE DISTANCE BETWEEN THE DRIVEWAY OPENING LIMIT AND THE INTERSECTION POINT OF THE PROJECTED EDGE OF DRIVEWAY AND THE EDGE OF PAVEMENT.

| DRIVEWAY CLASSIFICATION | "R" |
|-------------------------------|-----|
| RESIDENTIAL "W" ≤ 13' | 16' |
| RESIDENTIAL "W" > 13' | 13' |
| MINOR COMMERCIAL (ALL WIDTHS) | 33' |


| CORNER ANGLE | "X" FT. | | |
|--------------|---|---|-----------------------------------|
| | RESIDENTIAL DRIVEWAY ≤ 13' WIDE (R=16') | RESIDENTIAL DRIVEWAY > 13' WIDE (R=13') | MINOR COMMERCIAL DRIVEWAY (R=33') |
| 60° | 27.7 | 22.5 | 57.2 |
| 65° | 25.1 | 20.4 | 51.8 |
| 70° | 22.8 | 18.6 | 47.1 |
| 75° | 20.8 | 16.9 | 43.0 |
| 80° | 19.1 | 15.5 | 39.3 |
| 85° | 17.5 | 14.2 | 36.0 |
| 90° | 16.0 | 13.0 | 33.0 |
| 95° | 14.7 | 11.9 | 30.2 |
| 100° | 13.4 | 10.9 | 27.7 |
| 105° | 12.3 | 10.0 | 25.3 |
| 110° | 11.2 | 9.1 | 23.1 |
| 115° | 10.2 | 8.3 | 21.0 |
| 120° | 9.2 | 7.5 | 19.0 |

| DRIVEWAY CLASSIFICATION | TAPER (1:T') | LAYOUT DISTANCE |
|-------------------------|--------------|-----------------|
| RESIDENTIAL | 1:2 | 28' |
| MINOR COMMERCIAL | 1:1½ | 41' |

LAYOUT DISTANCE IS MEASURED FROM THE INSIDE EDGE OF OUTERMOST TRAVEL LANE, TO THE LAYOUT LINE.


SEE GENERAL NOTE 15.

"X" REFERS TO EITHER "X"_{IN} OR "X"_{OUT}. THE CORNER ANGLE FOR "X"_{IN} + "X"_{OUT} IS EQUAL TO 180°.



RADIUS LAYOUT

VALID FOR RESIDENTIAL OR MINOR COMMERCIAL DRIVEWAYS (FOR THE VALUES OF "R" AND "X" SEE TABLES 6 AND 7, RESPECTIVELY)



TAPER LAYOUT

VALID FOR RESIDENTIAL OR MINOR COMMERCIAL DRIVEWAYS (FOR THE VALUE OF "T" SEE TABLE 8)

NOTE:
ALL GENERAL NOTES AND ABBREVIATIONS REFERENCED ON THIS SHEET CAN BE FOUND ON STANDARD SHEET 608-03, SHEET 1 OF 9.

| | | |
|--|--|---------------|
| <p>NEW YORK STATE OF OPPORTUNITY.</p> | <p>Department of Transportation</p> | |
| | <p>U.S. CUSTOMARY STANDARD SHEET</p> | |
| <p>RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 3 OF 9)</p> | | |
| <p>APPROVED MARCH 07, 2016 /S/ RICHARD W. LEE, P.E. DEPUTY CHIEF ENGINEER (DESIGN)</p> | <p>ISSUED UNDER EB 16-012</p> | <p>608-03</p> |

TABLE 9
DRIVEWAY OPENING "Y" (FT.) VALUES FOR RADIUS METHOD
RESIDENTIAL DRIVEWAYS ≤ 13' WIDE (R=16')

| CORNER ANGLE | DRIVEWAY OFFSET FROM INSIDE EDGE OF TRAVEL LANE (OR OFFSET FROM OUTSIDE EDGE OF A 12' TRAVEL LANE) | | | | | | | | | | |
|--------------|--|----------|----------|----------|----------|----------|----------|----------|----------|----------|-----------|
| | 12' (0') | 13' (1') | 14' (2') | 15' (3') | 16' (4') | 17' (5') | 18' (6') | 19' (7') | 20' (8') | 21' (9') | 22' (10') |
| 60° | 22.3 | 19.7 | 17.4 | 15.7 | 14.1 | 12.5 | 11.2 | 9.8 | 8.9 | 7.9 | 6.9 |
| 65° | 19.7 | 17.1 | 15.1 | 13.5 | 11.8 | 10.5 | 9.2 | 8.2 | 7.2 | 6.2 | 5.2 |
| 70° | 17.7 | 15.1 | 13.1 | 11.5 | 10.2 | 8.9 | 7.9 | 6.6 | 5.9 | 4.9 | 4.3 |
| 75° | 15.7 | 13.1 | 11.5 | 9.8 | 8.5 | 7.2 | 6.2 | 5.2 | 4.6 | 3.9 | 3.3 |
| 80° | 14.1 | 11.5 | 9.8 | 8.5 | 7.2 | 5.9 | 5.2 | 4.3 | 3.6 | 3.0 | 2.3 |
| 85° | 12.5 | 10.2 | 8.5 | 6.9 | 5.9 | 4.9 | 3.9 | 3.3 | 2.6 | 2.0 | 1.6 |
| 90° | 10.8 | 8.9 | 7.2 | 5.9 | 4.9 | 3.9 | 3.3 | 2.6 | 2.0 | 1.6 | 1.0 |
| 95° | 9.5 | 7.5 | 5.9 | 4.9 | 3.9 | 3.0 | 2.3 | 2.0 | 1.3 | 1.0 | 0.7 |
| 100° | 8.5 | 6.6 | 4.9 | 3.9 | 3.0 | 2.3 | 1.6 | 1.3 | 1.0 | 0.7 | 0.3 |
| 105° | 7.2 | 5.6 | 4.3 | 3.0 | 2.3 | 1.6 | 1.3 | 0.7 | 0.7 | 0.3 | 0.0 |
| 110° | 6.6 | 4.6 | 3.3 | 2.3 | 1.6 | 1.0 | 0.7 | 0.3 | 0.3 | 0.0 | 0.0 |
| 115° | 5.6 | 3.6 | 2.6 | 1.6 | 1.0 | 0.7 | 0.3 | 0.3 | 0.0 | 0.0 | 0.0 |
| 120° | 4.6 | 3.0 | 2.0 | 1.3 | 0.7 | 0.3 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |

TABLE 10
DRIVEWAY OPENING "Y" (FT.) VALUES FOR RADIUS METHOD
RESIDENTIAL DRIVEWAYS > 13' WIDE (R=16')

| CORNER ANGLE | DRIVEWAY OFFSET FROM INSIDE EDGE OF TRAVEL LANE (OR OFFSET FROM OUTSIDE EDGE OF A 12' TRAVEL LANE) | | | | | | | | | | |
|--------------|--|----------|----------|----------|----------|----------|----------|----------|----------|----------|-----------|
| | 12' (0') | 13' (1') | 14' (2') | 15' (3') | 16' (4') | 17' (5') | 18' (6') | 19' (7') | 20' (8') | 21' (9') | 22' (10') |
| 60° | 17.4 | 14.8 | 12.8 | 11.2 | 9.8 | 8.5 | 7.2 | 6.2 | 5.2 | 4.6 | 3.6 |
| 65° | 15.4 | 12.8 | 11.2 | 9.5 | 8.2 | 6.9 | 5.9 | 4.9 | 4.3 | 3.3 | 2.6 |
| 70° | 13.5 | 11.2 | 9.5 | 8.2 | 6.9 | 5.9 | 4.9 | 3.9 | 3.3 | 2.6 | 2.0 |
| 75° | 12.1 | 9.8 | 8.2 | 6.9 | 5.6 | 4.6 | 3.9 | 3.0 | 2.3 | 2.0 | 1.3 |
| 80° | 10.8 | 8.5 | 6.9 | 5.9 | 4.6 | 3.6 | 3.0 | 2.3 | 2.0 | 1.3 | 1.0 |
| 85° | 9.2 | 7.2 | 5.9 | 4.6 | 3.6 | 3.0 | 2.3 | 1.6 | 1.3 | 1.0 | 0.7 |
| 90° | 8.2 | 6.2 | 4.9 | 3.9 | 3.0 | 2.3 | 1.6 | 1.3 | 1.0 | 0.7 | 0.3 |
| 95° | 7.2 | 5.2 | 4.3 | 3.3 | 2.3 | 1.6 | 1.3 | 0.7 | 0.3 | 0.3 | 0.0 |
| 100° | 6.2 | 4.6 | 3.3 | 2.3 | 1.6 | 1.3 | 0.7 | 0.3 | 0.3 | 0.0 | 0.0 |
| 105° | 5.6 | 3.9 | 2.6 | 2.0 | 1.3 | 0.7 | 0.3 | 0.3 | 0.0 | 0.0 | 0.0 |
| 110° | 4.6 | 3.3 | 2.0 | 1.3 | 1.0 | 0.3 | 0.3 | 0.0 | 0.0 | 0.0 | 0.0 |
| 115° | 3.9 | 2.6 | 1.6 | 1.0 | 0.7 | 0.3 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 120° | 3.3 | 2.0 | 1.0 | 0.7 | 0.3 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |

TABLE 11
DRIVEWAY OPENING "Y" (FT.) VALUES FOR RADIUS METHOD
MINOR COMMERCIAL DRIVEWAYS (R=33')

| CORNER ANGLE | DRIVEWAY OFFSET FROM INSIDE EDGE OF TRAVEL LANE (OR OFFSET FROM OUTSIDE EDGE OF A 12' TRAVEL LANE) | | | | | | | | | | |
|--------------|--|----------|----------|----------|----------|----------|----------|----------|----------|----------|-----------|
| | 12' (0') | 13' (1') | 14' (2') | 15' (3') | 16' (4') | 17' (5') | 18' (6') | 19' (7') | 20' (8') | 21' (9') | 22' (10') |
| 60° | 48.2 | 44.6 | 41.7 | 39.0 | 36.7 | 34.8 | 32.8 | 31.2 | 29.5 | 27.9 | 26.2 |
| 65° | 43.3 | 39.4 | 36.7 | 34.1 | 32.2 | 30.2 | 28.2 | 26.6 | 24.9 | 23.6 | 22.3 |
| 70° | 38.7 | 35.1 | 32.2 | 29.9 | 27.9 | 25.9 | 24.3 | 22.6 | 21.0 | 19.4 | 18.7 |
| 75° | 34.8 | 31.2 | 28.5 | 26.2 | 24.3 | 22.6 | 21.0 | 19.4 | 18.0 | 16.7 | 15.7 |
| 80° | 31.2 | 27.6 | 24.9 | 23.0 | 21.0 | 19.4 | 17.7 | 16.4 | 15.1 | 14.1 | 12.8 |
| 85° | 27.9 | 24.6 | 22.0 | 20.0 | 18.0 | 16.7 | 15.1 | 13.8 | 12.8 | 11.5 | 10.5 |
| 90° | 24.9 | 21.7 | 19.4 | 17.4 | 15.7 | 14.1 | 12.8 | 11.5 | 10.5 | 9.5 | 8.5 |
| 95° | 22.3 | 19.0 | 16.7 | 14.8 | 13.5 | 11.8 | 10.5 | 9.5 | 8.5 | 7.5 | 6.9 |
| 100° | 19.7 | 16.7 | 14.4 | 12.8 | 11.2 | 9.8 | 8.9 | 7.5 | 6.6 | 5.9 | 5.2 |
| 105° | 17.7 | 14.8 | 12.5 | 10.8 | 9.2 | 8.2 | 6.9 | 5.9 | 5.2 | 4.6 | 3.9 |
| 110° | 15.4 | 12.5 | 10.5 | 8.9 | 7.5 | 6.6 | 5.6 | 4.6 | 3.9 | 3.3 | 2.6 |
| 115° | 13.5 | 10.8 | 8.9 | 7.2 | 5.9 | 4.9 | 4.3 | 3.3 | 2.6 | 2.3 | 1.6 |
| 120° | 11.5 | 8.9 | 7.2 | 5.6 | 4.6 | 3.6 | 3.0 | 2.3 | 1.6 | 1.3 | 1.0 |

TABLE 12
DRIVEWAY OPENING "Y" (FT.) VALUES FOR TAPER METHOD
RESIDENTIAL DRIVEWAYS

| CORNER ANGLE | DRIVEWAY OFFSET FROM INSIDE EDGE OF TRAVEL LANE (OR OFFSET FROM OUTSIDE EDGE OF A 12' TRAVEL LANE) | | | | | | | | | | |
|--------------|--|------------|------------|------------|----------|----------|----------|----------|----------|----------|-----------|
| | 12' * (0') | 13' * (1') | 14' * (2') | 15' * (3') | 16' (4') | 17' (5') | 18' (6') | 19' (7') | 20' (8') | 21' (9') | 22' (10') |
| 80° | 11.2 | 10.5 | 9.8 | 9.2 | 8.5 | 7.9 | 7.2 | 6.6 | 5.9 | 5.2 | 4.6 |
| 85° | 9.8 | 9.2 | 8.5 | 7.9 | 7.5 | 6.9 | 6.2 | 5.6 | 5.2 | 4.6 | 3.9 |
| 90° | 8.2 | 7.9 | 7.2 | 6.9 | 6.2 | 5.9 | 5.2 | 4.9 | 4.3 | 3.9 | 3.3 |
| 95° | 6.9 | 6.6 | 6.2 | 5.6 | 5.2 | 4.9 | 4.3 | 3.9 | 3.6 | 3.3 | 3.0 |
| 100° | 5.6 | 5.2 | 4.9 | 4.6 | 4.3 | 3.9 | 3.6 | 3.3 | 3.0 | 2.6 | 2.3 |

* SEE NOTE 6

TABLE 13
DRIVEWAY OPENING "Y" (FT.) VALUES FOR TAPER METHOD
MINOR COMMERCIAL DRIVEWAYS

| CORNER ANGLE | DRIVEWAY OFFSET FROM INSIDE EDGE OF TRAVEL LANE (OR OFFSET FROM OUTSIDE EDGE OF A 12' TRAVEL LANE) | | | | | | | | | | |
|--------------|--|------------|------------|------------|----------|----------|----------|----------|----------|----------|-----------|
| | 12' * (0') | 13' * (1') | 14' * (2') | 15' * (3') | 16' (4') | 17' (5') | 18' (6') | 19' (7') | 20' (8') | 21' (9') | 22' (10') |
| 80° | 24.9 | 24.3 | 23.3 | 22.6 | 21.7 | 21.0 | 20.0 | 19.4 | 18.4 | 17.4 | 16.7 |
| 85° | 22.3 | 21.7 | 21.0 | 20.0 | 19.4 | 18.7 | 18.0 | 17.1 | 16.4 | 15.7 | 15.1 |
| 90° | 19.7 | 19.0 | 18.4 | 17.7 | 17.1 | 16.4 | 15.7 | 15.1 | 14.4 | 13.8 | 13.1 |
| 95° | 17.4 | 16.7 | 16.1 | 15.4 | 15.1 | 14.4 | 13.8 | 13.1 | 12.8 | 12.1 | 11.5 |
| 100° | 14.8 | 14.1 | 13.8 | 13.1 | 12.8 | 12.1 | 11.8 | 11.2 | 10.8 | 10.2 | 9.8 |

* SEE NOTE 6

TABLE 14
DRIVEWAY OPENING WIDTH CALCULATION

DRIVEWAY OPENING WIDTH = "Y"_{IN} + ("W" x "SK") + "Y"_{OUT}

| CORNER ANGLE | 60°/120° | 65°/115° | 70°/110° | 75°/105° | 80°/100° | 85°/95° | 90° |
|--------------|----------|----------|----------|----------|----------|---------|------|
| SK | 1.16 | 1.10 | 1.07 | 1.04 | 1.02 | 1.01 | 1.00 |

IF THE DRIVEWAY IS A ONE-WAY ENTRANCE OR EXIT, THEN "Y" OUT OR "Y" IN, RESPECTIVELY, IS NOT INCLUDED IN THE EQUATION. HOWEVER FOR CURBED HIGHWAYS, ADDITIONAL DRIVEWAY OPENING WIDTH SHOULD BE ADDED TO ALLOW FOR A SMALL CORNER CURB RADIUS. THIS ELIMINATES SHARP CORNER BENDS IN THE CURB LINE, WHICH IS SAFER FOR SNOWPLOW OPERATIONS.


SAMPLE CALCULATION:

A 10' WIDE RESIDENTIAL DRIVEWAY CONNECTS WITH A CORNER ANGLE OF 70° TO A HIGHWAY WITH A 12' WIDE TRAVEL LANE AND 4' PAVED SHOULDER. THE CORNER ANGLE IS OUTSIDE OF THE RANGE FOR THE TAPER METHOD, THEREFORE THE RADIUS METHOD IS USED. IN THIS INSTANCE, THE DRIVEWAY OFFSET EQUALS 16'. THIS WOULD REQUIRE A DRIVEWAY OPENING WIDTH = "Y"_{70°} + ("W" x "SK") + "Y"_{110°}

$$= 10.2' + (10' \times 1.07) + 1.6' = 22.5'$$

FIELD LAYOUT:

- STEP 1. LOCATE THE INTERSECTION POINTS OF THE PROJECTED EDGES OF DRIVEWAY AND THE EDGE OF PAVEMENT.
- STEP 2. ALONG THE EDGE OF PAVEMENT, MEASURE OUT FROM THE INTERSECTION POINTS AT DISTANCES "Y"_{IN} AND "Y"_{OUT} RESPECTIVELY TO LOCATE THE DRIVEWAY OPENING LIMITS.




PRELIMINARY DRIVEWAY OPENING LAYOUT


ALTHOUGH THE DETAIL ONLY SHOWS A RADIUS ENTRANCE TYPE, THE DETAIL APPLIES TO BOTH RADIUS AND TAPER METHODS OF LAYOUT. FOR THE VALUES OF "Y" REFER TO TABLES 9 THROUGH 13. FOR THE VALUE OF "SK" REFER TO TABLE 14.

NOTE:
ALL GENERAL NOTES AND ABBREVIATIONS REFERENCED ON THIS SHEET CAN BE FOUND ON STANDARD SHEET 608-03, SHEET 1 OF 9.

| | |
|---|--|
| <p>NEW YORK STATE OF OPPORTUNITY.</p> | <p>Department of Transportation</p> |
| U.S. CUSTOMARY STANDARD SHEET | |
| RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 4 OF 9) | |
| APPROVED MARCH 07, 2016 | ISSUED UNDER EB 16-012 |
| /S/ RICHARD W. LEE, P.E. DEPUTY CHIEF ENGINEER (DESIGN) | 608-03 |






TYPE 1 DRIVEWAY ENTRANCE
 NOTE: SEE RADIUS METHOD OF LAYOUT ON SHEET 3




TYPE 2 DRIVEWAY ENTRANCE
 MINOR COMMERCIAL ONLY
 NOTE: SEE RADIUS METHOD OF LAYOUT ON SHEET 3



NOTE:
 ALL GENERAL NOTES AND ABBREVIATIONS REFERENCED ON THIS SHEET CAN BE FOUND ON STANDARD SHEET 608-03, SHEET 1 OF 9.

| | | | |
|--|--|-------------------------------------|--|
|  NEW YORK STATE OF OPPORTUNITY. | | Department of Transportation | |
| U.S. CUSTOMARY STANDARD SHEET | | | |
| RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 5 OF 9) | | | |
| APPROVED MARCH 07, 2016 | | ISSUED UNDER EB 16-012 | |
| /S/ RICHARD W. LEE, P.E. DEPUTY CHIEF ENGINEER (DESIGN) | | 608-03 | |



NOTE:
 ALL GENERAL NOTES AND ABBREVIATIONS REFERENCED ON THIS SHEET
 CAN BE FOUND ON STANDARD SHEET 608-03, SHEET 1 OF 9.

| | |
|---|------------------------|
|  Department of Transportation | |
| U.S. CUSTOMARY STANDARD SHEET | |
| RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 6 OF 9) | |
| APPROVED MARCH 07, 2016 | ISSUED UNDER EB 16-012 |
| /S/ RICHARD W. LEE, P.E. DEPUTY CHIEF ENGINEER (DESIGN) | 608-03 |



NOTE:
 ALL GENERAL NOTES AND ABBREVIATIONS REFERENCED ON THIS SHEET
 CAN BE FOUND ON STANDARD SHEET 608-03, SHEET 1 OF 9.










U.S. CUSTOMARY STANDARD SHEET

RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS
 (SHEET 7 OF 9)


APPROVED MARCH 07, 2016
 /S/ RICHARD W. LEE, P.E.
 DEPUTY CHIEF ENGINEER
 (DESIGN)

ISSUED UNDER EB 16-012
 608-03


STANDARD SHEETS (USC), May 01, 2019




NOTES:
 ALL GENERAL NOTES AND ABBREVIATIONS REFERENCED ON THIS SHEET CAN BE FOUND ON STANDARD SHEET 608-03, SHEET 1 OF 9.
 DETAILS SHOWN ON THIS SHEET SHALL BE USED FOR RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS ONLY, CURB RAMPS SHALL BE USED AT MAJOR COMMERCIAL DRIVEWAYS, PUBLIC HIGHWAYS, AND STREETS. REFER TO SHEET 1 FOR THE DEFINITION OF MAJOR AND MINOR COMMERCIAL DRIVEWAYS.

| | |
|---|------------------------|
|  Department of Transportation | |
| U.S. CUSTOMARY STANDARD SHEET | |
| RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 8 OF 9) | |
| APPROVED MARCH 07, 2016 | ISSUED UNDER EB 16-012 |
| /S/ RICHARD W. LEE, P.E. DEPUTY CHIEF ENGINEER (DESIGN) | 608-03 |


FILE NAME = 608-0308.dgn
 DATE/TIME = 08-MAR-2016 14:59
 USER = jmontgomery




DETAIL 8
TYPICAL DRIVEWAY ENTRANCE
LIMITS OF SHOULDER RECONSTRUCTION



DETAIL 9
TIE-IN TO EXISTING DRIVEWAYS
FOR HOT MIX ASPHALT (HMA)



DETAIL 10
SHOULDER AND DRIVEWAY RECONSTRUCTION
PROFILE FOR HOT MIX ASPHALT (HMA) SHOULDER



DETAIL 11
SHOULDER AND DRIVEWAY RECONSTRUCTION
PROFILE FOR PCC SHOULDER

NOTE:

ALL GENERAL NOTES AND ABBREVIATIONS REFERENCED ON THIS SHEET CAN BE FOUND ON STANDARD SHEET 608-03, SHEET 1 OF 9.



U.S. CUSTOMARY STANDARD SHEET


RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS
(SHEET 9 OF 9)

APPROVED MARCH 07, 2016


/S/ RICHARD W. LEE, P.E.
DEPUTY CHIEF ENGINEER
(DESIGN)

ISSUED UNDER EB 16-012


608-03




PLAN VIEW WITHOUT OPTIONAL DRAINAGE TREATMENT




PLAN VIEW WITH OPTIONAL DRAINAGE TREATMENT (SEE NOTE 2)




LONGITUDINAL TRANSITION AREA - HOT MIX ASPHALT OVERLAY SPLICE




TRANSVERSE TRANSITION AREA - HOT MIX ASPHALT OVERLAY SPLICE (SEE NOTE 2)



SECTION A-A WITH OR WITHOUT OPTIONAL DRAINAGE TREATMENT



SECTION B-B WITHOUT OPTIONAL DRAINAGE TREATMENT



SECTION C-C WITH OPTIONAL DRAINAGE TREATMENT (SEE NOTE 2)

NOTES:

1. RAISED CROSSWALK REQUIRES STORM WATER TO BE COLLECTED AND CONVEYED TO AN APPROPRIATE LOCATION.
2. THE OPTIONAL DRAINAGE TREATMENT SHALL ONLY BE USED IN RETROFIT SITUATIONS. THE TRANSVERSE TRANSITION AREA DETAIL ABOVE IS FOR USE ON HIGHWAYS WITH CROSS SLOPES. RETROFIT RAISED CROSSWALKS ON ROADWAYS THAT EXCEEDED THIS LIMIT SHALL BE DETAILED IN THE PLANS.
3. THE TRANSITION AREA MAY BE CONCRETE OR HMA, AND WILL BE AS SHOWN ON THE PLANS.
4. ALL SURFACES OF THE MILLED TRANSITION AREA SHALL BE CLEANED. TACK-COAT SHALL BE APPLIED PRIOR TO HMA PLACEMENT. THE COST OF MILLING REBATES AND TACK COAT IN THE HMA OVERLAY SPLICE TRANSITION AREA SHALL BE PAID FOR UNDER THEIR RESPECTIVE ITEMS. THE COST OF LEAVING A NEAT EDGE SHALL BE INCLUDED IN THE MILLING ITEM.
5. SEE SHEET 2 OF 3 FOR PCC RAISED CROSSWALK DETAILS.
6. SEE SHEET 3 OF 3 FOR SIGNING AND PAVEMENT MARKING DETAILS.
7. SIGNING AND PAVEMENT MARKINGS SHALL BE IN ACCORDANCE WITH THE MUTCD.
8. FOR CONTRAST OR AESTHETICS, A TYPE S CROSSWALK PAVEMENT MARKING MAY BE USED WITH A COLORED OR TEXTURED CROSSWALK SURFACE.




U.S. CUSTOMARY STANDARD SHEET

RAISED CROSSWALK DETAILS (SHEET 1 OF 3)


APPROVED MARCH 07, 2016
/S/ RICHARD W. LEE, P.E.
DEPUTY CHIEF ENGINEER (DESIGN)

ISSUED UNDER EB 16-012


608-07




CAST IN PLACE CONCRETE
RAISED CROSSWALK REINFORCEMENT PLAN
(SEE NOTE 9)




SECTION A-A
HIGHWAY PROFILE



SECTION B-B
HIGHWAY CROSS SECTION



OPTIONAL TRANSITION AREA
FOR PCC OVERLAY SPLICE ON FULL DEPTH HMA
(SEE NOTE 6)



TRANSITION AREA - FULL DEPTH
(SEE NOTE 8)

NOTES:

1. GROUT BETWEEN GRANITE/PRECAST CURBS AND CONCRETE PAVEMENT SHALL MEET STANDARD SPECIFICATION 705.21 FOR TYPE S MASONRY MORTAR. CAULKING SHALL CONFORM TO REQUIREMENTS OF CAULKING COMPOUND FOR DRAINAGE STRUCTURES.
2. EXTRA LONGITUDINAL JOINT TIES, USED AS REINFORCEMENT, ARE NEEDED ONLY WHEN DRAINAGE STRUCTURES ARE PRESENT.
3. SEE NYSDOT STANDARD SHEET 502-02 FOR PROPER DOWEL BAR/TIE BAR SPACING.
4. SEE NYSDOT STANDARD SHEETS 502-03 THROUGH 502-07 FOR LONGITUDINAL AND TRANSVERSE JOINT DETAILS.
5. SIGNAGE AND PAVEMENT MARKINGS SHALL BE IN ACCORDANCE WITH THE MUTCD. SEE STANDARD SHEET 608-07 SHEET 3 OF 3 FOR SIGNING AND PAVEMENT MARKING DETAILS.
6. MAY BE USED FOR HIGHWAYS WITH $\leq 20,000$ ADT, $\leq 5\%$ TRUCKS, AND A PAVEMENT SURFACE SCORE OF 7 OR GREATER.
7. DETERMINE PCC THICKNESS (D) FROM THE CONTRACT DOCUMENTS.
8. FOR PCC PAVEMENT, COMPOSITE PAVEMENTS, AND HMA PAVEMENTS NOT MEETING NOTE 6, FULL DEPTH REPLACEMENT IS REQUIRED.
9. SEE CURB & GUTTER STANDARD SHEETS FOR ANCHOR REQUIREMENTS, IF APPLICABLE.



U.S. CUSTOMARY STANDARD SHEET


RAISED CROSSWALK DETAILS
(SHEET 2 OF 3)

APPROVED MARCH 07, 2016


ISSUED UNDER EB 16-012

/S/ RICHARD W. LEE, P.E.
DEPUTY CHIEF ENGINEER
(DESIGN)


608-07




MIDBLOCK RAISED CROSSWALK
 ADVANCE PAVEMENT MARKING DETAIL
 TWO LANE



MIDBLOCK RAISED CROSSWALK
 ADVANCE PAVEMENT MARKING DETAIL
 FOUR LANE



MULTILANE
 ROUNDABOUT
 RAISED CROSSWALK




RAISED CROSSWALK APPROACH
 PAVEMENT MARKING DETAIL


NOTES:

1. FOR CONTRAST OR AESTHETICS, TYPE S CROSSWALK PAVEMENT MARKING MAY BE USED WITH A COLORED OR TEXTURED CROSSWALK SURFACE.
2. FOR ONE-WAY TRAFFIC, PAVEMENT MARKING SHALL BE PLACED ON APPROACH SIDE ONLY.
3. REFER TO THE MUTCD FOR ADDITIONAL ADVANCED WARNING SIGNS, TYPE AND LOCATION.
4. FOR CONCRETE RAISED CROSSWALKS, TERMINATE LANE MARKINGS AT THE BEGINNING OF THE LINEAR TRANSITION FOR CONCRETE, EXCEPT AT ROUNDABOUTS, WHERE LANE MARKINGS SHALL TERMINATE AT THE CROSSWALK MARKING. FOR HMA RAISED CROSSWALKS, LANE MARKINGS SHALL TERMINATE AT THE CROSSWALK MARKING.
5. FOR CROSSWALK MARKING DETAILS, REFER TO STANDARD SHEET 685-01, SHEET 2 OF 9.


| | |
|--|----------------------------------|
| | |
| Department of Transportation | |
| U.S. CUSTOMARY STANDARD SHEET | |
| RAISED CROSSWALK DETAILS (SHEET 3 OF 3) | |
| APPROVED MARCH 07, 2016 /S/ RICHARD W. LEE, P.E. DEPUTY CHIEF ENGINEER (DESIGN) | ISSUED UNDER EB 16-012 608-07 |




TYPE "A" CURB
SAWED, HAMMERED OR THERMAL
FINISH TOP, QUARRY SPLIT FACE




TYPE "B" CURB
SAWED, HAMMERED OR THERMAL
FINISH TOP AND FACE




TYPE "C" CURB
SAWED, HAMMERED OR THERMAL FINISH TOP,
QUARRY SPLIT, SAWED, HAMMERED OR THERMAL FINISH FACE




TYPE "D" CURB
SAWED, HAMMERED OR THERMAL
FINISH TOP AND FACE




TYPE "E100" CURB
SAWED, HAMMERED OR THERMAL
FINISH TOP AND FACE



LIGHT DUTY CURB
SAWED, HAMMERED OR THERMAL FINISH TOP,
QUARRY SPLIT, SAWED, HAMMERED OR THERMAL FINISH FACE



LANDSCAPING CURB
QUARRY SPLIT TOP AND FACE



TYPE "TS" CURB
QUARRY SPLIT, HAMMERED
OR THERMAL FINISH FACE

NOTES:

1. AS MARKED IN THE DETAILS ABOVE, THE FRONT ARRIS LINE FOR VERTICAL-FACED AND NEAR-VERTICAL STONE AND GRANITE CURBS SHALL BE BUZZED TO REMOVE A MINIMUM OF 1/8 INCH; MAXIMUM OF 3/8 INCH ALL ALONG THE EXPOSED EDGE.



**Department of
Transportation**


U.S. CUSTOMARY STANDARD SHEET

STONE CURB AND GRANITE CURB

APPROVED: MAY 12, 2016
/S/ RICHARD W. LEE, P.E.
DEPUTY CHIEF ENGINEER
(DESIGN)


ISSUED UNDER EB 16-019

609-01




CAST-IN-PLACE CONCRETE CURB TRANSITIONS
 (SEE NOTE 2)

| CURB TRANSITION LENGTHS (L) | | | |
|-----------------------------|-----|------|------|
| H \ SLOPE | 1:4 | 1:12 | 1:20 |
| 4" | 16" | 48" | 80" |
| 6" | 24" | 72" | 120" |



PRECAST CONCRETE, STONE, AND GRANITE CURB TRANSITIONS
 (SEE NOTE 2)


| CURB TRANSITION LENGTHS (L) WITH CURB REVEAL | | | |
|--|-----|------|------|
| H \ SLOPE | 1:4 | 1:12 | 1:20 |
| 4" | 12" | 36" | 60" |
| 6" | 20" | 60" | 100" |




CURB AND CURB BOX ADJACENT TO CONCRETE SIDEWALK
 (NOT ON STRUCTURES)

| STANDARD PRECAST CURB RADII IN INCHES |
|---------------------------------------|
| 12" BULLNOSE * |
| 18" BULLNOSE * |
| 24" HALF BULLNOSE* |
| 30" HALF BULLNOSE |
| 60" |
| 72" * |
| 120" |
| 180" |
| 240" |
| 300" |
| 360" |
| 420" * |
| 480" |
| 540" * |
| 600" |
| 720" |
| 840" |
| 960" |
| 1080" |

* NOT ALL PRECASTERS MANUFACTURE THESE RADII




CURVED CURB (CONVEX)




BULLNOSE

MOUNTABLE CURB


VERTICAL FACED CURB



CURVED CURB (CONCAVE)



1/2 BULLNOSE MOUNTABLE CURB



1/2 BULLNOSE VERTICAL FACED CURB

NOTES:

- USE 1" REVEAL AND CONTINUE CURB ACROSS DRIVEWAY ENTRANCES ONLY IF SHOWN IN THE CONTRACT DOCUMENTS, OR DIRECTED BY THE ENGINEER AS A FIELD CONDITION.
- TERMINATE CURB, CURB AND GUTTER AND ASPHALT CURB BY TRANSITIONING ON A MAXIMUM SLOPE OF 1:12 TO PAVEMENT SURFACE, EXCEPT WHEN BEHIND GUIDE RAIL.
- EXTEND JOINT FILLER 6" MINIMUM BEHIND CURB ON BOTH SIDES OF CURB BOX. 705-07 NOT NEEDED WHEN VERTICAL FACED CURB WIDTH EQUAL TO WIDTH OF CURB BOX.



STATE OF NEW YORK
 DEPARTMENT OF TRANSPORTATION

U.S. CUSTOMARY STANDARD SHEET

MISCELLANEOUS CURB DETAILS


APPROVED: JUNE 14, 2013

/S/ RICHARD W. LEE, P.E.
 ACTING DEPUTY CHIEF ENGINEER
 (DESIGN)


ISSUED UNDER EB 13-007

609-02


EFFECTIVE DATE: 01/09/14




TYPE VF150
(VERTICAL FACED CURB WITHOUT CURB ANCHOR)
(SEE NOTE 4)




TYPE M150
(MOUNTABLE CURB WITHOUT CURB ANCHOR)
(SEE NOTE 5)




TYPE M100
(MOUNTABLE CURB WITHOUT CURB ANCHOR)




TYPE T100
(TRAVERSABLE CURB)




CURB ANCHOR
(NEW CURB BY EXISTING PAVEMENT)




TYPE VF150A
(VERTICAL FACED CURB WITH CURB ANCHOR)
(SEE CURB ANCHOR DETAILS)
(SEE NOTE 4)




TYPE M150A
(VERTICAL FACED CURB WITH CURB ANCHOR)
(SEE CURB ANCHOR DETAILS)
(SEE NOTE 5)




TYPE M100A
(MOUNTABLE CURB WITH CURB ANCHOR)
(SEE CURB ANCHOR DETAILS)



CURB ANCHOR
(NEW CONSTRUCTION)
(SEE NOTE 2)




TYPE PVF150
(VERTICAL FACED CURB) **TYPE PM100**
(MOUNTABLE CURB)
PRECAST CONCRETE CURB




TYPE PT100
(TRAVERSABLE CURB)
PRECAST CONCRETE CURB

CAST-IN-PLACE CONCRETE CURB




TYPE VF150G
(VERTICAL FACED CURB AND GUTTER)




TYPE M100G
(MOUNTABLE CURB AND GUTTER)


CAST-IN-PLACE CONCRETE CURB AND GUTTER



PRECAST CONCRETE, STONE, AND GRANITE CURB WITH FLEXIBLE PAVEMENT BEDDING AND BACKFILL




PRECAST CONCRETE, STONE, AND GRANITE CURB WITH RIGID PAVEMENT BEDDING AND BACKFILL



VERTICAL FACED TYPE

HOT MIX ASPHALT CURB

AREA = 40.2 SQ.IN.
VOL./LF = 0.279 C.F.



MOUNTABLE TYPE


AREA = 34.4 SQ.IN.
VOL./LF = 0.239 C.F.

NOTES:


- USE CURB AND CURB AND GUTTER MEETING THE MATERIAL AND CONSTRUCTION REQUIREMENTS OF SECTION 609 OF THE STANDARD SPECIFICATIONS.
- CURB ANCHOR (NEW CONSTRUCTION). THIS DETAIL SHOWS PLACEMENT OF CURB ANCHORS. PUSH-IN TYPE ANCHORS MAY BE USED (SHOWN ON THE STANDARD SHEET FOR LONGITUDINAL TIES).
- CURB TYPES M150A, VF150A AND M100A REQUIRE CURB ANCHOR. CURB AND GUTTER TYPES VF150G AND M100G REQUIRE ANCHORS WHEN PLACED ADJACENT TO CONCRETE PAVEMENT OR SHOULDER.
- WHEN VERTICAL FACED CURB LESS THAN 9" WIDE IS USED WITH CURB BOXES CU1, CU2, AND CU3 AND CONCRETE SIDEWALK IS PLACED ADJACENT TO THIS CURB, SEE STANDARD SHEET MISCELLANEOUS CURB DETAILS FOR CURB BOX JOINTS.
- USE WITH CURB BOXES, CM1, CM2, AND CM3.

EFFECTIVE DATE: 01/08/09


| | |
|---|---|
| | STATE OF NEW YORK DEPARTMENT OF TRANSPORTATION |
| | U.S. CUSTOMARY STANDARD SHEET |
| CONCRETE CURB, CURB AND GUTTER, AND HOT MIX ASPHALT CURB | |
| APPROVED SEPTEMBER 19, 2008 /S/ DANIEL D'ANGELO, P.E. DEPUTY CHIEF ENGINEER (DESIGN) | ISSUED UNDER EB 08-036 609-03 |



BOTTOM FRAME
TOP VIEW




TEMPORARY WOODEN SIGN STAND
TOP VIEW




CORNER BRACE DETAIL
(TO BE USED ON UPRIGHT AND BOTTOM FRAMES)

NOTES:


1. ALL LUMBER SHALL BE 2 X 4 DIMENSIONAL LUMBER. CONNECT FRAME MEMBERS WITH 2 EACH 12D COATED NAILS.
2. ALL HOLES SHALL BE DRILLED IN CENTERLINE OF FRAME MEMBERS AND DIAGONAL BRACES.
3. 6" BLOCK SPACER MAY BE USED BETWEEN DIAGONAL BRACE AND VERTICAL SUPPORT.
4. CONNECT FRAME CORNER BRACES TO FRAME MEMBERS WITH 6 EACH - 8D COATED NAILS. (3 NAILS INTO EACH FRAME MEMBER).
5. UPRIGHT FRAME MOUNTS ON THE OUTSIDE OF THE BOTTOM FRAME.
6. PAINT SIGN SUPPORT WITH 2 COATS OF WHITE PAINT.
7. DIAGONAL SUPPORTS MOUNT INSIDE BOTH UPRIGHT AND BOTTOM FRAMES. ALL UPRIGHT DIAGONAL BRACING SHALL BE SLOPED SUCH THAT BRACING COLLAPSES DOWNWARD UPON IMPACT BY A VEHICLE.
8. A SINGLE LAYER OF BALLAST PLACED ON THE BOTTOM FRAME MAY BE USED TO PREVENT SIGNS FROM TIPPING OVER FROM WIND AND VEHICLE GUSTS.
9. NO HORIZONTAL BRACING ALLOWED BETWEEN 2' AND 5' ON UPRIGHT VERTICALS, MEASURED FROM THE BOTTOM OF THE SKID BASE.
10. 5' MINIMUM SIGN MOUNTING HEIGHT, MEASURED FROM THE BOTTOM OF THE SKID BASE TO THE BOTTOM OF THE SIGN. VERTICAL SUPPORTS SHALL BE TALL ENOUGH TO ALLOW FOR HIGHER MOUNTING HEIGHTS FOR THOSE LOCATIONS REQUIRED BY THE MUTCD (I.E. SIDEWALKS, ROADSIDE PARKING AND EMBANKMENTS).
11. CONNECTIONS ALLOW FOR THE FOLDING, TRANSPORT AND STORAGE OF THE SUPPORT. WHEN FOLDED IN THE DOWN POSITION WITHIN THE CLEAR ZONE, THE MAXIMUM ASSEMBLY HEIGHT SHALL NOT EXCEED 4'. SIMILAR NON-FOLDING SUPPORTS SHALL BE STORED OUTSIDE THE CLEAR ZONE OR BEHIND A BARRIER.
12. L = LENGTH OF BOTTOM FRAME.
W = WIDTH OF BOTTOM FRAME.




TEMPORARY WOODEN SIGN STAND
SIDE VIEW



TEMPORARY WOODEN SIGN STAND
FRONT VIEW



UPRIGHT FRAME
FRONT VIEW

| | |
|---|-------------------------------|
|  <p>STATE OF NEW YORK DEPARTMENT OF TRANSPORTATION</p> | |
| <p>U.S. CUSTOMARY STANDARD SHEET</p> | |
| <p>PORTABLE TEMPORARY WOODEN SIGN SUPPORT</p> | |
| <p>APPROVED OCTOBER 06, 2008</p> | <p>ISSUED UNDER EB 08-036</p> |
| <p>/S/ J. F. TYNAN, P.E. DEPUTY CHIEF ENGINEER (CONSTRUCTION)</p> | |
| <p>619-04</p> | |

GENERAL NOTES

1. THE TYPICAL DETAILS DEPICTED ON THE STANDARD SHEETS AND IN THE MUTCD, REFLECT THE MINIMUM REQUIREMENTS.
2. THE CONTRACTOR MUST SUBMIT TO THE ENGINEER, IN WRITING, PROPOSED REVISIONS TO THE TRAFFIC CONTROL PLAN FOR REVIEW AND APPROVAL BY THE REGIONAL DIRECTOR OR HIS/HER DESIGNEE FIVE (5) WORK DAYS PRIOR TO THE PLANNED IMPLEMENTATION OF SUCH PROPOSED REVISIONS, EXCEPT FOR CHANGES THAT ALTER THE SCOPE OF THE TRAFFIC CONTROL PLAN. SUCH CHANGES IN SCOPE MUST BE SUBMITTED TO THE ENGINEER FOR APPROVAL BY THE REGIONAL DIRECTOR OR HIS/HER DESIGNEE THIRTY (30) WORKING DAYS PRIOR TO IMPLEMENTATION OF SUCH REVISIONS.
3. THE CONTRACTOR SHALL PROVIDE THE ENGINEER, IN WRITING, WITH THE NAMES, ADDRESSES, AND TELEPHONE NUMBERS OF STAFF WHO ARE AUTHORIZED TO SECURE LABOR, MATERIALS, AND EQUIPMENT FOR EMERGENCY REPAIRS OUTSIDE NORMAL WORKING HOURS. THE ENGINEER WILL PROVIDE THE SUBMITTED INFORMATION TO REGIONAL MANAGEMENT, THE NEW YORK STATE POLICE, THE RESIDENT ENGINEER, AND THE LOCAL POLICE.

ACTIVITY AREA

1. THE CONTRACTOR SHALL MAINTAIN A MINIMUM 500' LONGITUDINAL DISTANCE BETWEEN CONSTRUCTION OPERATIONS ON ALTERNATE SIDES OF THE ROADWAY, UNLESS OTHERWISE APPROVED BY THE ENGINEER.
2. WHEN TWO OR MORE AREAS ARE ADJACENT, OVERLAP, OR ARE IN CLOSE PROXIMITY, THE CONTRACTOR SHALL ENSURE THERE ARE NO CONFLICTING SIGNS AND THAT LANE CONTINUITY IS MAINTAINED THROUGHOUT ALL WORK AREAS.

SIGNS

1. THE LOCATIONS OF THE SIGNS SHOWN ON THE WORK ZONE TRAFFIC CONTROL PLANS AND DETAILS MAY BE ADJUSTED BASED ON SIGHT DISTANCE AND OTHER CONSIDERATIONS. THE FINAL LOCATIONS OF SIGNS ARE SUBJECT TO APPROVAL OF THE ENGINEER.
2. ANY EXISTING SIGNS, INCLUDING OVERHEAD SIGNS, WHICH CONFLICT WITH THE TEMPORARY TRAFFIC CONTROL SIGN LAYOUT SHALL BE COVERED, REMOVED, STORED OR RESET, AS APPROVED BY THE ENGINEER. ALL APPROPRIATE EXISTING SIGNS SHALL BE RESTORED TO THEIR ORIGINAL CONDITION AND/OR LOCATION UNLESS OTHERWISE REPLACED IN THIS CONTRACT.
3. SIGNS AT OR NEAR INTERSECTIONS SHALL BE PLACED SO THAT THEY DO NOT OBSTRUCT A MOTORIST'S LINE OF SIGHT.
4. ALL WARNING AND REGULATORY SIGNS SHALL BE POSTED ON BOTH SIDES OF MULTI-LANE DIVIDED HIGHWAYS, MULTI-LANE RAMPS, AND ONE-WAY STREETS. IN CASES WHERE LANE RESTRICTIONS REDUCE THE TRAVEL LANE TO ONE LANE, SIGNS SHALL BE POSTED ON THE RIGHT SIDE OF THE ACTIVE TRAVEL LANE, UNLESS OTHERWISE AUTHORIZED BY THE ENGINEER.
5. SIGNS MOUNTED ON THE MEDIAN OF DIVIDED HIGHWAYS WHERE MEDIAN BARRIER IS IN PLACE MAY BE MOUNTED ON THE BARRIER WITH A SADDLE TYPE BRACKET. LAYING THE SIGN DOWN IN A HORIZONTAL POSITION IS NOT PERMITTED.
6. THE DIMENSIONS OF WORK ZONE TRAFFIC CONTROL SIGNS ARE DESCRIBED IN THE MUTCD. ANY CHANGES TO THE DIMENSIONS SHALL BE APPROVED BY THE REGIONAL DIRECTOR OR BY HIS/HER DESIGNEE.
7. NYR9-12 MAY BE USED IN PLACE OF NYR9-11.

CHANNELIZING DEVICES

1. WHERE POSSIBLE ALL CHANNELIZING AND GUIDING DEVICES ARE TO BE PLACED SO AS TO PROVIDE A MINIMUM 2' LATERAL CLEARANCE TO THE TRAVELED WAY.

PUBLIC ACCESS

1. PROPERTY OWNERS WHOSE DRIVEWAYS WILL BE MADE INACCESSIBLE SHALL BE NOTIFIED BY THE CONTRACTOR AT LEAST 24 HOURS PRIOR TO RESTRICTING USE OF THE DRIVEWAY. FOR MULTIPLE ACCESS PROPERTIES, AT LEAST ONE DRIVEWAY SHALL BE OPEN AT ALL TIMES. ACCESS SHALL BE RESTORED TO ALL DRIVEWAYS AS SOON AS POSSIBLE.
2. SUITABLE RAMPS SHALL BE INSTALLED TO MAINTAIN SMOOTH TRANSITIONS FROM RESIDENTIAL AND COMMERCIAL DRIVEWAYS TO AND FROM THE WORK AREA.

LANE CLOSURES

1. THE CONTRACTOR SHALL LOCATE LANE CLOSURES TO PROVIDE OPTIMUM VISIBILITY, I.E. BEFORE CURVES AND CRESTS, TO THE EXTENT CONDITIONS PERMIT.
2. THE ENGINEER MAY REQUIRE THAT ALL LANES BE RE-OPENED AT ANY TIME IF THE ROUTE IS NEEDED FOR EMERGENCY PURPOSES. THIS COULD INCLUDE INCIDENTS AT LOCATIONS OUTSIDE THE CONTRACT LIMITS.

LANE WIDTHS

1. UNLESS AUTHORIZED BY THE ENGINEER, THE MINIMUM LANE WIDTHS FOR WORK ZONE TRAVEL LANES SHALL BE AS FOLLOWS: FREEWAYS AND/OR EXPRESSWAYS IS 11'. THE MINIMUM LANE WIDTH FOR ALL OTHER TYPES OF ROADWAYS IS 10'.
2. THE CONTRACTOR SHALL PROVIDE A WRITTEN NOTICE TO THE ENGINEER, A MINIMUM OF 21 CALENDAR DAYS IN ADVANCE OF PERFORMING ANY WORK THAT RESULTS IN THE REDUCED WIDTH OF AN EXISTING ROADWAY, SO THAT THE ENGINEER MAY NOTIFY THE REGIONAL PERMIT ENGINEER IN A TIMELY MANNER.

BARRIER/SHADOW VEHICLES

1. BARRIER AND SHADOW VEHICLES SHALL BE REQUIRED AS PER STANDARD SHEET TITLED "WORK ZONE TRAFFIC CONTROL LEGENDS AND NOTES".
2. NO WORK ACTIVITY, EQUIPMENT, VEHICLES AND/OR MATERIALS SHALL BE LOCATED BETWEEN THE BARRIER OR SHADOW VEHICLE AND THE ACTIVE WORK AREA (ROLL AHEAD DISTANCE).
3. THE CONTRACTOR MAY BE REQUIRED TO PROVIDE A BARRIER VEHICLE IN CONJUNCTION WITH POLICE PRESENCE IN THE WORK ZONE, TO BE INCLUDED IN THE UNIT BID PRICE FOR BASIC WORK ZONE TRAFFIC CONTROL.



STATE OF NEW YORK
DEPARTMENT OF TRANSPORTATION

U.S. CUSTOMARY STANDARD SHEET

WORK ZONE TRAFFIC CONTROL
GENERAL NOTES

APPROVED SEPTEMBER 18, 2008

ISSUED UNDER EB 08-036

/S/ DAVID J. CLEMENTS, P.E.
DIRECTOR, OFFICE OF
TRAFFIC SAFETY AND MOBILITY

619-10

EFFECTIVE DATE: 01/08/09

| TABLE NY1-A BARRIER VEHICLE USE REQUIREMENTS (LONG TERM, INTERMEDIATE TERM, AND SHORT TERM STATIONARY CLOSURES) | | | | | |
|---|---|---------------------------------|---|-----------------------|-----------------------|
| CLOSURE TYPE | EXPOSURE CONDITION ¹ | USE REQUIREMENTS ^{4,5} | | | |
| | | FREEWAY | NON-FREEWAY (PRECONSTRUCTION POSTED SPEED LIMIT) | | |
| | | | ≥ 45 MPH | 35-40 MPH | ≤ 30 MPH |
| LANE CLOSURE | WORKERS ON FOOT OR IN VEHICLES EXPOSED TO TRAFFIC | REQUIRED ³ | REQUIRED ³ | REQUIRED ³ | OPTIONAL ² |
| | NON-TRAVERSABLE HAZARD (IE. EQUIPMENT, MATERIALS, EXCAVATION) ONLY NO WORKERS EXPOSED | REQUIRED ³ | REQUIRED ³ | OPTIONAL ² | OPTIONAL ² |
| SHOULDER CLOSURE | WORKERS ON FOOT OR IN VEHICLES EXPOSED TO TRAFFIC | REQUIRED ³ | REQUIRED ³ | OPTIONAL ² | OPTIONAL ² |
| | NON-TRAVERSABLE HAZARD (IE. EQUIPMENT, MATERIALS, EXCAVATION) ONLY NO WORKERS EXPOSED | REQUIRED ³ | OPTIONAL ² | OPTIONAL ² | OPTIONAL ² |

- THE EXPOSURE CONDITIONS DESCRIBED IN TABLE NY1-A ASSUMES THERE IS NO POSITIVE PROTECTION (TEMPORARY TRAFFIC BARRIER) PRESENT. WHERE WORKERS OR HAZARDS ARE PROTECTED BY A TEMPORARY TRAFFIC BARRIER, BARRIER VEHICLES ARE NOT REQUIRED.
- WHERE THE REQUIREMENT IS "OPTIONAL", EITHER A BARRIER VEHICLE OR THE STANDARD LONGITUDINAL BUFFER SPACE (TABLE 6C-2) SHALL BE PROVIDED.
- REQUIREMENTS SHALL INCLUDE PROVIDING A SEPARATE BARRIER VEHICLE FOR EACH CLOSED LANE AND EACH CLOSED PAVED SHOULDER 8' OR GREATER IN WIDTH. IF THE WORK SPACE MOVES WITHIN THE STATIONARY CLOSURE, THE BARRIER VEHICLE SHALL BE REPOSITIONED ACCORDINGLY. BARRIER VEHICLES PROTECTING NON-TRAVERSABLE HAZARDS SHALL REMAIN IN PLACE DURING BOTH WORKING AND NON-WORKING HOURS UNTIL THE HAZARD NO LONGER EXISTS. EXCEPTIONS TO THESE REQUIREMENTS MAY BE MADE, AS APPROVED BY THE REGIONAL DIRECTOR OR HIS/HER DESIGNEE WHERE BARRIER VEHICLE PLACEMENT WOULD BE INEFFECTIVE OR WOULD INTERFERE WITH THE SAFE OPERATION OF TRAFFIC.
- BARRIER VEHICLES ARE NOT REQUIRED FOR MILLING AND/OR PAVING OPERATIONS, BUT THE STANDARD LONGITUDINAL BUFFER SPACE (TABLE 6C-2) SHALL BE PROVIDED.
- BARRIER VEHICLES ARE NOT REQUIRED FOR FLAGGING OPERATIONS, BUT THE STANDARD LONGITUDINAL BUFFER SPACE (TABLE 6C-2) SHALL BE PROVIDED.

| TABLE NY1-B SHADOW VEHICLE USE REQUIREMENTS (MOBILE CLOSURES) | | | | | |
|---|---|-------------------------|---|-------------------------|-------------------------|
| CLOSURE TYPE | EXPOSURE CONDITION | USE REQUIREMENTS | | | |
| | | FREEWAY | NON-FREEWAY (PRECONSTRUCTION POSTED SPEED LIMIT) | | |
| | | | ≥ 45 MPH | 35-40 MPH | ≤ 30 MPH |
| LANE CLOSURE | WHEN ANY WORKER, VEHICLE, OR OTHER HAZARD IS EXPOSED TO TRAFFIC | REQUIRED ^{2,4} | REQUIRED ^{2,4} | REQUIRED ^{2,4} | REQUIRED ^{2,4} |
| SHOULDER CLOSURE | WHEN ANY WORKER, VEHICLE, OR OTHER HAZARD IS EXPOSED TO TRAFFIC | REQUIRED ^{2,4} | REQUIRED ^{2,4} | REQUIRED ^{2,4} | REQUIRED ^{2,4} |

- A MOBILE CLOSURE SHALL BE USED FOR ANY WORK ACTIVITY THAT MOVES CONTINUOUSLY OR INTERMITTENTLY ALONG THE TRAVELED WAY OR SHOULDER SLOWER THAN THE PREVAILING SPEED OF TRAFFIC. CHANNELIZING DEVICES ARE NOT USED FOR MOBILE CLOSURES.
- SHADOW VEHICLES SHALL BE EQUIPPED WITH AN APPROVED REAR MOUNTED ATTENUATOR (TRUCK MOUNTED OR TRAILER MOUNTED) FOR THE FOLLOWING MOBILE CLOSURES: LANE CLOSURES ON FREEWAYS, LANE CLOSURES ON NON-FREEWAY ROADWAYS HAVING A PRE-CONSTRUCTION POSTED SPEED LIMIT OF 35 MPH OR MORE, SHOULDER CLOSURES ON FREEWAYS, AND SHOULDER CLOSURES ON NON-FREEWAY ROADWAYS HAVING A PRE-CONSTRUCTION SPEED LIMIT OF 45 MPH OR MORE.
- FOR MOBILE LANE CLOSURES ON NON-FREEWAY ROADWAYS HAVING A PRE-CONSTRUCTION POSTED SPEED LIMIT OF 30 MPH OR LESS AND MOBILE SHOULDER CLOSURES ON NON-FREEWAY ROADWAYS HAVING A PRE-CONSTRUCTION SPEED LIMIT OF 40 MPH OR LESS, SHADOW VEHICLES ARE NOT REQUIRED TO BE EQUIPPED WITH A REAR MOUNTED ATTENUATOR.
- A SHADOW VEHICLE IS USED TO PROTECT EXPOSED WORKERS (ON FOOT OR IN A VEHICLE) AND SHALL BE REQUIRED FOR ALL MOBILE CLOSURES. SHADOW VEHICLE REQUIREMENTS SHALL INCLUDE PROVIDING A SEPARATE SHADOW VEHICLE FOR EACH CLOSED LANE AND EACH CLOSED PAVED SHOULDER 8' OR GREATER IN WIDTH. ADDITIONAL SHADOW VEHICLES MAY BE REQUIRED TO PROMOTE THE SAFE OPERATION OF TRAFFIC AND THE INCREASED PROTECTION OF EXPOSED WORKERS, AS DIRECTED BY THE REGIONAL DIRECTOR OR HIS/HER DESIGNEE.

| TABLE 6H-4 FORMULAS FOR DETERMINING TAPER LENGTHS | | | | | | | | | | |
|---|---------------------------|--|--|--|--|--|--|--|--|--|
| SPEED LIMIT (S) (MPH) | TAPER LENGTH (L) (FT.) | | | | | | | | | |
| (40 MPH) OR LESS | $L = WS^2 / 60$ | | | | | | | | | |
| (45 MPH) OR MORE | $L = WS$ | | | | | | | | | |

L = TAPER LENGTH
W = WIDTH OF OFFSET (FT.)
S = PRECONSTRUCTION POSTED SPEED LIMIT (MPH)

| STANDARD TAPER LENGTHS | | | | | | | | | | |
|--|---|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| LATERAL SHIFT OF TRAFFIC FLOW PATH | TEMPORARY TRAFFIC CONTROL ZONE POSTED SPEED LIMIT | | | | | | | | | |
| | (25 MPH) | (30 MPH) | (35 MPH) | (40 MPH) | (45 MPH) | (50 MPH) | (55 MPH) | (60 MPH) | (65 MPH) | (70 MPH) |
| 4 | 45 | 60 | 85 | 110 | 180 | 200 | 220 | 240 | 260 | 280 |
| 5 | 55 | 75 | 105 | 135 | 225 | 250 | 275 | 300 | 325 | 350 |
| 6 | 65 | 90 | 125 | 160 | 270 | 300 | 330 | 360 | 390 | 420 |
| 7 | 75 | 105 | 145 | 190 | 315 | 350 | 385 | 420 | 455 | 490 |
| 8 | 85 | 120 | 165 | 215 | 360 | 400 | 440 | 480 | 520 | 560 |
| 9 | 95 | 135 | 185 | 240 | 405 | 450 | 495 | 540 | 585 | 630 |
| 10 | 105 | 150 | 205 | 270 | 450 | 500 | 550 | 600 | 650 | 700 |
| 11 | 115 | 165 | 225 | 295 | 495 | 550 | 605 | 660 | 715 | 770 |
| 12 | 125 | 180 | 245 | 320 | 540 | 600 | 660 | 720 | 780 | 840 |

| TABLE 6C-2 LONGITUDINAL BUFFER SPACE | |
|--|----------|
| PRECONSTRUCTION POSTED SPEED LIMIT (MPH) | DISTANCE |
| 25 | 155 FT. |
| 30 | 200 FT. |
| 35 | 250 FT. |
| 40 | 305 FT. |
| 45 | 360 FT. |
| 50 | 425 FT. |
| 55 | 495 FT. |
| 60 | 570 FT. |
| 65 | 645 FT. |

| TABLE NY2-A PLACEMENT DISTANCE FOR BARRIER VEHICLES | | | | |
|--|---|---------|--------------|---------|
| PRECONSTRUCTION POSTED SPEED LIMIT (MPH) | PLACEMENT DISTANCE (FT.) BARRIER VEHICLES* | | | |
| | (18000 LBS.) | | (24000 LBS.) | |
| | MINIMUM | MAXIMUM | MINIMUM | MAXIMUM |
| > 55 | 100 FT. | 200 FT. | 100 FT. | 200 FT. |
| 45 - 55 | 100 FT. | 200 FT. | 85 FT. | 165 FT. |
| < 45 | 85 FT. | 165 FT. | 50 FT. | 100 FT. |

- AS DEFINED IN NYS DOT STANDARD SPECIFICATION 619:
- BARRIER VEHICLE - VEHICLE USED FOR STATIONARY SHOULDER CLOSURES, LANE CLOSURES, AND OTHER STATIONARY WORK ZONES.
- MINIMUM DISTANCE SHOWN REFLECTS THE ACTUAL ROLL AHEAD DISTANCE FROM MANUFACTURER.

| TABLE NY2-B PLACEMENT DISTANCE FOR SHADOW VEHICLES | | | | |
|---|---|---------|--------------|---------|
| PRECONSTRUCTION POSTED SPEED LIMIT (MPH) | PLACEMENT DISTANCE (FT.) SHADOW VEHICLES** | | | |
| | (18000 LBS.) | | (24000 LBS.) | |
| | MINIMUM | MAXIMUM | MINIMUM | MAXIMUM |
| > 55 | 230 FT. | 330 FT. | 180 FT. | 280 FT. |
| 45 - 55 | 180 FT. | 280 FT. | 150 FT. | 250 FT. |
| < 45 | 100 FT. | 200 FT. | 100 FT. | 200 FT. |

- AS DEFINED IN NYS DOT STANDARD SPECIFICATION 619:
- SHADOW VEHICLE - VEHICLE USED FOR MOBILE OR SHORT DURATION WORK OPERATIONS.
- MINIMUM DISTANCE SHOWN REFLECTS THE ACTUAL ROLL AHEAD DISTANCE FROM MANUFACTURER.

| TABLE 6C-3 TAPER LENGTH FOR TEMPORARY TRAFFIC CONTROL ZONES | |
|---|------------------|
| TYPE OF TAPER | TAPER LENGTH (L) |
| MERGING TAPER | L |
| SHIFTING TAPER | L/2 |
| SHOULDER TAPER | L/3 |
| ONE-LANE, TWO-WAY TRAFFIC TAPER | 100 FT. MAXIMUM |
| DOWNSTREAM TAPER | 100 FT. PER LANE |

| TABLE 619-4 FLARE RATES FOR POSITIVE BARRIER | | | | | |
|---|--------------------|--------|--------|--------|--------|
| TYPE OF POSITIVE BARRIER | POSTED SPEED LIMIT | | | | |
| | 30 MPH | 40 MPH | 50 MPH | 55 MPH | 65 MPH |
| TEMPORARY CONCRETE BARRIER | 8:1 | 11:1 | 14:1 | 16:1 | 20:1 |
| BOX BEAM OR HEAVY POST CORRUGATED BEAM | 7:1 | 9:1 | 11:1 | 12:1 | 15:1 |

| TABLE NY6H-3 ADVANCE WARNING SIGN SPACING | | | | | |
|--|------------------------|---------|---------|-------------|----------|
| ROAD TYPE | DISTANCE BETWEEN SIGNS | | | SIGN LEGEND | |
| | A (FT.) | B (FT.) | C (FT.) | XX | YY |
| URBAN (≤ 30 MPH*) | 100 | 100 | 100 | AHEAD | AHEAD |
| URBAN (35-40 MPH*) | 200 | 200 | 200 | AHEAD | AHEAD |
| URBAN (≥ 45 MPH*) | 350 | 350 | 350 | 1000 FT. | AHEAD |
| RURAL | 500 | 500 | 500 | 1500 FT. | 1000 FT. |
| EXPRESSWAY / FREEWAY | 1000 | 1500 | 2640 | 1 MILE | 1/2 MILE |

- PRECONSTRUCTION POSTED SPEED LIMIT
- URBAN: (MEETS MORE THAN 1 OF THE FOLLOWING CRITERIA) SIDEWALKS, BICYCLE USAGE, CURBING, CLOSED DRAINAGE SYSTEMS, DRIVEWAY DENSITIES GREATER THAN 24 DRIVEWAYS PER MILE, MINOR COMMERCIAL DRIVEWAY DENSITIES OF 10 DRIVEWAYS PER MILE OR GREATER, MAJOR COMMERCIAL DRIVEWAYS, NUMEROUS RIGHT OF WAY CONSTRAINTS, HIGH DENSITY OF CROSS STREETS, 85TH PERCENTILE SPEEDS OF 45 MPH OR LESS.
- RURAL: ANY AREA NOT EXHIBITING MORE THAN ONE OF THE ABOVE CHARACTERISTICS.
- EXPRESSWAY: DIVIDED HIGHWAYS FOR TRAFFIC WITH FULL OR PARTIAL CONTROL OF ACCESS AND GENERALLY WITH GRADE SEPARATIONS AT MAJOR CROSSROADS.
- FREEWAYS/INTERSTATE: LOCAL OR INTER REGIONAL HIGH-SPEED, DIVIDED, HIGH-VOLUME FACILITIES WITH FULL OR PARTIAL CONTROL OF ACCESS.

| WORK DURATION DEFINITIONS |
|---|
| LONG-TERM STATIONARY IS WORK THAT OCCUPIES A LOCATION MORE THAN 3 CONSECUTIVE DAYS. |
| INTERMEDIATE-TERM STATIONARY IS WORK THAT OCCUPIES A LOCATION MORE THAN ONE DAYLIGHT PERIOD UP TO 3 CONSECUTIVE DAYS, OR NIGHTTIME WORK LASTING MORE THAN 1 HOUR. |
| SHORT-TERM STATIONARY IS DAYTIME WORK THAT OCCUPIES A LOCATION FOR MORE THAN 1 HOUR WITHIN A SINGLE DAYLIGHT PERIOD. |
| SHORT DURATION IS WORK THAT OCCUPIES A LOCATION UP TO 1 HOUR. |
| MOBILE IS WORK THAT MOVES INTERMITTENTLY OR CONTINUOUSLY. |

| WORK ZONE TRAFFIC CONTROL LEGEND | |
|----------------------------------|---|
| SYMBOL | DESCRIPTION |
| | ARROW PANEL |
| | ARROW PANEL, CAUTION MODE |
| | ARROW PANEL TRAILER OR SUPPORT |
| | CHANGEABLE MESSAGE SIGN (PVMS) |
| | CHANNELIZING DEVICE |
| | CRASH CUSHION/TEMPORARY IMPACT ATTENUATOR |
| | DIRECTION OF TEMPORARY TRAFFIC DETOUR |
| | DIRECTION OF TRAFFIC |
| | FLAGGER |
| | FLAG TREE |
| | LUMINAIRE |
| | PAVEMENT MARKINGS THAT SHALL BE REMOVED FOR A LONG TERM PROJECT |
| | SIGN, TEMPORARY |
| | TEMPORARY BARRIER |
| | TEMPORARY BARRIER WITH WARNING LIGHTS |
| | TRAFFIC OR PEDESTRIAN SIGNAL |
| | TYPE III BARRICADE |
| | WARNING LIGHTS |
| | WORK SPACE |
| | WORK VEHICLE |
| | WORK VEHICLE WITH TRUCK MOUNTED ATTENUATOR |

| | |
|---|------------------------|
| STATE OF NEW YORK DEPARTMENT OF TRANSPORTATION | |
| U.S. CUSTOMARY STANDARD SHEET | |
| WORK ZONE TRAFFIC CONTROL LEGENDS AND NOTES | |
| APPROVED SEPTEMBER 18, 2008 | ISSUED UNDER EB 08-036 |
| /S/ DAVID J. CLEMENTS, P.E. DIRECTOR, OFFICE OF TRAFFIC SAFETY AND MOBILITY | 619-11 |

| WORK ZONE TRAFFIC CONTROL SIGN TABLE | | | | | |
|--------------------------------------|------------------|---------------|--------------------------|------------|---------|
| SIGN | SIGN DESIGNATION | COLOR CODE | CONVENTIONAL ROAD | EXPRESSWAY | FREEWAY |
| | E5-1 | C | ----- | 72"x60" | 72"x60" |
| | G20-1 | A | 36"x18" | 48"x24" | 48"x24" |
| | G20-2 | A | 36"x18" | 48"x24" | 48"x24" |
| | G20-4 | A | 36"x18" | ----- | ----- |
| | G20-5aP | A | 24"x18" | 36"x24" | 36"x24" |
| | M1-1 | G | 1 OR 2 DIGITS 24"x24" | 36"x36" | 36"x36" |
| | M1-1t | G | 3 DIGITS 30"x24" | 45"x36" | 45"x36" |
| | M1-4 | B | 1 OR 2 DIGITS 24"x24" | 36"x36" | 36"x36" |
| | M1-4t | B | 3 DIGITS 30"x24" | 45"x36" | 45"x36" |
| | M3-1 | SEE NOTE 3 | 24"x12" | 36"x18" | 36"x18" |
| | M3-2 | | | | |
| | M3-3 | | | | |
| | M3-4 | | | | |
| | M4-8 | A | 24"x12" | 36"x18" | 36"x18" |
| | M4-8a | A | 24"x18" | 24"x18" | 24"x18" |
| | M4-9 | A | 30"x24" | 48"x36" | 48"x36" |
| | M4-9L | | | | |
| | M4-9R | | | | |
| | M4-9a | A | 30"x24" | 30"x24" | ----- |
| | M4-9b | A | 30"x24" | 30"x24" | ----- |
| | M4-9c | A | 30"x24" | 30"x24" | ----- |
| | M4-10L | A | 48"x18" | 48"x18" | 48"x18" |
| | M4-10R | | | | |
| | M5-1 | SEE NOTE 3 | 21"x15" | 30"x21" | 30"x21" |
| | M5-2 | SEE NOTE 3 | 21"x15" | 30"x21" | 30"x21" |
| | M6-1 | SEE NOTE 3 | 21"x15" | 30"x21" | 30"x21" |
| | M6-2 | | | | |
| | M6-3 | | | | |
| | M6-4 | | | | |
| | NYM3-1 | B | 24"x24" | 36"x36" | 36"x36" |
| | NYM3-2 | B | 30"x24" | 45"x36" | 45"x36" |
| | NYM3-3 | B | 30"x24" | 45"x36" | 45"x36" |

| WORK ZONE TRAFFIC CONTROL SIGN TABLE | | | | | |
|--------------------------------------|--------------------|------------|--|-------------|-------------|
| SIGN | SIGN DESIGNATION | COLOR CODE | CONVENTIONAL ROAD | EXPRESSWAY | FREEWAY |
| | NYR9-11 | B | 24"x42" | 48"x84" | 48"x84" |
| | NYR9-12 | B | 24"x36" | 36"x54" | 48"x72" |
| | NYW4-17 | A | 36"x36" | 48"x48" | 48"x48" |
| | NYW8-30 | A | 48"x24" | 48"x24" | 48"x24" |
| | NYW8-31 | A | 48"x24" | 48"x24" | 48"x24" |
| | NYW8-32 | A | 48"x24" | 48"x24" | 48"x24" |
| | NYW8-33 | A | 48"x24" | 48"x24" | 48"x24" |
| | R1-1 | D | 36"x36" | 36"x36" | 48"x48" |
| | R1-2 | E | 36"x36"x36" | 48"x48"x48" | 60"x60"x60" |
| | R2-1 | B | 24"x30" OR 30"x36" (SEE NOTE 5) | 36"x48" | 36"x48" |
| | R2-11 | B | 24"x30" | 36"x48" | 36"x48" |
| | R2-12 | B | 24"x36" | 36"x54" | 36"x54" |
| | R4-1 | B | 24"x30" | 36"x48" | 36"x48" |
| | R4-7 | B | 24"x30" | 36"x48" | 36"x48" |
| | R4-7c NARROW | B | 18"x30" | ----- | ----- |
| | R4-8 | B | 24"x30" | 36"x48" | 36"x48" |
| | R4-8c NARROW | B | 18"x30" | ----- | ----- |
| | R4-9 | B | 24"x30" | 36"x48" | 36"x48" |
| | R5-1 | E | 36"x36" | 36"x36" | 48"x48" |
| | R9-8 | B | 36"x18" | 36"x18" | ----- |
| | R9-9 | B | 24"x12" | 24"x12" | ----- |
| | R9-10L R9-10R | B | 24"x12" | 24"x12" | ----- |
| | R9-11L R9-11R | B | 24"x18" | 24"x18" | ----- |
| | R9-11dL R9-11dR | B | 24"x12" | 24"x12" | ----- |
| | R10-6 | B | 24"x36" | 24"x36" | ----- |
| | R11-2 | B | 48"x30" | 48"x30" | 48"x30" |

| WORK ZONE TRAFFIC CONTROL SIGN TABLE | | | | | |
|--------------------------------------|------------------|---------------------|-------------------|------------|---------|
| SIGN | SIGN DESIGNATION | COLOR CODE | CONVENTIONAL ROAD | EXPRESSWAY | FREEWAY |
| | R11-3a | B | 60"x30" | 60"x30" | ----- |
| | W1-4L W1-4R | A | 36"x36" | 48"x48" | 48"x48" |
| | W1-4bL W1-4bR | A | 36"x36" | 48"x48" | 48"x48" |
| | W1-4cL W1-4cR | A | 36"x36" | 48"x48" | 48"x48" |
| | W1-6L | A | 48"x24" | 60"x30" | 60"x30" |
| | W1-6R | A | 48"x24" | 60"x30" | 60"x30" |
| | W1-8L | A (NO BORDER) | 18"x24" | 30"x36" | 30"x36" |
| | W1-8R | A (NO BORDER) | 18"x24" | 30"x36" | 30"x36" |
| | W3-1 | A ⁴ | 36"x36" | 48"x48" | 48"x48" |
| | W3-2 | A ⁴ | 36"x36" | 48"x48" | 48"x48" |
| | W3-3 | A ⁴ | 36"x36" | 48"x48" | 48"x48" |
| | W3-4 | A | 36"x36" | 48"x48" | 48"x48" |
| | W3-5 | A ⁴ | 36"x36" | 48"x48" | 48"x48" |
| | W4-1L W4-1R | A | 36"x36" | 48"x48" | 48"x48" |
| | W4-2L W4-2R | A | 36"x36" | 48"x48" | 48"x48" |

ROADWAY DEFINITIONS:
 CONVENTIONAL ROAD - A STREET OR HIGHWAY OTHER THAN A FREEWAY, OR EXPRESSWAY.
 EXPRESSWAY - A DIVIDED HIGHWAY WITH PARTIAL CONTROL OF ACCESS.
 FREEWAY - A DIVIDED HIGHWAY WITH FULL CONTROL OF ACCESS.

| COLOR CODE LEGEND | |
|-------------------|--|
| CODE | DESCRIPTION |
| A | BLACK LEGEND AND BORDER ON AN ORANGE BACKGROUND |
| B | BLACK LEGEND AND BORDER ON A WHITE BACKGROUND |
| C | WHITE LEGEND AND BORDER ON A GREEN BACKGROUND |
| D | WHITE LEGEND AND BORDER ON A RED BACKGROUND |
| E | RED LEGEND AND BORDER ON A WHITE BACKGROUND |
| F | BLACK LEGEND AND BORDER ON A FLOURESCENT YELLOW GREEN BACKGROUND |
| G | WHITE LEGEND AND BORDER ON A BLUE AND RED BACKGROUND |

- NOTES:
- DIMENSIONS ARE SHOWN AS WIDTH X HEIGHT.
 - FOR SIGNAGE NOT SHOWN ON THESE TABLES REFER TO THE M.U.T.C.D.
 - COLORS FOR DIRECTION PLAQUES, ADVANCE TURN ARROWS, AND DIRECTIONAL ARROWS SHALL MATCH THE ROUTE OR INTERSTATE SIGN THAT THEY SUPPLEMENT AS PER THE M.U.T.C.D.
 - MULTICOLORED SYMBOL IMPOSED ON SIGN WITH BLACK LEGEND AND BORDER ON AN ORANGE BACKGROUND.
 - FOR R2-1 SIGN LARGER DIMENSIONS SHALL BE USED WHEN SIGN FACES MULTIPLE LANES ON A CONVENTIONAL ROAD.

| | |
|---|------------------------|
| <p>STATE OF NEW YORK DEPARTMENT OF TRANSPORTATION</p> | |
| U.S. CUSTOMARY STANDARD SHEET | |
| SIGN TABLE (SHEET 1 OF 2) | |
| APPROVED APRIL 1, 2012 | ISSUED UNDER EB 12-010 |
| /S/ TODD WESTHUIS, P.E. DIRECTOR, OFFICE OF TRAFFIC SAFETY AND MOBILITY | |
| 619-12 | |

EFFECTIVE DATE: 05/03/2012

| WORK ZONE TRAFFIC CONTROL SIGN TABLE | | | | | |
|--------------------------------------|--------------------|------------|-------------------|------------|---------|
| SIGN | SIGN DESIGNATION | COLOR CODE | CONVENTIONAL ROAD | EXPRESSWAY | FREEWAY |
| | W5-1 | A | 36"X36" | 48"X48" | 48"X48" |
| | W5-4 | A | 36"X36" | 48"X48" | 48"X48" |
| | W6-3 | A | 36"X36" | 48"X48" | 48"X48" |
| | W7-3dP | A | 24"X18" | 36"X30" | 36"X30" |
| | W8-1 | A | 36"X36" | 48"X48" | 48"X48" |
| | W8-3 | A | 36"X36" | 48"X48" | 48"X48" |
| | W8-7 | A | 36"X36" | 48"X48" | 48"X48" |
| | W8-8 | A | 36"X36" | 48"X48" | 48"X48" |
| | W8-9 | A | 36"X36" | 48"X48" | 48"X48" |
| | W8-12 | A | 36"X36" | ----- | ----- |
| | W8-14 | A | 36"X36" | 48"X48" | 48"X48" |
| | W8-15 | A | 36"X36" | 48"X48" | 48"X48" |
| | W8-17 | A | 36"X36" | 48"X48" | 48"X48" |
| | W8-17p | A | 24"X18" | 30"X24" | 30"X24" |
| | W8-23 | A | 36"X36" | 48"X48" | 48"X48" |
| | W8-24 | A | 36"X36" | 48"X48" | 48"X48" |
| | W9-3 | A | 36"X36" | 48"X48" | 48"X48" |
| | W11-1L W11-1R | A OR F | 36"X36" | 36"X36" | ----- |
| | W11-2L W11-2R | F | 36"X36" | 36"X36" | ----- |
| | W11-15L W11-15R | F | 36"X36" | 36"X36" | ----- |

| WORK ZONE TRAFFIC CONTROL SIGN TABLE | | | | | |
|--------------------------------------|--------------------|-------------------|-------------------|------------|---------|
| SIGN | SIGN DESIGNATION | COLOR CODE | CONVENTIONAL ROAD | EXPRESSWAY | FREEWAY |
| | W13-1P | A | 24"X24" | 30"X30" | 30"X30" |
| | W14-3 | A | 36"X36" | 36"X36" | 36"X36" |
| | W13-4P | A | 48"X48"X36" | ----- | ----- |
| | W16-1P | SEE NOTE 3 A OR F | 18"X24" | 24"X30" | ----- |
| | W16-2P | A | 24"X18" | 30"X24" | ----- |
| | W16-4P | SEE NOTE 3 A OR F | 30"X24" | ----- | ----- |
| | W16-5PL W16-5PR | A | 24"X18" | ----- | ----- |
| | W16-7PL W16-7PR | SEE NOTE 3 A OR F | 24"X12" | 30"X18" | ----- |
| | W16-9P | SEE NOTE 3 A OR F | 24"X12" | 30"X18" | ----- |
| | W20-1 | A | 36"X36" | 48"X48" | 48"X48" |
| | W20-2 | A | 36"X36" | 48"X48" | 48"X48" |
| | W20-3 | A | 36"X36" | 48"X48" | 48"X48" |
| | W20-4 | A | 36"X36" | 48"X48" | 48"X48" |
| | W20-5 | A | 36"X36" | 48"X48" | 48"X48" |
| | W20-5a | A | 36"X36" | 48"X48" | 48"X48" |
| | W20-7 | A | 36"X36" | 48"X48" | 48"X48" |

| WORK ZONE TRAFFIC CONTROL SIGN TABLE | | | | | |
|--------------------------------------|--------------------|------------|-------------------|------------|---------|
| SIGN | SIGN DESIGNATION | COLOR CODE | CONVENTIONAL ROAD | EXPRESSWAY | FREEWAY |
| | W21-1 | A | 36"X36" | 48"X48" | 48"X48" |
| | W21-4 | A | 36"X18" | 48"X24" | 48"X24" |
| | W21-5 | A | 36"X36" | 48"X48" | 48"X48" |
| | W21-5dL W21-5dR | A | 36"X36" | 48"X48" | 48"X48" |
| | W21-5bL W21-5bR | A | 36"X36" | 48"X48" | 48"X48" |
| | W21-8 | A | 36"X36" | 48"X48" | 48"X48" |
| | W22-1 | A | 36"X36" | 48"X48" | 48"X48" |
| | W22-2 | A | 42"X36" | 42"X36" | 42"X36" |
| | W22-3 | A | 42"X36" | 42"X36" | 42"X36" |
| | W23-2 | A | 36"X36" | 48"X48" | 48"X48" |
| | W24-1L W24-1R | A | 36"X36" | 48"X48" | 48"X48" |
| | W24-1dL W24-1dR | A | 36"X36" | 48"X48" | 48"X48" |
| | W24-1bL W24-1bR | A | 36"X36" | 48"X48" | 48"X48" |


ROADWAY DEFINITIONS:
CONVENTIONAL ROAD - A STREET OR HIGHWAY OTHER THAN A FREEWAY, OR EXPRESSWAY.
EXPRESSWAY - A DIVIDED HIGHWAY WITH PARTIAL CONTROL OF ACCESS.
FREEWAY - A DIVIDED HIGHWAY WITH FULL CONTROL OF ACCESS.

| COLOR CODE LEGEND | |
|-------------------|--|
| CODE | DESCRIPTION |
| A | BLACK LEGEND AND BORDER ON AN ORANGE BACKGROUND |
| B | BLACK LEGEND AND BORDER ON A WHITE BACKGROUND |
| C | WHITE LEGEND AND BORDER ON A GREEN BACKGROUND |
| D | WHITE LEGEND AND BORDER ON A RED BACKGROUND |
| E | RED LEGEND AND BORDER ON A WHITE BACKGROUND |
| F | BLACK LEGEND AND BORDER ON A FLOURESCENT YELLOW GREEN BACKGROUND |
| G | WHITE LEGEND AND BORDER ON A BLUE AND RED BACKGROUND |

- NOTES:
- DIMENSIONS ARE SHOWN AS WIDTH X HEIGHT.
 - FOR SIGNAGE NOT SHOWN ON THESE TABLES REFER TO THE M.U.T.C.D.
 - WHEN USED IN CONJUNCTION WITH A BICYCLE SIGN (W11-1) OR PEDESTRIAN CROSSING (W11-2) COLOR CODE SHALL MATCH.

| | |
|--|---|
| | STATE OF NEW YORK DEPARTMENT OF TRANSPORTATION |
| U.S. CUSTOMARY STANDARD SHEET | |
| SIGN TABLE (SHEET 2 OF 2) | |
| APPROVED APRIL 1, 2012 | ISSUED UNDER EB 12-010 |
| /S/ TODD WESTHUIS, P.E. DIRECTOR, OFFICE OF TRAFFIC SAFETY AND MOBILITY | 619-12 |

EFFECTIVE DATE: 05/03/2012



SHOULDER CLOSURE
SHORT OR INTERMEDIATE TERM STATIONARY
2-LANE 2-WAY ROADWAY
(NOT TO SCALE)


NOTES:

1. WHEN THE MINIMUM LANE WIDTH OF 10' CANNOT BE MAINTAINED DUE TO A SHOULDER CLOSURE, USE THE DETAIL FOR SHORT OR INTERMEDIATE TERM STATIONARY FLAGGING OPERATION.
2. NO WORK ACTIVITY OR STORAGE OF EQUIPMENT, VEHICLES, OR MATERIAL SHOULD OCCUR WITHIN A BUFFER SPACE.
3. WHEN THE DISTANCE BETWEEN THE ADVANCE WARNING SIGNS AND WORK IS 2 MILES TO 5 MILES, A SUPPLEMENTAL DISTANCE PLAQUE (W7-3a) SHOULD BE USED WITH THE SHOULDER WORK SIGN (W21-5).
4. THE ROAD WORK NEXT XX MILES SIGN (G20-1) MAY BE USED INSTEAD OF THE ROAD WORK AHEAD SIGN (W20-1) IF WORK LOCATIONS OCCUR OVER A DISTANCE OF MORE THAN 2 MILES.
5. FOR BARRIER VEHICLE USE REQUIREMENTS SEE TABLES NY1-A AND NY2-A ON THE STANDARD SHEET TITLED "WORK ZONE TRAFFIC CONTROL LEGENDS AND NOTES".
6. IN THOSE SITUATIONS WHERE MULTIPLE WORK LOCATIONS EXIST WITHIN A LIMITED DISTANCE MAKE IT PRACTICAL TO PLACE STATIONARY SIGNS, THE DISTANCE BETWEEN THE ADVANCE WARNING SIGN AND WORK SHALL NOT EXCEED 5 MILES.
7. CHANNELIZING DEVICE SPACING (CENTER TO CENTER) SHALL NOT EXCEED 40' IN THE ACTIVE WORK SPACE.
8. TRANSVERSE DEVICES SHALL BE REQUIRED (AS PER 619 STANDARD SPECIFICATIONS) WHEN A PAVED SHOULDER HAVING A WIDTH OF 8' OR GREATER IS CLOSED FOR A DISTANCE GREATER THAN 1500'.


NOTE: SEE STANDARD SHEET TITLED "WORK ZONE TRAFFIC CONTROL LEGENDS AND NOTES" FOR LEGEND OF SYMBOLS AND/OR LETTER CODES USED IN THIS DRAWING.

| | | |
|---|---|--------|
| | STATE OF NEW YORK DEPARTMENT OF TRANSPORTATION | |
| | U.S. CUSTOMARY STANDARD SHEET | |
| SHOULDER CLOSURE 2-LANE 2-WAY ROADWAY | | |
| APPROVED SEPTEMBER 15, 2009 /S/ DAVID J. CLEMENTS, P.E. DIRECTOR, OFFICE OF TRAFFIC SAFETY AND MOBILITY | ISSUED UNDER EB 09-025 | 619-20 |

EFFECTIVE DATE: 01/07/10



SIDEWALK DETOUR
 SHORT, INTERMEDIATE, OR LONG TERM STATIONARY
 2-LANE 2-WAY ROADWAY
 (NOT TO SCALE)



SIDEWALK DIVERSION
 SHORT, INTERMEDIATE, OR LONG TERM STATIONARY
 2-LANE 2-WAY ROADWAY
 (NOT TO SCALE)

NOTES:

1. WHEN CROSSWALKS OR OTHER PEDESTRIAN FACILITIES ARE CLOSED OR RELOCATED, TEMPORARY FACILITIES SHALL BE DETECTABLE AND SHALL INCLUDE ACCESSIBILITY FEATURES CONSISTENT WITH THE FEATURES PRESENT IN THE EXISTING FACILITY.
2. WHERE HIGH SPEEDS ARE ANTICIPATED, A TEMPORARY TRAFFIC BARRIER AND TEMPORARY IMPACT ATTENUATOR SHOULD BE USED TO SEPARATE THE TEMPORARY SIDEWALKS FROM VEHICULAR TRAFFIC.
3. ONLY THE WORK ZONE TRAFFIC CONTROL DEVICES RELATED TO PEDESTRIANS ARE SHOWN. OTHER DEVICES, SUCH AS LANE CLOSURE SIGNING OR ROAD NARROWS SIGNS (W5-4), MAY BE USED TO CONTROL VEHICULAR TRAFFIC.
4. FOR NIGHTTIME CLOSURES, FLASHING WARNING LIGHTS SHALL BE USED ON BARRICADES SUPPORTING SIGNS AND CLOSING SIDEWALKS.
5. SIGNS SUCH AS KEEP RIGHT (LEFT) SHALL BE PLACED ALONG A TEMPORARY SIDEWALK, WHERE APPLICABLE AND ACCORDING TO AMERICAN WITH DISABILITIES STANDARDS, TO GUIDE OR DIRECT PEDESTRIANS.
6. TYPE II BARRICADES MAY BE SUBSTITUTED FOR TYPE III BARRICADES AS PER 619 STANDARD SPECIFICATIONS.

NOTE: SEE STANDARD SHEET TITLED "WORK ZONE TRAFFIC CONTROL LEGENDS AND NOTES" FOR LEGEND OF SYMBOLS AND/OR LETTER CODES USED IN THIS DRAWING.



STATE OF NEW YORK
 DEPARTMENT OF TRANSPORTATION

U.S. CUSTOMARY STANDARD SHEET

SIDEWALK DETOUR OR DIVERSION

APPROVED SEPTEMBER 15, 2009

ISSUED UNDER EB 09-025

/S/ DAVID J. CLEMENTS, P.E.
 DIRECTOR, OFFICE OF
 TRAFFIC SAFETY AND MOBILITY


619-50

EFFECTIVE DATE: 01/07/10

NEW YORK STATE STANDARD SHEETS

BOOK 4 of 4

SHEETS 645-01 THRU 685-01



**Department of
Transportation**

U.S. CUSTOMARY UNITS
ENGINEERING DIVISION, OFFICE OF DESIGN

MAY 01, 2019

NOTE: INDIVIDUAL STANDARD SHEETS IN THIS BOOK BECOME PART OF A CONTRACT BY REFERENCE TO THE SHEET NUMBER IN THE PROJECT PLANS OR PROPOSAL. THIS ENTIRE SET OF 4 BOOKS IS OFFICIALLY FINALIZED AND ADOPTED AS OF THE DATE SHOWN ON THIS COVER.

| SHEET NO. | SUBJECT | ISSUED BY | EFFECTIVE |
|--------------------|--|------------------|-----------------|
| BOOK 1 of 4 | | | |
| 203-01 | CONSTRUCTION DETAILS UNSUITABLE MATERIAL EXCAVATION AND BACKFILL | EB 08-036 | 01/08/09 |
| 203-02 | EARTHWORK TRANSITION AND BENCHING DETAILS (ERRATA ISSUED BY EB 14-025) | EB 08-036 | 01/08/09 |
| 203-03 | INSTALLATION DETAILS FOR GRANULAR FILL-SLOPE PROTECTION | EB 08-036 | 01/08/09 |
| 203-04 | INSTALLATION DETAILS FOR REINFORCED CONCRETE PIPES | EB 13-038 | 01/09/14 |
| 203-05 | INSTALLATION DETAILS FOR CORRUGATED AND STRUCTURAL PLATE PIPE AND PIPE ARCHES | EB 16-020 | 09/01/16 |
| 204-01 | CONTROLLED LOW STRENGTH MATERIAL (CLSM) INSTALLATION DETAILS FOR CIRCULAR AND ELLIPTICAL CORRUGATED METAL PIPES, STRUCTURAL PLATE PIPES AND PIPE-ARCHES, AND REINFORCED CONCRETE AND OTHER "RIGID" PIPES | EB 08-036 | 01/08/09 |
| 209-01 | LINEAR MEASURES | EB 09-036 | 09/02/10 |
| 209-02 | CHECK DAMS (SHEET 1 OF 2) (ERRATA ISSUED BY EB 13-042) | EB 09-036 | 09/02/10 |
| | CHECK DAMS (SHEET 2 OF 2) | EB 09-036 | 09/02/10 |
| 209-03 | DRAINAGE STRUCTURE INLET PROTECTION (SHEET 1 OF 2) | EB 09-036 | 09/02/10 |
| | DRAINAGE STRUCTURE INLET PROTECTION (SHEET 2 OF 2) | EB 09-036 | 09/02/10 |
| 209-04 | PIPE INLET/OUTLET PROTECTION PIPE SLOPE DRAIN | EB 09-036 | 09/02/10 |
| 209-05 | CONSTRUCTION ENTRANCES | EB 09-036 | 09/02/10 |
| 209-06 | TURBIDITY CURTAIN | EB 09-036 | 09/02/10 |
| 209-07 | SEDIMENT TRAPS | EB 09-036 | 09/02/10 |
| 212-01 | WIRE ROPE ROCK CATCHMENT FENCE (SHEET 1 OF 3) | EB 10-004 | 05/06/10 |
| | WIRE ROPE ROCK CATCHMENT FENCE (SHEET 2 OF 3) | EB 10-004 | 05/06/10 |
| | WIRE ROPE ROCK CATCHMENT FENCE (SHEET 3 OF 3) | EB 10-004 | 05/06/10 |
| 212-02 | CHAIN LINK ROCK CATCHMENT FENCE (SHEET 1 OF 2) | EB 18-020 | 01/01/19 |
| | CHAIN LINK ROCK CATCHMENT FENCE (SHEET 2 OF 2) | EB 18-020 | 01/01/19 |
| 212-03 | WIRE MESH SLOPE PROTECTION (SHEET 1 OF 2) | EB 10-004 | 05/06/10 |
| | WIRE MESH SLOPE PROTECTION (SHEET 2 OF 2) | EB 10-004 | 05/06/10 |
| 212-04 | WIRE MESH DRAPE (ERRATA ISSUED BY EB 13-042) | EB 10-004 | 05/06/10 |
| 212-05 | TEMPORARY ROCK CATCHMENT BARRIER (SHEET 1 OF 2) | EB 10-004 | 05/06/10 |
| | TEMPORARY ROCK CATCHMENT BARRIER (SHEET 2 OF 2) | EB 10-004 | 05/06/10 |
| 402-01 | HOT MIX ASPHALT OVERLAY SPLICE (PAVEMENT TERMINATION DETAIL) | EB 08-036 | 01/08/09 |
| 502-01 | METAL REINFORCEMENT FOR CONCRETE PAVEMENT | EB 18-044 | 05/01/19 |
| 502-02 | TYPICAL PLAN, CROSS SECTION AND JOINT LAYOUT | EB 18-044 | 05/01/19 |
| 502-03 | LONGITUDINAL JOINTS | EB 18-044 | 05/01/19 |
| 502-04 | LONGITUDINAL JOINT TIES | EB 18-044 | 05/01/19 |
| 502-05 | TRANSVERSE JOINTS | EB 18-044 | 05/01/19 |
| 502-06 | JOINT SAWING AND SEALING | EB 18-044 | 05/01/19 |
| 502-07 | UTILITY ISOLATION AND JOINT LAYOUT GENERAL NOTES | EB 18-044 | 05/01/19 |
| 502-08 | UTILITY ISOLATION GUIDELINES | EB 18-044 | 05/01/19 |
| 502-09 | TELESCOPING MANHOLE CASTING LAYOUT | EB 18-044 | 05/01/19 |
| 502-10 | NON-TELESCOPING MANHOLE CASTING LAYOUT | EB 18-044 | 05/01/19 |
| 502-11 | SHALLOW STRUCTURE ISOLATION | EB 18-044 | 05/01/19 |
| 502-12 | DRAINAGE STRUCTURE ISOLATION | EB 18-044 | 05/01/19 |
| 502-13 | DRAINAGE STRUCTURE ISOLATION NEAR MANHOLE CASTINGS | EB 18-044 | 05/01/19 |
| 502-14 | MULTIPLE UTILITIES ISOLATION | EB 18-044 | 05/01/19 |
| 554-01 | PROPRIETARY FILL TYPE RETAINING WALLS - SHEET 1 OF 5 GENERAL NOTES (ERRATA ISSUED BY EB 13-042) | EB 10-041 | 05/05/11 |
| | PROPRIETARY FILL TYPE RETAINING WALLS - SHEET 2 OF 5 GENERAL DETAILS | EB 10-041 | 05/05/11 |
| | PROPRIETARY FILL TYPE RETAINING WALLS - SHEET 3 OF 5 TYP. SECTIONS FOR MECH. STABILIZED EARTH SYSTEMS | EB 10-041 | 05/05/11 |
| | PROPRIETARY FILL TYPE RETAINING WALLS - SHEET 4 OF 5 TYP. SECTIONS FOR MECH. STABILIZED WALL SYSTEMS | EB 10-041 | 05/05/11 |
| | PROPRIETARY FILL TYPE RETAINING WALLS - SHEET 5 OF 5 TYP. SECTIONS FOR PREFABRICATED WALL SYSTEMS | EB 10-041 | 05/05/11 |

| SHEET NO. | SUBJECT | ISSUED BY | EFFECTIVE |
|-----------|---|-----------|-----------|
| 554-02 | GEOSYNTHETICALLY REINFORCED SOIL SYSTEMS SHEET 1 OF 6 - WALLS - GENERAL NOTES AND DETAILS | EB 10-041 | 05/05/11 |
| | GEOSYNTHETICALLY REINFORCED SOIL SYSTEMS SHEET 2 OF 6 - WALLS - TYPICAL SECTIONS | EB 10-041 | 05/05/11 |
| | GEOSYNTHETICALLY REINFORCED SOIL SYSTEMS SHEET 3 OF 6 - SLOPES - GENERAL NOTES AND DETAILS | EB 10-041 | 05/05/11 |
| | GEOSYNTHETICALLY REINFORCED SOIL SYSTEMS SHEET 4 OF 6 - SLOPES - TYPICAL SECTIONS | EB 10-041 | 05/05/11 |
| | GEOSYNTHETICALLY REINFORCED SOIL SYSTEMS SHEET 5 OF 6 - FACING DETAILS | EB 10-041 | 05/05/11 |
| | GEOSYNTHETICALLY REINFORCED SOIL SYSTEMS SHEET 6 OF 6 - FACING DETAILS | EB 10-041 | 05/05/11 |
| 601-01 | PRECAST CONCRETE STREET PAVING LAYOUT DETAILS | EB 12-009 | 09/06/12 |
| 603-01 | REINFORCED CONCRETE PIPE END SECTIONS AND CONCRETE COLLARS | EB 08-036 | 01/08/09 |
| 603-02 | ALUMINUM AND STEEL END SECTIONS FOR CORRUGATED PIPE AND PIPE-ARCH | EB 08-036 | 01/08/09 |
| 603-03 | CATTLE PASS | EB 08-036 | 01/08/09 |
| 603-04 | CUT-OFF WALLS FOR END SECTIONS | EB 11-013 | 01/12/12 |
| 603-05 | CULVERT-END SAFETY GRATE | EB 08-036 | 01/08/09 |
| 604-01 | PRE-CAST CONCRETE TRANSVERSE DRAINAGE INTERCEPTOR (ERRATA ISSUED BY EB 14-025) | EB 08-036 | 01/08/09 |
| 604-02 | DRAINAGE STRUCTURE DETAILS (SHEET 1 OF 4) | EB 12-044 | 05/02/13 |
| | DRAINAGE STRUCTURE DETAILS (SHEET 2 OF 4) | EB 08-036 | 01/08/09 |
| | DRAINAGE STRUCTURE DETAILS (SHEET 3 OF 4) | EB 08-036 | 01/08/09 |
| | DRAINAGE STRUCTURE DETAILS (SHEET 4 OF 4) | EB 08-036 | 01/08/09 |
| 605-01 | POROUS CONCRETE PIPE UNDERDRAIN | EB 08-036 | 01/08/09 |



U.S. CUSTOMARY STANDARD SHEET

INDEX OF SHEETS EFFECTIVE
05/01/2019
(LATEST CHANGES HIGHLIGHTED)
BOOK 1

| SHEET NO. | SUBJECT | ISSUED BY | EFFECTIVE |
|--------------------|---|-----------|-----------|
| BOOK 2 of 4 | | | |
| 606-01 | CABLE GUIDE RAIL (SHEET 1 OF 3) (ERRATA ISSUED BY EB 18-003) | EB 12-003 | 09/06/12 |
| | CABLE GUIDE RAILING (SHEET 2 OF 3) | EB 12-003 | 09/06/12 |
| | CABLE GUIDE RAILING (SHEET 3 OF 3) | EB 12-003 | 09/06/12 |
| 606-02 | CABLE MEDIAN BARRIER (SHEET 1 OF 2) (ERRATA ISSUED BY EB 18-003) | EB 12-003 | 09/06/12 |
| | CABLE MEDIAN BARRIER (SHEET 2 OF 2) (ERRATA ISSUED BY EB 18-003) | EB 12-003 | 09/06/12 |
| | CABLE MEDIAN BARRIER (SHEET 3 OF 3) | EB 12-003 | 09/06/12 |
| 606-04 | BOX BEAM GUIDE RAIL (SHEET 1 OF 4) | EB 11-013 | 01/12/12 |
| | BOX BEAM GUIDE RAIL (SHEET 2 OF 4) (ERRATA ISSUED BY EB 14-025 & EB 18-003) | EB 11-013 | 01/12/12 |
| | BOX BEAM GUIDE RAIL (SHEET 3 OF 4) | EB 11-013 | 01/12/12 |
| | BOX BEAM GUIDE RAIL (SHEET 4 OF 4) | EB 10-022 | 01/06/11 |
| 606-05 | BOX BEAM MEDIAN BARRIER | EB 08-036 | 01/08/09 |
| 606-06 | BOX BEAM END ASSEMBLY TYPE III GRADING, PAYMENT, AND LAYOUT DETAILS | EB 09-025 | 01/07/10 |
| 606-07 | WEAK POST CORRUGATED-BEAM GUIDE RAILING SHEET 1 OF 3 (ERRATA ISSUED BY EB 14-025 & EB 18-003) | EB 13-028 | 05/08/14 |
| | WEAK POST CORRUGATED-BEAM GUIDE RAILING SHEET 2 OF 3 (ERRATA ISSUED BY EB 14-025 & EB 18-003) | EB 13-028 | 05/08/14 |
| | WEAK POST CORRUGATED-BEAM GUIDE RAILING SHEET 3 OF 3 (ERRATA ISSUED BY EB 14-025 & EB 18-003) | EB 13-028 | 05/08/14 |
| 606-08 | WEAK POST W-BEAM MEDIAN BARRIER (ERRATA ISSUED BY EB 14-025 & EB 18-003) | EB 11-013 | 01/12/12 |
| 606-09 | HEAVY POST BLOCKED-OUT (MOD.) CORRUGATED-BEAM GUIDE RAILING (SHEET 1 OF 2) (ERRATA ISSUED BY EB 16-008 & EB 18-023) | EB 13-028 | 05/08/14 |
| | HEAVY POST BLOCKED-OUT (MOD.) CORRUGATED-BEAM GUIDE RAILING (SHEET 2 OF 2) (ERRATA ISSUED BY EB 14-025) | EB 13-028 | 05/08/14 |
| 606-10 | HEAVY POST BLOCKED-OUT (MOD.) CORRUGATED-BEAM MEDIAN BARRIER (ERRATA ISSUED BY EB 18-003) | EB 13-028 | 05/08/14 |
| 606-11 | GRADING DETAILS FOR PROPRIETARY HPBO (MOD.) TERMINALS | EB 13-028 | 05/08/14 |
| 606-13 | SINGLE-SLOPE CONCRETE HALF SECTION BARRIER | EB 13-028 | 05/08/14 |
| 606-14 | SINGLE-SLOPE CONCRETE MEDIAN BARRIER AND SINGLE-SLOPE CONCRETE WIDE BARRIER (ERRATA ISSUED BY EB 12-026) | EB 08-036 | 01/08/09 |
| 606-15 | SINGLE-SLOPE CONCRETE BARRIER TERMINAL SECTION - RAMPED TERMINAL (ERRATA ISSUED BY EB 12-026) | EB 08-036 | 01/08/09 |
| 606-19 | TRANSITION: BOX - CABLE | EB 12-003 | 09/06/12 |
| 606-20 | TRANSITION: BOX - W-BEAM (MOD.) (ERRATA ISSUED BY EB 16-008 & EB 18-003) | EB 08-036 | 01/08/09 |
| 606-21 | TRANSITION: BOX - HPBO (MOD.) (ERRATA ISSUED BY EB 18-003) | EB 13-028 | 05/08/14 |
| 606-22 | TRANSITION: BOX - SINGLE SLOPE (SHEET 1 OF 3) (ERRATA ISSUED BY EB 13-042) | EB 08-036 | 01/08/09 |
| | TRANSITION: BOX - SINGLE SLOPE (SHEET 2 OF 3) (ERRATA ISSUED BY EB 14-025 & EB 18-003) | EB 08-036 | 01/08/09 |
| | TRANSITION: BOX - SINGLE SLOPE (SHEET 3 OF 3) | EB 13-028 | 05/08/14 |
| 606-24 | TRANSITION: BOX MEDIAN - WEAK POST AND HPBO (MOD.) MEDIAN (SHEET 1 OF 2) (ERRATA ISSUED BY EB 18-003) | EB 13-028 | 05/08/14 |
| | TRANSITION: BOX MEDIAN - WEAK POST AND HPBO (MOD.) MEDIAN (SHEET 2 OF 2) (ERRATA ISSUED BY EB 14-025 & EB 18-023) | EB 13-028 | 05/08/14 |
| 606-25 | TRANSITION: BOX MEDIAN - SINGLE SLOPE MEDIAN (SHEET 1 OF 3) (ERRATA ISSUED BY EB 13-042) | EB 08-036 | 01/08/09 |
| | TRANSITION: BOX MEDIAN - SINGLE SLOPE MEDIAN (SHEET 2 OF 3) | EB 08-036 | 01/08/09 |
| | TRANSITION: BOX MEDIAN - SINGLE SLOPE MEDIAN (SHEET 3 OF 3) | EB 08-036 | 01/08/09 |
| 606-27 | TRANSITION: WEAK POST - HPBO (MOD.) GUIDE RAIL AND MEDIAN BARRIER (ERRATA ISSUED BY EB 18-023) | EB 13-028 | 05/08/14 |

| SHEET NO. | SUBJECT | ISSUED BY | EFFECTIVE |
|-----------|--|-----------|-----------|
| 606-28 | TRANSITION: HPBO (MOD.) - SINGLE SLOPE HALF SECTION (SHEET 1 OF 3) | EB 13-028 | 05/08/14 |
| | TRANSITION: HPBO (MOD.) - SINGLE SLOPE HALF SECTION (SHEET 2 OF 3) | EB 13-028 | 05/08/14 |
| | TRANSITION: HPBO (MOD.) - SINGLE SLOPE HALF SECTION (SHEET 3 OF 3) | EB 13-028 | 05/08/14 |
| 606-29 | TRANSITION: HPBO (MOD.) MEDIAN - SINGLE SLOPE MEDIAN (SHEET 1 OF 3) (ERRATA ISSUED BY EB 14-025 & EB 18-023) | EB 13-028 | 05/08/14 |
| | TRANSITION: HPBO (MOD.) MEDIAN - SINGLE SLOPE MEDIAN (SHEET 2 OF 3) (ERRATA ISSUED BY EB 18-023) | EB 13-028 | 05/08/14 |
| | TRANSITION: HPBO (MOD.) MEDIAN - SINGLE SLOPE MEDIAN (SHEET 3 OF 3) | EB 13-028 | 05/08/14 |
| 606-31 | TRANSITION: WIDE - NORMAL WIDTH SINGLE SLOPE MEDIAN (ERRATA ISSUED BY EB 12-026) | EB 08-036 | 01/08/09 |
| 606-32 | TRANSITION: HALF-SECTION TO FULL-SECTION SINGLE SLOPE CONCRETE BARRIER | EB 13-049 | 05/08/14 |
| 606-33 | W-BEAM GUIDE RAILING (SHEET 1 OF 2) (MAINTENANCE SUPPORT) | EB 08-036 | 01/08/09 |
| | W-BEAM GUIDE RAILING (SHEET 2 OF 2) (MAINTENANCE SUPPORT) (ERRATA ISSUED BY EB 18-023) | EB 08-036 | 01/08/09 |
| 606-35 | CONCRETE BARRIER (CAST-IN-PLACE) (MAINTENANCE SUPPORT) | EB 08-036 | 01/08/09 |
| 606-36 | PRECAST CONCRETE BARRIER | EB 11-013 | 01/12/12 |
| 606-37 | MACHINE FORMED CONCRETE BARRIER | EB 08-036 | 01/08/09 |
| 606-38 | TRANSITION: BOX BEAM - W-BEAM (MAINTENANCE SUPPORT) | EB 08-036 | 01/08/09 |
| 606-40 | TRANSITION: HPBO - JERSEY SHAPE (MAINTENANCE SUPPORT) | EB 08-036 | 01/08/09 |
| 606-41 | TRANSITION: CONCRETE WALL - JERSEY MEDIAN (MAINTENANCE SUPPORT) | EB 08-036 | 01/08/09 |
| 606-42 | TRANSITION: CONCRETE BARRIER BETWEEN STANDARD (NJ) AND SINGLE SLOPE CONCRETE SHAPES | EB 08-036 | 01/08/09 |
| 606-43 | HPBO GUIDE RAILING AND TRANSITIONS (8 SHEETS) (MAINTENANCE SUPPORT) (ERRATA ISSUED BY EB 18-023) | EB 13-028 | 05/08/14 |
| 606-44 | HPBO MEDIAN BARRIER AND TRANSITIONS (5 SHEETS) (MAINTENANCE SUPPORT) (ERRATA ISSUED BY EB 18-023) | EB 13-028 | 05/08/14 |
| 607-01 | R.O.W. FENCING | EB 08-036 | 01/08/09 |
| 607-04 | CHAIN LINK FENCE WITH TOP RAIL (ERRATA ISSUED BY EB 13-042) | EB 08-036 | 01/08/09 |
| 607-05 | CHAIN LINK FENCE WITH TOP TENSION WIRE (ERRATA ISSUED BY EB 13-042) | EB 08-036 | 01/08/09 |
| 607-06 | GATES AND CHAIN LINK FENCE ADJACENT TO GATES | EB 08-036 | 01/08/09 |



U.S. CUSTOMARY STANDARD SHEET

INDEX OF SHEETS EFFECTIVE
05/01/2019
(LATEST CHANGES HIGHLIGHTED)
BOOK 2

| SHEET NO. | SUBJECT | ISSUED BY | EFFECTIVE |
|--------------------|---|-----------|-----------|
| BOOK 3 of 4 | | | |
| 608-01 | SIDEWALK CURB RAMP DETAILS (SHEET 1 OF 9) | EB 16-012 | 05/01/16 |
| | SIDEWALK CURB RAMP DETAILS (SHEET 2 OF 9) | EB 17-042 | 10/05/17 |
| | SIDEWALK CURB RAMP DETAILS (SHEET 3 OF 9) | EB 16-012 | 05/01/16 |
| | SIDEWALK CURB RAMP DETAILS (SHEET 4 OF 9) | EB 16-012 | 05/01/16 |
| | SIDEWALK CURB RAMP DETAILS (SHEET 5 OF 9) | EB 16-012 | 05/01/16 |
| | SIDEWALK CURB RAMP DETAILS (SHEET 6 OF 9) | EB 16-012 | 05/01/16 |
| | SIDEWALK CURB RAMP DETAILS (SHEET 7 OF 9) | EB 16-012 | 05/01/16 |
| | SIDEWALK CURB RAMP DETAILS (SHEET 8 OF 9) | EB 16-012 | 05/01/16 |
| 608-02 | ACCESSIBLE PARKING FOR PERSONS WITH DISABILITIES DETAILS | EB 16-012 | 05/01/16 |
| 608-03 | RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 1 OF 9) | EB 16-012 | 05/01/16 |
| | RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 2 OF 9) | EB 16-012 | 05/01/16 |
| | RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 3 OF 9) | EB 16-012 | 05/01/16 |
| | RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 4 OF 9) | EB 16-012 | 05/01/16 |
| | RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 5 OF 9) | EB 16-012 | 05/01/16 |
| | RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 6 OF 9) | EB 16-012 | 05/01/16 |
| | RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 7 OF 9) | EB 16-012 | 05/01/16 |
| | RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 8 OF 9) | EB 16-012 | 05/01/16 |
| | RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 9 OF 9) | EB 16-012 | 05/01/16 |
| 608-07 | RAISED CROSSWALK DETAILS (SHEET 1 OF 3) | EB 16-012 | 05/01/16 |
| | RAISED CROSSWALK DETAILS (SHEET 2 OF 3) | EB 16-012 | 05/01/16 |
| | RAISED CROSSWALK DETAILS (SHEET 3 OF 3) | EB 16-012 | 05/01/16 |
| 609-01 | STONE CURB AND GRANITE CURB | EB 16-019 | 09/01/16 |
| 609-02 | MISCELLANEOUS CURB DETAILS | EB 13-007 | 01/09/14 |
| 609-03 | CONCRETE CURB, CURB AND GUTTER, AND HOT MIX ASPHALT CURB | EB 08-036 | 01/08/09 |
| 609-04 | GRANITE SLOPED CURB DETAILS, TYPE S | EB 13-007 | 01/09/14 |
| 611-01 | LANDSCAPE PLANTING DETAILS (SHEET 1 OF 2) (ERRATA ISSUED BY EB 13-042) | EB 12-011 | 09/06/12 |
| | LANDSCAPE PLANTING DETAILS (SHEET 2 OF 2) | EB 12-011 | 09/06/12 |
| 619-01 | TEMPORARY CONCRETE BARRIER (SHEET 1 OF 5) (ERRATA ISSUED BY EB 14-025) | EB 09-025 | 01/07/10 |
| | TEMPORARY CONCRETE BARRIER (SHEET 2 OF 5) (ERRATA ISSUED BY EB 18-023) | EB 09-025 | 01/07/10 |
| | TEMPORARY CONCRETE BARRIER (SHEET 3 OF 5) (ERRATA ISSUED BY EB 13-042) | EB 10-034 | 01/06/11 |
| | TEMPORARY CONCRETE BARRIER (SHEET 4 OF 5) | EB 17-005 | 09/01/17 |
| | TEMPORARY CONCRETE BARRIER (SHEET 5 OF 5) | EB 17-005 | 09/01/17 |
| 619-02 | TYPE III CONSTRUCTION BARRICADES (SHEET 1 OF 2) | EB 08-036 | 01/08/09 |
| | TYPE III CONSTRUCTION BARRICADES (SHEET 2 OF 2) | EB 08-036 | 01/08/09 |
| 619-04 | PORTABLE TEMPORARY WOODEN SIGN SUPPORT | EB 08-036 | 01/08/09 |
| 619-10 | WORK ZONE TRAFFIC CONTROL GENERAL NOTES | EB 08-036 | 01/08/09 |
| 619-11 | WORK ZONE TRAFFIC CONTROL LEGENDS AND NOTES | EB 08-036 | 01/08/09 |
| 619-12 | SIGN TABLE (SHEET 1 OF 2) | EB 12-010 | 05/03/12 |
| | SIGN TABLE (SHEET 2 OF 2) | EB 12-010 | 05/03/12 |
| 619-20 | SHOULDER CLOSURE 2-LANE 2-WAY ROADWAY | EB 09-025 | 01/07/10 |
| 619-21 | SHOULDER CLOSURE 2-LANE 2-WAY ROADWAY MULTIPLE WORK LOCATIONS | EB 09-025 | 01/07/10 |
| 619-22 | SHOULDER CLOSURE EXPRESSWAY / FREEWAY | EB 08-036 | 01/08/09 |
| 619-23 | SHOULDER CLOSURE EXPRESSWAY / FREEWAY RAMP APPROACH | EB 08-036 | 01/08/09 |

| SHEET NO. | SUBJECT | ISSUED BY | EFFECTIVE |
|-----------|--|-----------|-----------|
| 619-24 | PARTIAL EXIT RAMP CLOSURE EXPRESSWAY / FREEWAY | EB 09-025 | 01/07/10 |
| 619-30 | SINGLE LANE CLOSURE MULTI LANE HIGHWAY | EB 08-036 | 01/08/09 |
| 619-31 | SINGLE LANE CLOSURE MULTI LANE DIVIDED HIGHWAY | EB 08-036 | 01/08/09 |
| 619-32 | SINGLE LANE CLOSURE MULTI LANE HIGHWAY / EXPRESSWAY / FREEWAY | EB 08-036 | 01/08/09 |
| 619-33 | SINGLE LANE CLOSURE NEAR ENTRANCE RAMP EXPRESSWAY / FREEWAY | EB 09-025 | 01/07/10 |
| 619-34 | SINGLE LANE CLOSURE NEAR EXIT RAMP EXPRESSWAY / FREEWAY | EB 09-025 | 01/07/10 |
| 619-40 | DOUBLE LANE CLOSURE EXPRESSWAY / FREEWAY | EB 08-036 | 01/08/09 |
| 619-41 | DOUBLE INTERIOR LANE CLOSURE MULTI LANE HIGHWAY | EB 08-036 | 01/08/09 |
| 619-50 | SIDEWALK DETOUR OR DIVERSION | EB 09-025 | 01/07/10 |
| 619-51 | CROSSWALK CLOSURE AND PEDESTRIAN DETOUR | EB 08-036 | 01/08/09 |
| 619-60 | FLAGGING OPERATION 2-LANE 2-WAY ROADWAY | EB 09-025 | 01/07/10 |
| 619-61 | FLAGGING OPERATION 2-LANE 2-WAY ROADWAY INTERSECTION | EB 08-036 | 01/08/09 |
| 619-62 | TEMPORARY TRAFFIC SIGNAL 2-LANE 2-WAY ROADWAY | EB 08-036 | 01/08/09 |
| 619-63 | SINGLE LANE SHIFT 2-LANE 2-WAY ROADWAY WITH CENTER TURN LANE | EB 08-036 | 01/08/09 |
| 619-64 | CENTER TURN LANE CLOSURE 2-LANE 2-WAY ROADWAY WITH CENTER TURN LANE | EB 08-036 | 01/08/09 |
| 619-65 | MULTI LANE SHIFT EXPRESSWAY / FREEWAY | EB 08-036 | 01/08/09 |
| 619-66 | ROAD CLOSURE WITH OFF SITE DETOUR 2-LANE 2-WAY ROADWAY | EB 08-036 | 01/08/09 |
| 624-01 | CONCRETE GUTTER (ERRATA ISSUED BY EB 17-041) | EB 11-013 | 01/12/12 |
| 625-01 | R.O.W. AND SURVEY MARKERS | EB 17-047 | 05/01/18 |
| 630-01 | HIGHWAY BARRIER AND HIGHWAY-RAILROAD BARRICADE | EB 08-036 | 01/08/09 |
| 632-01 | PRECAST MODULAR WALLS (SHEET 1 OF 2) | EB 08-036 | 01/08/09 |
| | PRECAST MODULAR WALLS (SHEET 2 OF 2) | EB 08-036 | 01/08/09 |



U.S. CUSTOMARY STANDARD SHEET

INDEX OF SHEETS EFFECTIVE
05/01/2019
(LATEST CHANGES HIGHLIGHTED)
BOOK 3

| SHEET NO. | SUBJECT | ISSUED BY | EFFECTIVE |
|-----------|---|-----------|-----------|
| | BOOK 4 of 4 | | |
| 645-01 | STANDARD SIGN BLANK DETAILS (SHEET 1 OF 2) ERRATA ISSUED BY EB 18-003 | EB 09-025 | 01/07/10 |
| | STANDARD SIGN BLANK DETAILS (SHEET 2 OF 2) ERRATA ISSUED BY EB 18-003 | EB 09-025 | 01/07/10 |
| 645-02 | ROUTE MARKER ASSEMBLIES | EB 09-025 | 01/07/10 |
| 645-03 | POSITIONING OF TRAFFIC SIGNS (SHEET 1 OF 2) | EB 09-025 | 01/07/10 |
| | POSITIONING OF TRAFFIC SIGNS (SHEET 2 OF 2) | EB 09-025 | 01/07/10 |
| 645-05 | TOURIST, BUSINESS, AND RAMP SERVICE SIGNS (SHEET 1 OF 2) | EB 09-025 | 01/07/10 |
| | TOURIST, BUSINESS, AND RAMP SERVICE SIGNS (SHEET 2 OF 2) | EB 09-025 | 01/07/10 |
| 645-06 | TOURIST ORIENTED BUSINESS SIGNS (SHEET 1 OF 2) | EB 09-025 | 01/07/10 |
| | TOURIST ORIENTED BUSINESS SIGNS (SHEET 2 OF 2) | EB 09-025 | 01/07/10 |
| 645-07 | SPECIFIC SERVICES SIGNS (SHEET 1 OF 2) (ERRATA ISSUED BY EB 12-026) | EB 09-025 | 01/07/10 |
| | SPECIFIC SERVICES SIGNS (SHEET 2 OF 2) | EB 08-036 | 01/08/09 |
| 645-09 | SIGN PANEL DETAILS FOR GUIDE, INFORMATION, AND OTHER SIGNS (ERRATA ISSUED BY EB 13-042 & 18-023) | EB 12-040 | 05/02/13 |
| 645-10 | MULTIPLE POST SIGN INSTALLATION USING TYPE B SIGN POSTS (ERRATA ISSUED BY EB 12-026) | EB 09-025 | 01/07/10 |
| 645-11 | BI-DIRECTIONAL BREAKAWAY BASE AND HINGE ASSEMBLY | EB 09-025 | 01/07/10 |
| 645-12 | OMNI-DIRECTIONAL BREAKAWAY BASE AND HINGE ASSEMBLY | EB 09-025 | 01/07/10 |
| 645-14 | POLE MOUNTED SIGNS (ERRATA ISSUED BY EB 14-025) | EB 08-045 | 05/07/09 |
| 646-11 | REFERENCE MARKER DETAILS (ERRATA ISSUED BY EB 14-025) | EB 11-006 | 09/01/11 |
| 646-12 | DELINEATOR MOUNTING ON CONCRETE MEDIAN BARRIER DETAILS | EB 10-020 | 01/06/11 |
| 646-13 | STANDARD AND LARGE DELINEATOR PANEL DETAILS | EB 10-020 | 01/06/11 |
| 646-14 | STANDARD DELINEATOR BRACKET AND FASTENER DETAILS | EB 10-020 | 01/06/11 |
| 646-15 | DELINEATOR SNOWPLOWING MARKER AND SUPPLEMENTARY SNOWPLOWING MARKER DETAILS AND NOTES | EB 11-006 | 09/01/11 |
| 646-16 | REFERENCE MARKER LARGE DELINEATOR SNOWPLOWING AND SUPPLEMENTARY SNOWPLOWING MARKER LAYOUT ON FREEWAYS AND EXPRESSWAYS | EB 10-020 | 01/06/11 |
| 649-02 | MILLED-INAUDIBLE ROADWAY DELINEATORS | EB 13-040 | 01/09/14 |
| 649-03 | CENTERLINE AUDIBLE ROADWAY DELINEATORS | EB 13-040 | 01/09/14 |
| 649-04 | SECONDARY HIGHWAY AUDIBLE ROADWAY DELINEATORS | EB 16-030 | 01/01/17 |
| 655-01 | RECTANGULAR GRATES | EB 08-036 | 01/08/09 |
| 655-02 | PARALLEL BAR FRAMES AND GRATES (ERRATA ISSUED BY EB 14-025) | EB 08-049 | 05/07/09 |
| 655-03 | CAST MANHOLE FRAMES, GRATES AND COVERS | EB 08-049 | 05/07/09 |
| 655-04 | RETICULINE GRATES (ERRATA ISSUED BY EB 16-008 & EB 18-003) | EB 12-031 | 01/10/13 |
| 655-05 | CAST FRAMES AND CURB BOXES AND WELDED FRAMES (ERRATA ISSUED BY EB 13-042 & 18-023) | EB 09-025 | 01/07/10 |
| 655-06 | PROOF LOADED CAST STEEL OR IRON MANHOLE FRAMES, GRATES AND COVERS (ERRATA ISSUED BY EB 14-025) | EB 08-036 | 01/08/09 |
| 655-07 | WELDED FRAMES AND PROOF LOADED CAST STEEL OR IRON FRAMES AND CURB BOXES (ERRATA ISSUED BY EB 16-008 & 18-023) | EB 08-049 | 05/07/09 |
| 655-08 | TELESCOPING MANHOLE CASTING AND RING | EB 08-036 | 01/08/09 |
| 663-01 | WATER MAIN PIPE INSTALLATION DETAILS (ERRATA ISSUED BY EB 18-003) | EB 13-038 | 01/09/14 |
| 663-02 | WATER MAIN HORIZONTAL THRUST RESTRAINT DETAILS | EB 11-025 | 05/03/12 |
| 663-03 | WATER MAIN THRUST RESTRAINT DETAILS | EB 11-025 | 05/03/12 |
| 663-04 | WATER MAIN UTILITY CROSSING RELOCATION DETAILS | EB 08-036 | 01/08/09 |
| 663-05 | WATER MAIN HYDRANT AND VALVE DETAILS | EB 08-036 | 01/08/09 |
| 663-06 | WATER MAIN HYDRANT FENDER DETAILS | EB 08-036 | 01/08/09 |
| 663-07 | WATER MAIN SERVICE CONNECTION DETAILS | EB 08-036 | 01/08/09 |
| 664-01 | SANITARY SEWER MAIN PIPE INSTALLATION DETAILS (ERRATA ISSUED BY EB 18-003) | EB 13-038 | 01/09/14 |
| 670-01 | LAMPPOST FOUNDATIONS | EB 08-036 | 01/08/09 |
| 670-02 | LIGHT STANDARD DETAILS | EB 08-036 | 01/08/09 |
| 670-03 | DAVIT ARM, WOOD POLE BRACKET ARM AND DEEP FOUNDATIONS (ERRATA ISSUED BY EB 12-026) | EB 08-036 | 01/08/09 |

| SHEET NO. | SUBJECT | ISSUED BY | EFFECTIVE |
|-----------|---|-----------|-----------|
| 680-01 | TRAFFIC SIGNAL POLE FOUNDATIONS | EB 17-027 | 01/01/18 |
| 680-02 | PRECAST STANDARD RECTANGULAR PULLBOXES, FRAMES AND COVERS | EB 11-013 | 01/12/12 |
| 680-03 | STANDARD CIRCULAR PULLBOXES, FRAMES AND COVERS | EB 11-013 | 01/12/12 |
| 680-04 | PULLBOX, CONDUIT AND GROUND ROD INSTALLATION DETAILS | EB 18-041 | 01/01/18 |
| 680-05 | BASE - AND POLE - MOUNTED CABINET INSTALLATION DETAILS | EB 18-041 | 01/01/18 |
| 680-06 | STANDARD TRAFFIC SIGNAL POLES (SHEET 1 OF 2) | EB 08-036 | 01/08/09 |
| | STANDARD TRAFFIC SIGNAL POLES (SHEET 2 OF 2) | EB 08-036 | 01/08/09 |
| 680-07 | SPAN WIRE MOUNTED TRAFFIC SIGNAL INSTALLATION DETAILS | EB 13-045 | 05/08/14 |
| 680-08 | MAST ARM AND POLE MOUNTED TRAFFIC SIGNAL INSTALLATION DETAILS | EB 18-041 | 01/01/18 |
| 680-10 | PEDESTRIAN SIGNALS AND FLASHING BEACON INSTALLATION DETAILS | EB 08-036 | 01/08/09 |
| 680-11 | SIGNAL HEAD ASSEMBLY DETAILS | EB 13-045 | 05/08/14 |
| 680-12 | SINGLE SPAN WIRE MOUNTED SIGN INSTALLATION DETAILS | EB 18-041 | 01/01/18 |
| 680-13 | DUAL SPAN WIRE AND MAST ARM SIGN INSTALLATION DETAILS | EB 18-041 | 01/01/18 |
| 680-14 | INDUCTANCE LOOP VEHICLE DETECTOR INSTALLATION DETAILS | EB 18-041 | 01/01/18 |
| 680-15 | MAGNETIC VEHICLE DETECTOR INSTALLATION DETAILS (DISAPPROVED) | EB 18-041 | 01/01/18 |
| 680-16 | WOOD POLE DETAILS | EB 18-041 | 01/01/18 |
| 680-17 | UTILITY CLEARANCES TOO TRAFFIC SIGNALS | EB 18-041 | 01/01/18 |
| 685-01 | PAVEMENT MARKING DETAILS (SHEET 1 OF 9) | EI 18-008 | 01/01/19 |
| | PAVEMENT MARKING DETAILS (SHEET 2 OF 9) | EB 12-036 | 05/03/13 |
| | PAVEMENT MARKING DETAILS (SHEET 3 OF 9) | EB 12-036 | 05/03/13 |
| | PAVEMENT MARKING DETAILS (SHEET 4 OF 9) | EB 12-036 | 05/03/13 |
| | PAVEMENT MARKING DETAILS (SHEET 5 OF 9) | EB 12-036 | 05/03/13 |
| | PAVEMENT MARKING DETAILS (SHEET 6 OF 9) (ERRATA ISSUED BY EB 13-042) | EB 12-036 | 05/03/13 |
| | PAVEMENT MARKING DETAILS (SHEET 7 OF 9) (ERRATA ISSUED BY EB 17-041) | EB 12-036 | 05/03/13 |
| | PAVEMENT MARKING DETAILS (SHEET 8 OF 9) (ERRATA ISSUED BY EB 17-041) | EB 12-036 | 05/03/13 |
| | PAVEMENT MARKING DETAILS (SHEET 9 OF 9) (ERRATA ISSUED BY EB 13-041) | EB 12-036 | 05/03/13 |



**Department of
Transportation**

U.S. CUSTOMARY STANDARD SHEET





INDEX OF SHEETS EFFECTIVE
05/01/2019
(LATEST CHANGES HIGHLIGHTED)
BOOK 4
(THIS BOOK)

| A | B | C | H | AREA (SQ. FT.) | SEE NOTE |
|-----|-----|-----|------|----------------|----------|
| 12" | 12" | 8" | 1/2" | 1.0 | |
| 18" | 18" | 12" | 1/2" | 2.3 | |
| 12" | 6" | 4" | 1/2" | 0.5 | |
| 12" | 8" | 4" | 1/2" | 0.7 | |
| 12" | 9" | 4" | 1/2" | 0.8 | |
| 18" | 6" | 4" | 1/2" | 0.8 | |
| 18" | 12" | 6" | 1/2" | 1.5 | |
| 6" | 12" | 6" | 1/2" | 0.5 | |
| 8" | 16" | 10" | 1/2" | 0.9 | |
| 9" | 12" | 6" | 1/2" | 0.8 | |
| 12" | 18" | 12" | 1/2" | 1.5 | |
| 12" | 24" | 18" | 1/2" | 2.0 | |
| 12" | 30" | 24" | 1/2" | 2.5 | |
| 12" | 36" | 14" | 1/2" | 3.0 | 2 |
| 12" | 48" | 18" | 1/2" | 4.0 | 2 |
| 12" | 54" | 24" | 1/2" | 4.5 | 2 |
| 12" | 60" | 24" | 1/2" | 5.0 | 2 |
| 18" | 24" | 18" | 1/2" | 3.0 | |
| 18" | 30" | 24" | 1/2" | 3.8 | |
| 18" | 36" | 14" | 1/2" | 4.5 | 2 |
| 18" | 48" | 18" | 1/2" | 6.0 | 2 |
| 18" | 54" | 24" | 1/2" | 6.8 | 2 |
| 18" | 60" | 24" | 1/2" | 7.5 | 2 |


| A | B | C | D | H | AREA (SQ. FT.) | SEE NOTE |
|-----|-----|-----|-----|------|----------------|----------|
| 21" | 21" | 15" | 15" | 1/2" | 3.1 | |
| 24" | 24" | 18" | 18" | 1/2" | 4.0 | |
| 30" | 30" | 24" | 24" | 1/2" | 6.3 | |
| 20" | 18" | 12" | 15" | 1/2" | 2.5 | |
| 21" | 15" | 9" | 15" | 1/2" | 2.2 | |
| 24" | 6" | 3" | 18" | 1/2" | 1.0 | |
| 24" | 8" | 4" | 18" | 1/2" | 1.3 | |
| 24" | 12" | 6" | 18" | 1/2" | 2.0 | |
| 24" | 15" | 9" | 18" | 1/2" | 2.5 | |
| 24" | 18" | 12" | 18" | 1/2" | 3.0 | |
| 30" | 10" | 6" | 24" | 1/2" | 2.1 | |
| 30" | 15" | 9" | 24" | 1/2" | 3.1 | |
| 30" | 18" | 12" | 24" | 1/2" | 3.8 | |
| 30" | 21" | 15" | 24" | 1/2" | 4.4 | |
| 30" | 24" | 18" | 24" | 1/2" | 5.0 | |
| 24" | 30" | 22" | 18" | 1/2" | 5.0 | |
| 24" | 36" | 24" | 18" | 1/2" | 6.0 | |
| 30" | 36" | 24" | 24" | 1/2" | 7.5 | |
| 24" | 54" | 24" | 18" | 1/2" | 9.0 | 2 |
| 30" | 42" | 18" | 24" | 1/2" | 8.8 | 2 |

| A | B | C | D | H | POST SPACING | AREA (SQ. FT.) | SEE NOTE |
|-----|-----|-----|---------|--------|--------------|----------------|----------|
| 36" | 12" | 6" | 15" | 1/2" | 18" | 3.0 | |
| 36" | 18" | 12" | 15" | 1/2" | 18" | 4.5 | |
| 36" | 20" | 12" | 15" | 1/2" | 18" | 5.0 | |
| 36" | 24" | 18" | 15" | 1/2" | 18" | 6.0 | |
| 36" | 30" | 24" | 15" | 1/2" | 18" | 7.5 | |
| 36" | 36" | 24" | 15" | 3" | 18" | 9.0 | |
| 42" | 21" | 12" | 18" | 1/2" | 18" | 6.1 | |
| 42" | 26" | 18" | 18" | 1 1/8" | 18" | 7.6 | |
| 42" | 30" | 24" | 18" | 1 1/8" | 18" | 8.8 | |
| 45" | 36" | 24" | 19 1/2" | 2 1/4" | 24" | 11.3 | |
| 48" | 18" | 12" | 21" | 1/2" | 24" | 6.0 | |
| 48" | 24" | 18" | 21" | 1 1/8" | 24" | 8.0 | |
| 48" | 30" | 24" | 21" | 2 1/4" | 24" | 10.0 | |
| 48" | 36" | 24" | 21" | 2 1/4" | 24" | 12.0 | |
| 54" | 18" | 12" | 24" | 1 1/8" | 24" | 6.8 | |
| 60" | 24" | 18" | 27" | 1/2" | 30" | 10.0 | |
| 60" | 30" | 24" | 27" | 2 1/4" | 30" | 12.5 | |
| 36" | 48" | 18" | 15" | 2 1/4" | 18" | 12.0 | 2 |
| 36" | 54" | 24" | 15" | 2 1/4" | 18" | 13.5 | 2 |
| 36" | 60" | 24" | 15" | 2 1/4" | 18" | 15.0 | 2 |
| 42" | 60" | 24" | 18" | 3" | 24" | 17.5 | 2 |
| 48" | 60" | 24" | 21" | 3" | 24" | 20.0 | 2 |
| 42" | 42" | 18" | 21" | 3" | 24" | 12.3 | 2 |
| 48" | 48" | 18" | 21" | 3" | 24" | 16.0 | 2 |
| 60" | 48" | 18" | 27" | 3" | 30" | 20.0 | 2 |
| 64" | 42" | 18" | 27" | 3" | 30" | 18.7 | 2 |

| A | B | C | D | E | G | H | POST SPACING | AREA (SQ. FT.) | PAYMENT AREA (SQ. FT.) |
|-----|-----|-----|----|-----|-----|--------|--------------|----------------|------------------------|
| 40" | 30" | 10" | | | | 1 1/8" | 9" | 3.9 | 7.9 |
| 48" | 36" | 12" | | | | 2" | 12" | 5.6 | 11.1 |
| 64" | 48" | 11" | 6" | 18" | 17" | 3" | 12" | 9.9 | 19.8 |



| A | C | D | E | G | H | POST SPACING | AREA (SQ. FT.) | PAYMENT AREA (SQ. FT.) |
|-----|-----|-----|-----|----|--------|--------------|----------------|------------------------|
| 30" | 16" | 12" | 12" | 4" | 1 1/8" | | 5.2 | 6.3 |
| 36" | 18" | 18" | 15" | 4" | 2 1/4" | 18" | 7.3 | 9.0 |
| 48" | 24" | 24" | 21" | 6" | 3" | 24" | 13.0 | 16.0 |



NOTES:

- SIGN BLANKS SHALL BE 10 GAUGE THICK ALUMINUM. FIBERGLASS REINFORCED PLASTIC MAY BE USED FOR SIGN PANELS UP TO 48" X 48".
- THESE PANELS USE THE "C" DIMENSION TWICE FOR EITHER MOUNTING HOLES OR HORIZONTAL Z BARS.
- THE "PAYMENT AREA", WHICH INCLUDES FABRICATION WASTAGE, SHALL BE USED ONLY FOR DETERMINING PAYMENT FOR NON-RECTANGULAR SIGN BLANKS.
- INTERMEDIATE SIZE SIGN BLANKS THAT ARE NOT SHOWN, SHALL BE FABRICATED SIMILAR TO THE CLOSEST SHOWN SIZE.
- SIGN PANELS WIDER THAN SHOWN SHALL BE FABRICATED AS SHOWN ON THE CURRENT "LARGE GUIDE SIGNS" STANDARD SHEET.
- ADDITIONAL SIGN BLANK DIMENSIONS ARE GIVEN IN "STANDARD HIGHWAY SIGNS", FEDERAL HIGHWAY ADMINISTRATION.
- THE HORIZONTAL Z BAR LENGTH SHALL BE A MINIMUM OF 1" LONGER THAN THE CENTER TO CENTER DISTANCE BETWEEN EXTREME MOUNTING HOLES. WHERE POSTS ARE LOCATED AT THE END OF HORIZONTAL Z BAR, THE HORIZONTAL Z BAR SHALL EXTEND BEYOND THE SIDE OF THE POST A MINIMUM OF ONE 1/2" AND A MAXIMUM OF 2".
- ALUMINUM Z BARS WEIGHING ONE POUND PER FOOT AND MEASURING 2 3/8" X 1/4" X 3/16" MAY BE PREPUNCHED WITH 5/16" HOLES AT 1" CENTERS ALONG THE ENTIRE LENGTH.
- POST AND HORIZONTAL Z BAR ARRANGEMENTS ARE SHOWN FOR COMMON BLANKS. THESE ARRANGEMENTS MAY BE ADJUSTED AS NECESSARY WHERE A NUMBER OF SIGN BLANKS ARE GROUPED IN SIGN ASSEMBLIES OR WHERE ADDITIONAL POSTS ARE REQUIRED DUE TO POST CAPACITY LIMITATIONS.
- MATERIALS ARE PER SUBSECTIONS:
730-01 ALUMINUM SIGN PANELS
730-22 STIFFENERS, OVERHEAD BRACKETS AND MISCELLANEOUS HARDWARE
730-23 FIBERGLASS REINFORCED PLASTIC SIGN PANELS
- WHERE 730-05.02 REFLECTIVE SHEETING (CLASS B) OR TYPE IX IS REQUIRED, NYLON OR PLASTIC WASHERS SHALL BE INSTALLED BETWEEN FASTENER BOLT HEADS (OR NUTS) AND THE REFLECTIVE SHEETING ON THE SIGN FACE.
- POSTS AND POST FOOTINGS SHALL BE INSTALLED AS SPECIFIED ON THE APPROPRIATE STANDARD SHEETS OR AS PER MANUFACTURERS INSTRUCTIONS.
- THE TOP HOLES SHOWN ON THE HORIZONTAL Z BARS ARE FOR THE PANEL TO HORIZONTAL Z BAR CONNECTIONS. THE BOTTOM HOLES ON THE HORIZONTAL Z BARS ARE FOR THE HORIZONTAL Z BAR TO SIGN POST CONNECTIONS. THE HOLES SHOWN ON PANELS WITHOUT HORIZONTAL Z BARS ARE FOR PANEL TO POST CONNECTIONS.

ERRATA 1
ISSUED WITH EB 18-003



U.S. CUSTOMARY STANDARD SHEET

**SIGN BLANK DETAILS
(SHEET 1 OF 2)**

APPROVED OCTOBER 05, 2009

/S/ RICHARD W. LEE, P.E.
FOR THE DEPUTY CHIEF ENGINEER
(DESIGN)




ISSUED UNDER EB 09-025

645-01

| A | C | D | E | H | POST SPACING | AREA (SQ. FT.) |
|-----|-----|-----|-----|-----|--------------|----------------|
| 24" | 12" | | | 1" | | 4.0 |
| 30" | 18" | | | 1" | | 6.3 |
| 24" | 16" | 12" | | 1½" | | 4.0 |
| 30" | 20" | 15" | | 1⅞" | | 6.3 |
| 36" | 12" | 18" | 15" | 2½" | 18" | 9.0 |
| 48" | 16" | 24" | 21" | 3" | 24" | 16.0 |

| A | B | C | D | E | F | POST SPACING | AREA (SQ. FT.) | PAYMENT AREA (SQ. FT.) |
|-----|-----|-----|-----|-----|-----|--------------|----------------|------------------------|
| 24" | 24" | 18" | 12" | | | | 3.0 | 4.0 |
| 30" | 24" | 18" | 12" | | | | 4.0 | 5.0 |
| 36" | 36" | 24" | 18" | | | 18" | 6.8 | 9.0 |
| 45" | 36" | 24" | 18" | | | 18" | 9.1 | 11.3 |
| 48" | 48" | 18" | 18" | 18" | 12" | 24" | 12.1 | 16.0 |
| 60" | 48" | 18" | 18" | 24" | 12" | 24" | 16.2 | 20.0 |

| A | B | C | D | E | F | POST SPACING | AREA (SQ. FT.) | PAYMENT AREA (SQ. FT.) |
|-----|-----|-----|-----|-----|-----|--------------|----------------|------------------------|
| 24" | 24" | 18" | 18" | 6" | | | 3.2 | 4.0 |
| 30" | 24" | 18" | 24" | 12" | | | 3.8 | 5.0 |
| 36" | 36" | 24" | 24" | 12" | | 18" | 7.0 | 9.0 |
| 45" | 36" | 24" | 18" | 18" | | 18" | 8.8 | 11.3 |
| 48" | 48" | 16" | 10" | 16" | 19" | 24" | 12.4 | 16.0 |
| 60" | 48" | 16" | 10" | 16" | 25" | 24" | 15.5 | 20.0 |







| A | L | C | D | E | G | H | POST SPACING | AREA (SQ. FT.) | PAYMENT AREA (SQ. FT.) |
|-----|------|-----|-----|-----|----|-----|--------------|----------------|------------------------|
| 18" | 15" | 12" | | | | 1½" | | 1.0 | 1.9 |
| 24" | 21" | 12" | 15" | 2" | 3" | 1½" | | 1.8 | 3.5 |
| 30" | 27" | 14" | 18" | 4" | 4" | 1½" | | 2.7 | 5.7 |
| 36" | 31" | 18" | 24" | 4" | 4" | 2" | | 3.9 | 7.8 |
| 48" | 41.5 | 16" | 18" | 9" | 4" | 3" | 18" | 7.0 | 13.9 |
| 60" | 52 | 21" | 24" | 12" | 4" | 4" | 24" | 10.9 | 21.7 |

| A | C | D | E | POST SPACING | AREA (SQ. FT.) | PAYMENT AREA (SQ. FT.) |
|-----|-----|-----|-----|--------------|----------------|------------------------|
| 15" | 9" | | | | 1.3 | 1.6 |
| 18" | 12" | | | | 1.8 | 2.3 |
| 24" | 16" | 12" | | | 3.1 | 4.0 |
| 30" | 20" | 15" | | | 4.9 | 6.3 |
| 36" | 12" | 18" | 15" | 18" | 7.1 | 9.0 |
| 48" | 16" | 24" | 21" | 24" | 12.6 | 16.0 |

| A | C | D | E | POST SPACING | AREA (SQ. FT.) | PAYMENT AREA (SQ. FT.) |
|-----|-----|-----|-----|--------------|----------------|------------------------|
| 18" | 12" | | | | 1.8 | 2.3 |
| 24" | 14" | 12" | | | 3.1 | 4.0 |
| 30" | 18" | 15" | | | 5.0 | 6.3 |
| 36" | 12" | 18" | 15" | 18" | 7.0 | 9.0 |
| 48" | 16" | 24" | 21" | 24" | 12.5 | 16.0 |

| AREA (SQ. FT.) | PAYMENT AREA (SQ. FT.) | POST SPACING |
|----------------|------------------------|--------------|
| 5.4 | 1.3 | |
| 16.0 | 4.0 | |
| | | 24" |
| | | 12" |



Department of Transportation

U.S. CUSTOMARY STANDARD SHEET

SIGN BLANK DETAILS
(SHEET 2 OF 2)

APPROVED OCTOBER 05, 2009




/S/ RICHARD W. LEE, P.E.

FOR THE DEPUTY CHIEF ENGINEER (DESIGN)

ISSUED UNDER EB 09-025


645-01

ERRATA 1
ISSUED WITH EB 18-003




NOTES:

- THESE DETAILS ARE TYPICAL ONLY AND ARE TO BE USED BY THE CONTRACTOR AS GUIDES IN INSTALLING THE SIGN ARRANGEMENTS SHOWN ON THE PLANS.
- THE POST TYPE (TYPE A WITH OR WITHOUT SOIL PLATES OR EXTRA EMBEDMENT, HIGH CAPACITY TYPE A OR TYPE B) AND SIZE SHALL BE BASED ON THE SIGN AREA AND MOUNTING HEIGHT AS FOUND ON THE CURRENT MATERIALS DETAILS OR STANDARD SHEETS.
- POSTS SHALL BE ERECTED AS SHOWN ON THE CURRENT MATERIALS DETAILS OR STANDARD SHEETS. POSTS SHOULD NOT BE ERECTED IN OR STRADDLING THE DITCH LINE.
- HORIZONTAL Z BAR DIMENSIONS AND SPACING SHALL BE AS SHOWN ON THE CURRENT "SIGN BLANK DETAILS" STANDARD SHEETS. PANEL TO HORIZONTAL Z BAR CONNECTION DETAILS SHALL BE AS SHOWN ON THE CURRENT "SIGN PANEL DETAILS FOR INFO, GUIDE, AND OTHER SIGNS" STANDARD SHEET.
- SIGN ASSEMBLIES HAVING SIGN PANELS MOUNTED SIDE-BY-SIDE SHALL HAVE CONTINUOUS HORIZONTAL Z BARS.
- SIGNS WIDER THAN 30" SHALL USE TWO OR MORE POSTS.
- THE VERTICAL SPACING BETWEEN PANELS SHALL BE AS SHOWN (2" MAX.).
- THE VERTICAL DISTANCE TO THE BOTTOM OF THE SIGN SHALL BE DETERMINED AS FOLLOWS:
 - CLEARANCE - 7' FROM THE GROUND TO THE BOTTOM OF THE SIGN.
 - HEIGHT (ABOVE NEAR EDGE OF TRAVEL LANE OR ABOVE TOP OF CURB)
 - 7' (6' WITH SUPPLEMENTARY PANEL) ON CONVENTIONAL HIGHWAYS AND EXPRESSWAYS WHERE PARKED VEHICLES OR PEDESTRIAN ARE PRESENT.
 - 5' (4' WITH SUPPLEMENTARY PANEL) ON CONVENTIONAL HIGHWAYS AND EXPRESSWAYS WHERE NO PARKED VEHICLES OR PEDESTRIANS ARE PRESENT.
 - 7' (5' WITH LATERAL CLEARANCE GREATER THAN 30' ON FREEWAYS FOR GUIDE SIGNS. (WHERE FEASIBLE, A 30' MINIMUM LATERAL CLEARANCE IS REQUIRED FOR LARGE GUIDE SIGNS).
 - 7' ON FREEWAYS FOR REGULATORY, WARNING AND SMALL GUIDE SIGNS.
 - 5' (4' WITH SUPPLEMENTARY PANEL) ON RAMPS. (DIRECT CONNECT ROADWAYS SHALL BE CONSIDERED TO BE FREEWAYS, NOT RAMPS).
 - 4' MINIMUM ON BICYCLE PATHS. (5' MAX)
 - WHERE THERE ARE PHYSICAL LIMITATIONS OR VISIBILITY CONSIDERATIONS, THE SIGNS SHALL BE LOCATED AS ORDERED BY THE ENGINEER-IN-CHARGE.
- THE LATERAL CLEARANCE TO THE EDGE OF THE SIGN SHALL BE DETERMINED AS FOLLOWS:
 - SHOULDER WIDTH OF LESS THAN 6', 12' MINIMUM FROM THE EDGE OF TRAVEL LANE.
 - SHOULDER WIDTH OF 6' OR GREATER, 6' MINIMUM FROM THE EDGE OF SHOULDER.
 - CURBED SECTIONS, 2' TYP. FROM THE FACE OF CURB.
 - BICYCLE PATHS, 3' MINIMUM FROM THE EDGE OF PATH (6' MAX).
 - TYPE B OBJECT MARKERS SHOULD BE PLACED WITH THE NEAR EDGE OF THE MARKER IN LINE WITH THE EDGE OF THE OBSTRUCTION CLOSEST TO TRAFFIC.
 - WHERE THERE ARE PHYSICAL LIMITATIONS OR VISIBILITY CONSIDERATIONS, THE SIGNS SHALL BE LOCATED AS ORDERED BY THE ENGINEER-IN-CHARGE.
 - SEE STANDARD SHEET TITLED "POSITIONING OF TRAFFIC SIGNS (SHEET 2 OF 2)" WHEN GUIDE RAIL IS PRESENT.

| | |
|---|------------------------|
|  STATE OF NEW YORK DEPARTMENT OF TRANSPORTATION | |
| U.S. CUSTOMARY STANDARD SHEET | |
| POSITIONING OF TRAFFIC SIGNS (SHEET 1 OF 2) | |
| APPROVED OCTOBER 05, 2009 | ISSUED UNDER EB 09-025 |
| /S/ RICHARD W. LEE, P.E. FOR THE DEPUTY CHIEF ENGINEER (DESIGN) | |
| 645-03 | |

EFFECTIVE DATE: 01/07/10




GUIDE RAIL DISTANCE FOR NON-BREAKAWAY POSTS


| GUIDE RAIL TYPE / POST SPACING | MINIMUM DISTANCE |
|---|------------------|
| CABLE (POST 16'-0" O.C.) | 12'-0" |
| CABLE (POST 12'-0" O.C.) | 11'-0" |
| CABLE (POST 8'-0" O.C.) | 9'-0" |
| CORRUGATED BEAM (POST 12'-6" O.C.) | 9'-0" |
| CABLE (POST 4'-0" O.C.) | 8'-0" |
| CORRUGATED BEAM (POST 6'-3" O.C.) | 7'-0" |
| CORRUGATED BEAM (POST 4'-2" O.C.) | 6'-0" |
| 6" X 6" BOX BEAM (POST 6'-0" O.C.) | 6'-0" |
| HEAVY POST BLOCKED OUT CORRUGATED (POST 6'-3" O.C.) | 5'-6" |
| 6" X 6" BOX BEAM (POST 3'-0" O.C.) | 5'-0" |
| HEAVY POST BLOCKED OUT CORRUGATED (POST 3'-1/2" O.C.) | 3'-6" |

NOTE: IN ADDITION TO MEETING THE OFFSET REQUIREMENTS ON STANDARD SHEET TITLED "POSITIONING OF TRAFFIC SIGNS (SHEET 1 OF 2)" THE POST SHALL BE OFFSET FROM THE FACE OF THE GUIDE RAIL BY THE AMOUNT SHOWN IN THE TABLE ABOVE.


NOTE: ALL BACK TO BACK SIGNS SHALL BE MOUNTED AS SHOWN, INCLUDING STREET NAME SIGNS.




BACK TO BACK SIGN POSITIONING



GORE EXIT SIGN POSITIONING



PARKING SIGN POSITIONING



STANDARD SIGN POSITIONING

FOR LATERAL CLEARANCE < 30'
FOR > 30', SHOULD BE < 90°



STATE OF NEW YORK
DEPARTMENT OF TRANSPORTATION

U.S. CUSTOMARY STANDARD SHEET

POSITIONING OF TRAFFIC SIGNS
(SHEET 2 OF 2)

APPROVED OCTOBER 05, 2009

/S/ RICHARD W. LEE, P.E.
FOR THE DEPUTY CHIEF ENGINEER
(DESIGN)

ISSUED UNDER EB 09-025




645-03

EFFECTIVE DATE: 01/07/10




| VERTICAL POST SPACING AND HORIZONTAL STIFFENER SIZES | | | | |
|--|--------|----------------|---|---------------------------------------|
| WITH (2 POSTS) | | STIFFENERS | | |
| W | 3/5 W | 1/5 W | WIND ZONE | |
| | | | 70 MPH 80 MPH | |
| 3'-0" - 4'-0" | 2'-0" | 6" - 1'-0" | Z 2 3/8" x 1 1/4" x 3/16" @ 1.00 LB/FT | |
| 4'-6" - 5'-6" | 3'-0" | 9" - 1'-3" | | |
| 6'-0" - 7'-0" | 4'-0" | 1'-0" - 1'-6" | | |
| 7'-6" - 9'-0" | 5'-0" | 1'-3" - 1'-9" | | |
| 9'-6" - 10'-6" | 6'-0" | 2'-3" - 2'-3" | | |
| 11'-0" - 12'-0" | 7'-0" | 2'-0" - 2'-6" | | |
| 12'-6" - 14'-0" | 8'-0" | 2'-3" - 3'-0" | | |
| 14'-6" - 15'-6" | 9'-0" | 2'-9" - 3'-3" | | |
| 16'-0" - 17'-0" | 10'-0" | 3'-0" - 3'-6" | | |
| 17'-6" - 19'-0" | 11'-0" | 3'-3" - 4'-0" | | |
| 19'-6" - 20'-6" | 12'-0" | 3'-9" - 4'-3" | Z 3" x 2 1/16" x 1/4" @ 2.33 LB/FT | |
| 21'-0" - 22'-0" | 13'-0" | 4'-0" - 4'-6" | | |
| 22'-6" - 24'-0" | 14'-0" | 4'-3" - 5'-0" | | |
| 24'-6" - 25'-6" | 15'-0" | 4'-9" - 5'-3" | | |
| 26'-0" - 28'-0" | 16'-0" | 5'-0" - 6'-0" | | |
| 28'-6" - 31'-6" | 18'-0" | 5'-3" - 6'-9" | | |
| 32'-0" - 34'-6" | 20'-0" | 6'-0" - 7'-3" | | |
| 35'-0" - 38'-0" | 22'-0" | 6'-6" - 8'-0" | | |
| 38'-6" - 41'-6" | 24'-0" | 7'-3" - 8'-9" | | |
| 42'-0" - 44'-6" | 26'-0" | 8'-0" - 9'-3" | | Z 4" x 3 1/16" x 1/4" @ 2.85 LB/FT |
| 45'-0" - 48'-0" | 28'-0" | 8'-6" - 10'-0" | | |
| WITH (3 POSTS) | | | | |
| W | 1/3 W | 1/6 W | WIND ZONE | |
| | | | 70 MPH 80 MPH | |
| 13'-6" - 16'-0" | 5'-0" | 1'-9" - 3'-0" | Z 2 3/8" x 1 1/4" x 3/16" @ 1.00 LB/FT | |
| 16'-6" - 19'-0" | 6'-0" | 2'-3" - 3'-6" | | |
| 19'-6" - 22'-0" | 7'-0" | 2'-9" - 4'-0" | | |
| 22'-6" - 25'-0" | 8'-0" | 3'-3" - 4'-6" | | |
| 25'-6" - 28'-0" | 9'-0" | 3'-9" - 5'-0" | | |
| 28'-6" - 31'-0" | 10'-0" | 4'-3" - 5'-6" | | |
| 31'-6" - 34'-0" | 11'-0" | 4'-9" - 6'-0" | | |
| 34'-6" - 37'-0" | 12'-0" | 5'-3" - 6'-6" | | |
| 37'-6" - 40'-0" | 13'-0" | 5'-9" - 7'-0" | | |
| 40'-6" - 43'-0" | 14'-0" | 6'-3" - 7'-6" | | Z 3" x 2 1/16" x 1/4" @ 2.33 LB/FT |
| 43'-6" - 46'-0" | 15'-0" | 6'-9" - 8'-0" | | |
| 46'-6" - 49'-0" | 16'-0" | 7'-3" - 8'-6" | | |

| HORIZONTAL STIFFENER SPACING | | | | |
|------------------------------|-----|---------------|-----|---------------|
| HP | A | B | C | D |
| TWO STIFFENERS | | | | |
| 1'-6" | 12" | 3" | 8" | - |
| 2'-0" | 18" | 3" | 14" | - |
| 2'-6" | 18" | 6" | 14" | 4" |
| 3'-0", 3'-6" | 24" | 6", 9" | 20" | 4", 7" |
| 4'-0", 4'-6" | 30" | 9", 12" | 26" | 7", 10" |
| 5'-0", 5'-6", 6'-0" | 36" | 12", 15", 18" | 32" | 10", 13", 16" |
| THREE STIFFENERS | | | | |
| 6'-6" | 36" | 3" | 32" | - |
| 7'-0", 7'-6" | 36" | 6", 9" | 32" | 4", 7" |
| 8'-0", 8'-6" | 36" | 12", 15" | 32" | 10", 13" |
| 9'-0", 9'-6" | 36" | 18", 21" | 32" | 16", 19" |
| FOUR STIFFENERS | | | | |
| 10'-0", 10'-6" | 36" | 6", 9" | 32" | 4", 7" |
| 11'-0", 11'-6" | 36" | 12", 15" | 32" | 10", 13" |
| 12'-0", 12'-6" | 36" | 18", 21" | 32" | 16", 19" |
| FIVE STIFFENERS | | | | |
| 13'-0", 13'-6" | 36" | 6", 9" | 32" | 4", 7" |
| 14'-0", 14'-6" | 36" | 12", 15" | 32" | 10", 13" |
| 15'-0", 15'-6" | 36" | 18", 21" | 32" | 16", 19" |
| SIX STIFFENERS | | | | |
| 16'-0", 16'-6" | 36" | 6", 9" | 32" | 4", 7" |

NOTE:
AS PER BD-052E, THE MAX HEIGHT OF THE MAIN SIGN PANEL IS 16'-6" AND THE MAX HEIGHT OF THE SUPPLEMENTAL SIGN PANEL ABOVE IS 3'-0".



| STIFFENER | J | K | P (BOLT) |
|-----------|--------|------|--|
| 2 3/8" | 1/2" | 1/2" | 3/8" STAINLESS STEEL OR 3/8" ALUMINUM IN 1/16" DIA. HOLE |
| 3" | 1 3/8" | 1" | 1/2" STAINLESS STEEL OR 1/2" ALUMINUM IN 3/16" DIA. HOLE |
| 4" | 1 7/8" | 1" | 1/2" STAINLESS STEEL OR 1/2" ALUMINUM IN 3/16" DIA. HOLE |



- NOTES:
- AT THE CONTRACTOR'S OPTION, PANELS LARGER THAN STANDARD SIZE MAY BE USED TO MINIMIZE OR ELIMINATE JOINTS.
 - UNLESS OTHERWISE SHOWN, ALL HARDWARE SHALL BE ALUMINUM ALLOY 6061-T6, 6262-T9, 2024-T4 OR 7075-T6 ASTM F468M OR STAINLESS STEEL ASTM A193M-B8 & A194M-8.
 - ALL 2024-T4 HARDWARE SHALL BE COATED WITH TYPE 205 FINISH IN ACCORDANCE WITH §719-02 OF THE STANDARD SPECS.
 - COMPONENTS OF LOCK BOLTS MAY HAVE MODIFIED TEMPER IN COLD-FORMED ELEMENTS.
 - STIFFENERS FOR GROUND-MOUNTED SIGNS SHALL BE CONTINUOUS. (SPICES NOT ALLOWED.)
 - SIGNS OVER ONE STANDARD PANEL HEIGHT (12'-0" FOR ALUMINUM) MAY BE CONSTRUCTED AS TWO SEPARATE SIGNS OF APPROXIMATELY EQUAL HEIGHT WITH A HORIZONTAL CONSTRUCTION JOINT SIMILAR TO THE VERTICAL JOINTS DETAILED ON THIS SHEET. THE HORIZONTAL JOINT SHALL FALL BETWEEN LINES OF LEGEND, SPAN THE ENTIRE WIDTH OF THE PANELS, AND HAVE A BOLT SPACING OF 16" MAX C-C WITH A 1" EDGE DISTANCE THE VERTICAL PLATE LENGTHS SHOULD BE ADJUSTED, IF NEEDED.
 - SECONDARY PANELS AND EXIT NUMBER PLAQUES SHALL BE FABRICATED IN THE SAME MANNER AS THE MAIN PANEL.
 - SECONDARY PANELS (BELOW THE MAIN PANEL) SHALL BE ATTACHED EITHER AS SHOWN FOR THE EXIT NUMBER PLAQUE OR TO THE POSTS. WHEN ATTACHED TO THE POSTS, THE SECONDARY PANEL SHALL BE FASTENED ABOVE THE HINGE PLATES.
 - UNLESS OTHERWISE SHOWN, HOLES SHALL NOT BE MORE THAN 1/16" LARGER IN DIAMETER THAN THE NOMINAL DIAMETER OF THE FASTENER.
 - POST SPACING'S OF 7'-0" OR LESS SHALL BE USED ONLY WITH POSTS THAT ARE ACCEPTABLE AT THAT SPACING. SEE STANDARD SHEET FOR "MULTIPLE POST SIGN INSTALLATION USING TYPE B SIGN POSTS".
 - ALUMINUM Z BARS WEIGHING 1.00 LB/FT AND MEASURING 2 3/8" x 1 1/4" x 3/16" MAY BE PRE-PUNCHED WITH 3/16" DIAMETER HOLES AT 1" CENTERS ALONG THE ENTIRE LENGTH. THE 16 HOLES FOR THE 8 BOLTS IN THE Z-BAR SPLICES SHALL BE 1/16".
 - SEE STANDARD SHEET "POSITIONING OF TRAFFIC SIGNS" FOR HEIGHT AND LATERAL LOCATION OF SIGNS.
 - ALL SIGN PANEL TO Z-BAR CONNECTING BOLTS, AND ALUMINUM BATTEN PLATE BOLTS SHALL BE 1/4" HEX HEAD BOLT ALUMINUM 2024-T4 OR 1/4" BRAZIER HEAD LOCK BOLT, ALUMINUM 2024 WITH ALUMINUM 6061-T6 COLLAR F468M 3/16" DIAMETER HOLES. WITH PLASTIC OR NYLON WASHERS. FLAT OR BEVELED WASHERS SHALL BE USED, DOUBLE WASHERS WITH SLOTTED HOLES WITH ALUMINUM ALLOY LOCK OR STAR WASHERS.
 - OVERHEAD PANELS SHALL BE CONSTRUCTED AS SHOWN EXCEPT:
 - ALL LOCK BOLTS, BOLTS, NUTS & WASHERS SHALL BE STAINLESS STEEL. AFTER TIGHTENING, THREADS ON THREADED BOLTS MUST BE BURRED OR TACK WELDED USING TYPE E410 WELDING RODS TO PREVENT LOOSENING. ALUMINUM BATTEN PLATE BOLTS MAY BE ALUMINUM PER NOTE 13.
 - ALL HORIZONTAL STIFFENERS SHALL BE Z 2 3/8" x 1 1/4" x 3/16".
 - VERTICAL Z-BAR SUPPORTS, UNLESS OTHERWISE SHOWN ON THE CONTRACT DOCUMENTS, SHALL SUPPORT NOT MORE THAN 6'-0" OF SIGN WIDTH.



U.S. CUSTOMARY STANDARD SHEET

SIGN PANEL DETAILS FOR GUIDE, INFORMATION, AND OTHER SIGNS

APPROVED: NOVEMBER 4, 2013

RICHARD W. LEE, P.E.
DEPUTY CHIEF ENGINEER, DESIGN (ACTING)

ISSUED UNDER EB 12-040


645-09

ERRATA 2 EFF. 09/01/2018
ISSUED WITH EB 18-023


ERRATA 1 EFF. 01/09/2014
ISSUED WITH EB 13-042

FOUNDATION TABLE


| CODE NO. | MOMENT IN FT.-KIP AT TOP OF EARTH | J (2'-6" FOOTING WIDTH) | | | | K (3'-0" FOOTING WIDTH) | | | | L (3'-6" FOOTING WIDTH) | | | | M (4'-0" FOOTING WIDTH) | | | |
|----------|-----------------------------------|-------------------------|----------------------------|-----------------------------|------|-------------------------|----------------------------|-----------------------------|------|-------------------------|----------------------------|-----------------------------|------|-------------------------|----------------------------|-----------------------------|------|
| | | CU. YDS. | MINIMUM EMBEDMENT IN EARTH | VERTICAL REINFORCEMENT BARS | | CU. YDS. | MINIMUM EMBEDMENT IN EARTH | VERTICAL REINFORCEMENT BARS | | CU. YDS. | MINIMUM EMBEDMENT IN EARTH | VERTICAL REINFORCEMENT BARS | | CU. YDS. | MINIMUM EMBEDMENT IN EARTH | VERTICAL REINFORCEMENT BARS | |
| | | | | NUMBER | TYPE | | | NUMBER | TYPE | | | NUMBER | TYPE | | | NUMBER | TYPE |
| 1 | 40 AND UNDER | 1.1 | 6'-0" | 8 | #5 | 1.4 | 5'-3" | 8 | #5 | - | - | - | - | - | - | - | |
| 2 | 50 | 1.2 | 6'-6" | 8 | #5 | 1.6 | 5'-9" | 8 | #5 | 1.9 | 5'-4" | 8 | #5 | 2.4 | 5'-0" | 8 | #5 |
| 3 | 60 | 1.3 | 7'-0" | 14 | #5 | 1.8 | 6'-6" | 12 | #5 | 2.1 | 5'-10" | 12 | #5 | 2.6 | 5'-6" | 8 | #5 |
| 4 | 70 | 1.4 | 7'-6" | 14 | #5 | 1.8 | 6'-9" | 12 | #5 | 2.4 | 6'-6" | 12 | #5 | 2.8 | 6'-6" | 12 | #5 |
| 5 | 80 | 1.5 | 8'-0" | 14 | #5 | 1.9 | 7'-3" | 16 | #5 | 2.5 | 6'-9" | 12 | #5 | 3.1 | 6'-9" | 12 | #5 |
| 6 | 90 | 1.6 | 8'-6" | 14 | #6 | 2.1 | 7'-9" | 16 | #5 | 2.6 | 7'-3" | 16 | #5 | 3.2 | 6'-9" | 12 | #5 |
| 7 | 100 | 1.7 | 9'-0" | 14 | #6 | 2.2 | 8'-3" | 16 | #5 | 2.7 | 7'-6" | 16 | #5 | 3.3 | 7'-9" | 16 | #5 |
| 8 | 120 | 1.9 | 10'-0" | 14 | #6 | 2.5 | 9'-3" | 16 | #5 | 3.0 | 8'-3" | 16 | #5 | 3.7 | 7'-9" | 16 | #5 |
| 9 | 140 | 2.0 | 11'-0" | 14 | #7 | 2.7 | 10'-0" | 16 | #6 | 3.3 | 9'-3" | 16 | #5 | 4.0 | 8'-6" | 16 | #5 |
| 10 | 160 | - | - | - | - | 2.9 | 10'-9" | 16 | #6 | 3.5 | 9'-9" | 16 | #6 | 4.2 | 9'-0" | 16 | #5 |
| 11 | 180 | - | - | - | - | 3.1 | 11'-6" | 16 | #7 | 3.8 | 10'-6" | 16 | #6 | 4.6 | 9'-3" | 16 | #5 |
| 12 | 200 | - | - | - | - | 3.3 | 12'-3" | 16 | #7 | 4.1 | 11'-3" | 16 | #6 | 4.8 | 10'-3" | 16 | #6 |
| 13 | 220 | - | - | - | - | 3.4 | 12'-9" | 16 | #7 | 4.2 | 11'-9" | 16 | #7 | 5.1 | 10'-9" | 16 | #6 |
| 14 | 250 | - | - | - | - | 3.6 | 13'-9" | 16 | #8 | 4.6 | 12'-10" | 16 | #7 | 5.5 | 11'-9" | 16 | #7 |
| 15 | 275 | - | - | - | - | 3.9 | 14'-9" | 16 | #8 | 4.9 | 13'-6" | 16 | #8 | 5.9 | 12'-6" | 16 | #7 |
| 16 | 300 | - | - | - | - | - | - | - | - | - | - | - | - | 6.1 | 13'-0" | 16 | #8 |
| 17 | 350 | - | - | - | - | - | - | - | - | - | - | - | - | 6.7 | 14'-4" | 16 | #8 |
| 18 | 400 | - | - | - | - | - | - | - | - | - | - | - | - | 7.2 | 15'-6" | 16 | #10 |
| 19 | 450 | - | - | - | - | - | - | - | - | - | - | - | - | 7.8 | 16'-9" | 19 | #10 |
| 20 | 500 | - | - | - | - | - | - | - | - | - | - | - | - | 8.4 | 18'-0" | 21 | #10 |




TOP VIEW SQUARE FOOTING




TOP VIEW CIRCULAR FOOTING




ANCHOR BOLT PROJECTION DETAIL




NOTE: SHOWN WITHOUT MESH FOR CLARITY.




ELEVATION




ANCHOR BOLT PLATE DETAIL




FOOTINGS IN EMBANKMENTS



FOOTINGS IN SIDEWALKS



AUGERED OR DUG FOOTING



EXCAVATED FOOTING WITH SELECT GRANULAR BACKFILL

METHODS FOR PLACING FOOTINGS

GENERAL NOTES:

- FOOTING CAPACITY IN FOOT-KIPS WILL BE SPECIFIED IN THE CONTRACT DOCUMENTS. FOOTING WIDTH AND EMBEDMENT SHALL BE DETERMINED FROM THE TABLE BY THE CONTRACTOR AND APPROVED BY THE ENGINEER BEFORE INSTALLATION.
- FOOTINGS FOR FLASHING BEACON SIGN ASSEMBLIES SHALL BE J-2 FROM THE TABLE AND MAY BE EITHER CIRCULAR OR SQUARE.
- FOOTING EMBEDMENT IN EMBANKMENTS SHALL BE MEASURED FROM THE NORMAL SLOPE (ORIGINAL GRADE) AS SHOWN IN FOOTING IN EMBANKMENT DETAIL.
- FOOTINGS FOR SPAN WIRE POLES MAY BE CIRCULAR OR SQUARE.
- FOOTINGS FOR MAST ARM POLES WITH MAST ARMS 20' OR LESS IN LENGTH MAY BE CIRCULAR OR SQUARE. FOOTINGS FOR POLES WITH ARMS GREATER THAN 20' IN LENGTH SHALL BE SQUARE.
- ADJUST THE FINISHED GROUND SURFACE IN THE VICINITY OF THE FOOTING AS NECESSARY SO THAT NO FILL SPILLS ON THE TOP OF THE FOOTING. FOR FOOTINGS IN EMBANKMENTS, THE MAXIMUM DISTANCE FROM THE TOP OF FOOTING TO THE FINISHED GROUND AT THE CENTERLINE SHALL NOT EXCEED 8".
- PAYMENT QUANTITY FOR POLE EXCAVATION AND CONCRETE FOUNDATION IS THE CUBIC YARDS CONCRETE SPECIFIED IN THE TABLE. NO ADJUSTMENTS WILL BE MADE WHEN THE CONTRACTOR CHOOSES TO INSTALL A SQUARE FOOTING. WHEN A SQUARE FOOTING IS REQUIRED, THE QUANTITY IN THE TABLE WILL BE MULTIPLIED BY 1.3.
- WHEN A FOOTING IS USED WITH A BREAKAWAY TYPE OF POLE BASE, THE MAXIMUM DISTANCE FROM THE SURROUNDING SURFACE TO THE TOP OF ANCHOR BOLTS SHALL BE 4".
- THE GEOTECHNICAL ENGINEERING BUREAU AND THE OFFICE OF STRUCTURES SHOULD BE CONSULTED UNDER THE FOLLOWING CIRCUMSTANCES:
 - FOOTING IS PLACED IN SOFT CLAY OR ORGANIC DEPOSITS.
 - MOMENT AT THE TOP OF EARTH IS GREATER THAN 500 FOOT - KIPS.
 - WHEN ROCK IS ENCOUNTERED.
- BOLT COVERS SHALL BE USED ONLY WHEN SPECIFIED IN THE CONTRACT DOCUMENTS.
- ANCHOR BOLTS SHALL BE HOT-DIPPED GALVANIZED A MINIMUM OF THE TOP 12 INCHES AND THREADED A MINIMUM OF 8 INCHES









U.S. CUSTOMARY STANDARD SHEET

TRAFFIC SIGNAL POLE FOUNDATIONS

APPROVED JULY 18, 2017
/S/ RICHARD D. WILDER, P.E.
DEPUTY CHIEF ENGINEER
(DESIGN)

ISSUED UNDER EB 17-027

680-01




PAVEMENT MARKING LINE NOTES:

L1. EDGE LINES ON ALL RURAL, HIGH SPEED HIGHWAY SEGMENTS WITH POSTED SPEEDS OF 45 MPH OR MORE SHALL BE 6". ALSO, NORMAL PAVEMENT MARKING LINES SHALL BE 6" ON FREEWAYS AND EXPRESSWAYS AND ON RAMP TO AND FROM FREEWAYS AND EXPRESSWAYS, AND WHERE SPECIFIED IN THE CONTRACT DOCUMENTS. AT ALL OTHER LOCATIONS NORMAL PAVEMENT MARKING LINES SHALL BE 4". WIDE PAVEMENT MARKING LINES SHALL BE TWICE AS WIDE AS NORMAL LINES ON THE SAME HIGHWAY. CHANNELIZING LINES ARE THE SAME WIDTH AS WIDE LINES.

L2. PAVEMENT MARKING LINE CODES MAY BE SHOWN ON THE PLANS.
DESIGNATIONS:



"W"=WHITE "Y"=YELLOW "WIDE"=WIDE



| POSTED SPEED ≥ 45 MPH | | | | | POSTED SPEED < 45 MPH | | | | |
|-----------------------|----|-----|----|--------|-----------------------|----|-----|----|--------|
| TYPE | W | θ° | S | L | TYPE | W | θ° | S | L |
| A | 1' | 30° | 3' | 8' | A | 8" | 30° | 2' | 5'-4" |
| B | 1' | 35° | 3' | 7' | B | 1' | 35° | 3' | 7' |
| C | 2' | 45° | 6' | 11'-4" | C | 2' | 45° | 6' | 11'-4" |

CROSS HATCH LINE DIMENSIONS

NOTE: TYPE SHALL BE AS PER PLAN. DEFAULT VALUE IS TYPE C UNLESS OTHERWISE SHOWN.



GENERAL PAVEMENT MARKING NOTES:

- ALL PAVEMENT MARKINGS SHALL BE PLACED IN ACCORDANCE WITH THE MUTCD AND NYS SUPPLEMENT.
- EDGE LINES SHALL BE YELLOW ON THE LEFT SIDE AND WHITE ON THE RIGHT SIDE IN THE DIRECTION OF TRAVEL UNLESS OTHERWISE SHOWN ON THE PLANS. IF THE CURB OFFSET IS LESS THAN 2'-0", NO EDGE LINE SHALL BE APPLIED ADJACENT TO CURBS UNLESS OTHERWISE SHOWN ON THE PLANS. EDGE LINES SHALL BE PROVIDED AT THE CURB ADJACENT TO RAISED ISLANDS (SEE DETAIL).
- WHERE MARKINGS NORMALLY FOLLOW A PAVEMENT JOINT, SINGLE LINE MARKINGS SHALL BE PLACED ALONG ONE SIDE OF THE JOINT. DOUBLE LINE MARKINGS SHALL STRADDLE THE JOINT. LANE LINES ON ROADWAYS WHICH ARE MORE THAN TWO LANES WIDE AND HAVE LONGITUDINAL JOINTS BETWEEN ADJACENT LANES, SHALL BE PLACED ON THE SIDE OF THE JOINT WHICH WILL OBTAIN OPTIMUM LANE WIDTHS.

AT THE JUNCTION OF SINGLE AND DOUBLE LINE MARKINGS WHICH FOLLOW A PAVEMENT JOINT, THE SINGLE LINE SHALL BE AN EXTENSION OF EITHER OF THE DOUBLE LINES AND NOT THE SPACE BETWEEN THEM. AT THE JUNCTION OF SINGLE AND DOUBLE LINE MARKINGS WHICH DO NOT FOLLOW A PAVEMENT JOINT, THE SINGLE LINE MAY BE ALIGNED WITH THE CENTER OF THE DOUBLE LINE MARKING OR WITH EITHER LINE OF THE DOUBLE LINE.
- ALL DIMENSIONS AND THE PLACEMENT OF ARROWS, SYMBOLS, AND TEXT SHOWN ARE TYPICAL AND SHALL APPLY UNLESS OTHERWISE INDICATED IN THE CONTRACT DOCUMENTS.
- THE REGIONAL TRAFFIC ENGINEER WILL REVIEW AND APPROVE ANY CHANGES TO THE PAVEMENT MARKING PLANS PRIOR TO FINAL INSTALLATION. CHANGES SHALL BE SUBMITTED TWO WEEKS PRIOR TO INSTALLATION.






U.S. CUSTOMARY STANDARD SHEET

PAVEMENT_MARKING_DETAILS
(SHEET 1 OF 9)

APPROVED AUGUST 21, 2018
/S/ ROBERT LIMOGES P.E.
DIRECTOR, OFFICE OF TRAFFIC
SAFETY AND MOBILITY

ISSUED UNDER EI 18-008

685-01




- NOTES:
1. ALL CROSSWALK MARKINGS SHALL BE WHITE.
 2. TYPE "L" AND TYPE "LS" CROSSWALKS SHALL HAVE THE LONGITUDINAL LINES PARALLEL TO THE LANE LINES.

- NOTES:
1. AT SIGNALIZED INTERSECTIONS, AT LEAST ONE SIGNAL HEAD FOR THE THROUGH MOVEMENT AND AT LEAST ONE FOR EXCLUSIVE RIGHT OR LEFT TURN-LANES (IF PROVIDED) ARE REQUIRED TO BE AT LEAST 40'-0" BEYOND THE STOP LINE FOR THE LANES THEY CONTROL. THIS MAY PLACE THE STOP LINE MORE THAN 4'-0" UPSTREAM FROM THE CROSSWALK.
 2. DISCONTINUE BIKE LANE MARKINGS AT LEAST 100'-0" BEFORE INTERSECTION IF NO MARKED BIKE LANE IS PRESENT DOWNSTREAM.

1. SEE STANDARD SHEET 685-01 (SHEET 1 OF 9) FOR LINE LAYOUT AND DIMENSIONS (EXCEPT AS NOTED).
2. REFER TO STANDARD SHEET 685-01 (SHEET 1 OF 9) FOR GENERAL NOTES.

| | |
|--|---|
| | STATE OF NEW YORK DEPARTMENT OF TRANSPORTATION |
| | U.S. CUSTOMARY STANDARD SHEET |
| PAVEMENT MARKING DETAILS (SHEET 2 OF 9) | |
| APPROVED SEPTEMBER 24, 2012 | ISSUED UNDER EB 12-036 |
| /S/ TODD B. WESTHUIS, P.E. ACTING DIRECTOR, OFFICE OF TRAFFIC SAFETY AND MOBILITY | |
| 685-01 | |


EFFECTIVE DATE: 05/02/2013




LANE DROP AT A SINGLE LANE EXIT RAMP

LANE DROP AT A MULTI-LANE EXIT RAMP WITH OPTION LANE


TWO-LANE DROP AT AN EXIT RAMP

| | |
|---|---|
|  | STATE OF NEW YORK DEPARTMENT OF TRANSPORTATION |
| | U.S. CUSTOMARY STANDARD SHEET |
| PAVEMENT MARKING DETAILS (SHEET 3 OF 9) | |
| APPROVED SEPTEMBER 24, 2012 | ISSUED UNDER EB 12-036 |
| /S/ TODD B. WESTHUIS, P.E. ACTING DIRECTOR, OFFICE OF TRAFFIC SAFETY AND MOBILITY | 685-01 |

EFFECTIVE DATE: 05/02/2013




ROUTE SPLIT WITH DEDICATED LANES







AUXILIARY LANE AT CLOSELY SPACED RAMPS

NOTE: USE THIS DETAIL WHERE DISTANCE FROM THEORETICAL GORE OF ENTRANCE RAMP TO THEORETICAL GORE OF EXIT RAMP IS LESS THAN OR EQUAL TO 3/4 MILE.

| | | |
|---|---|--|
|  | STATE OF NEW YORK DEPARTMENT OF TRANSPORTATION | |
| | U.S. CUSTOMARY STANDARD SHEET | |
| PAVEMENT MARKING DETAILS (SHEET 4 OF 9) | | |
| APPROVED SEPTEMBER 24, 2012 | ISSUED UNDER EB 12-036 | |
| /S/ TODD B. WESTHUIS, P.E. ACTING DIRECTOR, OFFICE OF TRAFFIC SAFETY AND MOBILITY | 685-01 | |

EFFECTIVE DATE: 05/02/2013



1. SEE STANDARD SHEET TITLED "PAVEMENT MARKING DETAILS - SHEET 1 OF 9" FOR LINE LAYOUT AND DIMENSIONS. (EXCEPT AS NOTED)
2. REFER TO STANDARD SHEET TITLED "PAVEMENT MARKING DETAILS - SHEET 1 OF 9" FOR GENERAL NOTES.



STATE OF NEW YORK
DEPARTMENT OF TRANSPORTATION

U.S. CUSTOMARY STANDARD SHEET

PAVEMENT MARKING DETAILS
(SHEET 5 OF 9)

APPROVED SEPTEMBER 24, 2012


ISSUED UNDER EB 12-036

/S/ TODD B. WESTHUIS, P.E.


ACTING DIRECTOR, OFFICE OF
TRAFFIC SAFETY AND MOBILITY

685-01


EFFECTIVE DATE: 05/02/2013



AUXILIARY LANE BETWEEN INTERSECTIONS
 LESS THAN OR EQUAL TO 1 MILE APART




AUXILIARY LANE BETWEEN INTERSECTIONS
 GREATER THAN 1 MILE APART



LANE DROP AT INTERSECTION

SYMBOL SPACING NOTES:


- S1. SPACING BETWEEN ARROWS AND "ONLY" (X) IS 32' MIN. AND 80' MAX. LOWER SPEED ROADS SHOULD HAVE CLOSER SPACING THAN HIGHER SPEED ROADS.
- S2. IF $L < 75'$ OR $L > 400'$, REFER TO CONTRACT DOCUMENTS OR REGIONAL TRAFFIC SAFETY AND MOBILITY GROUP FOR GUIDANCE ON SPACING OF ARROWS AND "ONLY".
- S3. ON AN UNCONTROLLED APPROACH (NO STOP SIGN, YIELD SIGN, OR TRAFFIC SIGNAL) OMIT STOP LINE.
- S4. IF INTERSECTION LANE CONTROL SIGNS (EG. R3-5) ARE NOT PROVIDED FOR THE LANE, THE "ONLY" MARKINGS SHALL BE DELETED.
- S5. ARROWS AND "ONLY" TO BE CENTERED IN THE LANE.




LANE USE ARROW PLACEMENT
 $L \leq 200'$

LANE USE ARROW PLACEMENT
 $200' < L \leq 400'$

| | | |
|---|---|----------------------------------|
| | STATE OF NEW YORK DEPARTMENT OF TRANSPORTATION | |
| | U.S. CUSTOMARY STANDARD SHEET | |
| PAVEMENT MARKING DETAILS (SHEET 6 OF 9) | | |
| ERRATA 1 EFF. 01/09/2014 ISSUED WITH EB 13-042 EFFECTIVE DATE: 05/02/2013 | APPROVED: OCTOBER 23, 2013 /S/ TODD B. WESTHUIS, P.E. DEPUTY CHIEF ENGINEER: TRAFFIC, SAFETY AND MOBILITY (ACTING) | ISSUED UNDER EB 12-036 685-01 |




RAILROAD GRADE CROSSING MARKINGS AND LAYOUT PLAN



* PARKING LANE WIDTHS SHOWN IN CONTRACT DOCUMENTS.
PARKING SPACE LENGTHS AS SHOWN IN THIS DETAIL OR AS SHOWN IN CONTRACT DOCUMENTS.


TYPICAL PARKING LANE MARKINGS



(PAID AS LINEAR FEET)
(TOTAL PAYMENT IS 43.0')

(PAID AS ONE SYMBOL)

RAILROAD GRADE CROSSING




ALTERNATE PARKING LANE MARKINGS
(NO EDGE LINE)
(NOT TO SCALE)


RAILROAD GRADE CROSSING NOTES:

- R1. WHERE THERE IS NO RAILROAD CROSSING GATE, THE CLEARANCE LINE SHOULD BE PERPENDICULAR TO THE ROADWAY, AND 15'-0" FROM THE NEAREST RAIL AT ITS CLOSEST POINT. WHERE THERE IS A GATE, THE CLEARANCE LINE SHOULD BE PARALLEL TO THE GATE IN ITS LOWERED POSITION, AND EITHER 15'-0" FROM THE NEAREST RAIL OR 8'-0" FROM THE GATE, WHICHEVER PLACES THE LINE FURTHER FROM THE CROSSING.
- R2. ON A MULTI-LANE APPROACH, THE CLEARANCE LINE AND CROSSBARS SHALL EXTEND ACROSS ALL LANES, AND A "RXR" SYMBOL SHALL BE PLACED IN EACH LANE.
- R3. REFER TO STANDARD SHEET TITLED "PAVEMENT MARKING DETAILS - SHEET 1 OF 9" FOR GENERAL NOTES.
- R4. IF A W3-1 OR W3-2 SIGN IS NOT REQUIRED IN ADVANCE OF THE GRADE CROSSING, THE W10-1 SHALL BE LOCATED IN ACCORDANCE WITH TABLE NY2C-4. IF A W3-1 OR W3-2 SIGN IS REQUIRED IN ADVANCE OF A GRADE CROSSING, IT SHALL BE LOCATED IN ACCORDANCE WITH TABLE NY2C-4 AND THE W10-1 SIGN SHALL BE LOCATED APPROXIMATELY 200'-0" IN ADVANCE OF THE W3-1 OR W3-2 SIGN.
- R5. A PORTION OF THE "RXR" MARKING MUST BE OPPOSITE THE W10-1 SIGN. 24" WHITE CROSSBARS ARE PLACED IN RELATION TO "RXR" MARKING. THE DISTANCE TO CLEARANCE LINE WILL VARY.
- R6. NORMAL SOLID DOUBLE YELLOW LINE TO BEGIN A MINIMUM OF 10'-0" UPSTREAM OF FIRST 24" WHITE CROSS BAR.


| | |
|---|---|
|  Department of Transportation | |
| U.S. CUSTOMARY STANDARD SHEET | |
| PAVEMENT MARKING DETAILS (SHEET 7 OF 9) | |
| ERRATA 1 ISSUED WITH EB 17-041 EFFECTIVE DATE: 05/02/2013 | APPROVED SEPTEMBER 24, 2012 /S/ TODD B. WESTHUIS, P.E. ACTING DIRECTOR, OFFICE OF TRAFFIC SAFETY AND MOBILITY |
| | ISSUED UNDER EB 12-036 685-01 |




TURNING ARROW
(PAID AS ONE SYMBOL)




LANE REDUCTION ARROW
(PAID AS ONE SYMBOL)




"YIELD" LETTERS
SEE NOTE
(PAID AS FIVE LETTERS)




HANDICAPPED PARKING SYMBOL
(PAID AS ONE SYMBOL)




RAMP ARROW
(PAID BY LINEAR FEET)
(TOTAL PAYMENT IS 73')




TURNING/STRAIGHT ARROW FOR SHARED LANE
(PAID AS ONE SYMBOL)




DIVERGE ARROW
(PAID AS ONE SYMBOL)




"STOP" LETTERS
SEE NOTE
(PAID AS FOUR LETTERS)




PREFERENTIAL LANE SYMBOL
(PAID BY LINEAR FEET)
(TOTAL PAYMENT IS 35')



STRAIGHT ARROW
(PAID AS ONE SYMBOL)



"SCHOOL" LETTERS
SEE NOTE
(PAID AS SIX LETTERS)




"ONLY" LETTERS
SEE NOTE
(PAID AS FOUR LETTERS)


NOTES:

UNLESS OTHERWISE SHOWN:
LETTER HEIGHT = 8'-4"
LETTER WIDTH = 1'-4"
SPACING = 8"
(USE EQUAL SPACING BETWEEN LETTERS AND CENTER ENTIRE SYMBOL IN LANE)


| | |
|---|----------------------------|
|  Department of Transportation | |
| U.S. CUSTOMARY STANDARD SHEET | |
| PAVEMENT MARKING DETAILS (SHEET 8 OF 9) | |
| APPROVED SEPTEMBER 24, 2012 | ISSUED UNDER EB 12-036 |
| /S/ TODD B. WESTHUIS, P.E. ACTING DIRECTOR, OFFICE OF TRAFFIC SAFETY AND MOBILITY | 685-01 |
| ERRATA 1 ISSUED WITH EB 17-041 | EFFECTIVE DATE: 05/02/2013 |




SHARED LANE USE MARKING DETAIL
(CHEVRON PAID BY LINEAR FEET)
(BICYCLE PAID AS ONE SYMBOL)




BICYCLE ARROW
(PAID AS ONE SYMBOL)



BICYCLE DETECTOR MARKER
(PAID AS ONE SYMBOL)




BICYCLE SYMBOL
(PAID AS ONE SYMBOL)



BICYCLE LANE MARKING NOTES:

- B1. CENTER SYMBOL IN BICYCLE LANE OR SHOULDER.
- B2. PLACE BICYCLE LANE ARROW AND SYMBOL DOWNSTREAM OF MAJOR OR SIGNALIZED INTERSECTIONS.
 - PLACE BICYCLE SYMBOL AT 1320'-0" SPACING ALONG BICYCLE LANE OR AS INDICATED IN THE CONTRACT DOCUMENTS.
 - PLACE BICYCLE LANE ARROW AND SYMBOL 200'-0" UPSTREAM OF MAJOR OR SIGNALIZED INTERSECTIONS.
- B3. MARKINGS AS PER THE DIRECTIONS OF THE REGIONAL OFFICE OF TRAFFIC SAFETY AND MOBILITY GROUP OR AS PER PLAN. SIGNS SHALL BE USED WITH THE BICYCLE LANE.

| | | | |
|--|---|-------------------------------------|--------|
|  NEW YORK STATE OF OPPORTUNITY. | | Department of Transportation | |
| U.S. CUSTOMARY STANDARD SHEET | | | |
| PAVEMENT MARKING DETAILS (SHEET 9 OF 9) | | | |
| ERRATA 1 ISSUED WITH EB 17-041 EFFECTIVE DATE: 05/02/2013 | APPROVED SEPTEMBER 24, 2012 /S/ TODD B. WESTHUIS, P.E. ACTING DIRECTOR, OFFICE OF TRAFFIC SAFETY AND MOBILITY | ISSUED UNDER EB 12-036 | 685-01 |