



Tel: 865-379-7777

1170 Topside Road
Louisville, TN 37777

Quality Steel Trusses

Pre-welded purlin cups offer stability and a reduction in construction time. With pre-drilled holes for wood purlins: there is no quicker, cost efficient method.

Additional stability is offered through our stabilizer bar. With pre-drilled holes and the bolts provided with each order, additional stability is achieved quickly.

Additional overhang with purlin cup is standard. Measurements for building size from outside of post to outside of post. Available without overhang per request.

For stability and ease of install standard trusses and shed trusses offer a "bolt to the post" base plate. Standard design is for 6x6 inch post. Will build to requests.

The bolt together design of our steel trusses offers the versatility, durability and ease of install our customers have come to expect. Pre-drilled with bolts provided.





STEEL TRUSSES

With our Quality Crafted Steel trusses, we put our customers in control.

If you can imagine it...
you can build it!



Tel: 865-379-7777



With trusses spaced at apart 10' apart as a standard. you will reduce the number of trusses, materials and labor cost with our quality steel truss system.

With pre-welded, pre-drilled purlin cups, install is quicker and easier for even the novice craftsman.

All American Materials

Made in the USA

Bolt Together Truss Designs

Pre-Welded purlin Cups

Pre-Drilled Bolt Holes


10' to 80' Wide Truss Expansions

Shed Trusses Up to 30'

Unlimited Building Options



Arenas
Work Shops
Garages
Hay Storage
Stables



Home Kits
Greenhouses
Meeting Areas
Patio Covers
RV/Boat Cover



Customized orders...
If you can imagine it, we can build it.



www.MetalRoofingWholesalers.com

