

Keith Walker 12-12-15

PACE AMERICAN

53BPTEA23HF018022

DEALER	<u>D Manufacturing</u>	Base	<u>[REDACTED]</u>	Cost	<u>[REDACTED]</u>
Model	<u>OB85x16TE2</u>	Clearance lights	<u>Rounded RV Style</u>		
	<u>Outback Cargo Trailer</u>	Tail-lights	<u>Clear LED</u>		
Axle	<u>Tandem/Drop/Electric</u>	Side Door	<u>36" X 74" Built Door w/ Barlock - Curbside</u>		
			<u>Install 18" Back.</u>		
		Recessed Step	<u>Yes</u>		
Type	<u>Spring 3500#</u>	Door Holdback	<u>Steel Style</u>		
		Rear Door	<u>RAMP REAR DOOR 1" x 2" Tube</u>		
		Beavertail	<u>32"</u>		
		Ramp Extension	<u>16" DRYMAX</u>		
Tires	<u>ST 205/75R15 5 Lug Radials</u>	Dome Light	<u>(2) Centered in Ceiling.</u>		
Rim	<u>SILVER</u>	Switch	<u>(1) By Sidedoor.</u>		
Frame	<u>2" X 6" Tube 24" centers</u>	Roof	<u>Galvalume 16" centers</u>		
Coupler	<u>2-5/16"</u>	Fenders	<u>Round Aluminum Fenders</u>		
Hitch	<u>STD</u>	Reflectors	<u>Acrylic reflectors</u>		
Jack	<u>STD</u>	Sidewall Vents	<u>(2) Installed in Standard Locations</u>		
Sidewall	<u>90-3/4" 24" centers 6" Drop Wall</u>	D-Rings	<u>(4) 5K with Welded Backing Plates.</u>		
Sidewall	<u>6" Added Height</u>		<u>2- 12" In From Rear, 2-15' In from Rear.</u>		
	<u>Z Posts</u>		<u>Place D-Rings at 66" Apart</u>		
		DUE DATE	<u>2/12/2016</u>		
Floor	<u>3/4" DRYMAX</u>				
Walls	<u>3/8" DRYMAX</u>				
Exterior	<u>WHITE</u>				
Stoneguard	<u>Yes 025 24" Embossed</u>	DECALS	<u>STANDARD</u>		

#5895
SD/Ramp

12/12/2015