

Our Ref: 0075-MITREHOUSE-CWSTR-LW-PB

22nd September 2014

Paul Brown
Mitre House Management Ltd
7 Mitre House,
124 Kings Road,
Chelsea
London
SW3 4TP

Dear Paul

RE: COLD WATER STORAGE TANK REMOVAL AND REPLACEMENT

SITE: 124 KINGS ROAD, CHELSEA, LONDON SW3 4TP

Further to my site visit, I am pleased to provide the following quotation to carry out the removal of the existing CWST's and replace with a new GRP Hot Press Moulded Pre-Insulated Tank.

Our prices are based on normal working hours.

Please see following quotation.

We trust that the information presented meets with your approval and that we have understood your current requirements. If you have any queries or require any further information please do not hesitate to contact me on my mobile 07944 262970

Yours sincerely



Louis Wyborn
Risk Assessor/Technical Sales
Houseman Water Hygiene Specialists Ltd

QUOTATION FOR A CWST REMOVAL AND REPLACEMENT

<p>QUOTE NO: Q0075- MITREHOUSE- CWSTR-LW-PB</p>	<p>MR PAUL BROWN MITRE HOUSE MANAGEMENT LTD 7 MITRE HOUSE, 124 KINGS ROAD, CHELSEA LONDON SW3 4TP</p>	<p>DELIVERY ADDRESS: MITRE HOUSE MANAGEMENT LTD 7 MITRE HOUSE, 124 KINGS ROAD, CHELSEA LONDON SW3 4TP</p>
<p>DATE: 22/09/2014</p>		<p>SITE CONTACT PAUL BROWN - 07983333543</p>
<ul style="list-style-type: none"> • Isolate, drain down and cut out existing 3no. Iron CWST plus remove existing redundant F&E tank and remove from site via licensed waste operator. • Prepare base as required. • Supply, deliver and erect 1no. New GRP pre-insulated, sectional, hand laid-up, internally flanged CWST (WRAS approved). Dimensions of 1.5m x 1m x 1m high • Modify pipework where required. • Connect new CWST to existing pipework via new valves. • Clean and disinfect in accordance to BS8558. • Fill, test and bring on-line. • Insulate new and disturbed pipework with foil-faced insulation material. • Clear site of all arising's and handover installation. <p align="right">Total £6509 + Vat</p>		

