

Town of Baldwin, Maine
CULVERT INSTALLATION BID DETAILS
SENATOR BLACK ROAD & MURCH ROAD

- Senator Black Road culvert:
 - one – 60” x 40’ aluminized culvert on Marstons’ brook.
 - one – 24” x 40’ ABS culvert approximately 100’ – 150’ up from Marston’s Brook
- Murch Road culvert:
 - one – 60” x 40’ aluminized culvert on Quaker Brook
- Senator Black Road culvert must be completed by September 7th, 2018
- Murch Road culvert must be completed by October 26th, 2018.
- Both culverts installed the full 40’ with gravel to rip-rap. Possible rocks to be used instead of guard rails.
- Town of Baldwin Public Works will haul off the old culverts.
- All culverts are supplied by the Town of Baldwin. Other materials to be supplied by the contractor.
- Contractor must contact dig safe. There is possible underground telephone on Murch Road.
- Culverts to be compacted in 10” to 12” lifts,
- 6” to 12” rip-rap is required to be installed on either ends of the culverts.
- Contractor to leave crushed gravel on the surface on Senator Black Road.
- Murch Road culvert needs to be patched back in with hot top.
- THE BALDWIN MUNICIPAL OFFICERS RESERVE THE RIGHT TO ACCEPT OR REJECT ANY AND ALL OFFERS SUBMITTED WHICH ARE NOT IN THE TOWN'S BEST INTEREST AS DETERMINED BY THE MUNICIPAL OFFICERS
- The Contractor shall have and maintain liability insurance that is in force until the work is completed and accepted by the Municipality. The Contractor shall furnish to the Municipality, a certificate of insurance, within two weeks of notice to the Contractor of the acceptance of its offer. The failure to provide this certificate will constitute a breach of the Contract and may at the discretion of the Municipality; result in termination of the Contract.