

A NEW BUS MAINTENANCE FACILITY FOR
USD #286 – Chautauqua County Community Schools
Sedan, Kansas

ADDENDUM #2

ISSUED: 6 February 2019

The following items modify and supersede the Contract Documents and are hereby made a part of the Bid Documents. This addendum shall be acknowledged on the Bid Form.

1. Architectural Drawings:

- A. At all wall locations shown to have prefinished metal liner panels, apply 1x4 wood furring strips horizontally at 24" o.c. over 5/8" type "x" gypsum board. Gypsum board behind metal liner panels shall be fire taped. Paint all exposed wood furring strip edges that are visible around openings or, at contractor's option, trim with prefinished metal trim.
- B. At exterior wall locations, install a minimum R-25 batt insulation with a 6 mill poly vapor barrier under the gypsum board. At interior walls, install 3-1/2" thick sound batt insulation and at the mezzanine floor framing, install R-25 batt insulation between the floor joists. At the attic, install 12" of blown cellulose insulation as shown on the drawings.

End of Addendum Number Two

