

| Pipe Details & Test Specifications | 100% SMYS | Design MAOP | 110% Min Test PSIG | 125% MAOP Max Test PSIG | % SMYS |
|---------------------------------------|-----------|-------------|-----------------------|-------------------------------|--------|
| 12.75 x 0.219 x Grade X-65 | 2,233 | 1,000 | 1,100 | 1,250 | 55.98% |

The hydrostatic test includes filling the test sections with water, performing the strength test, investigating for leaks, making necessary repairs, displacing and disposing of test water, drying the pipeline, performing tie-ins and recording all test data.

The pipeline will be hydrostatically tested for a minimum of eight (8) hours at the prescribed test pressure. Four (4) hours will be at the higher test pressure, which is 125% of the MAOP of the pipeline, and the other four (4) hours will be at a test pressure equal to 110% of the MAOP (see chart below). The test pressure will not be allowed to exceed the Maximum Pressure at the lowest elevation point in the test segment for each line size. It is the Contractor's responsibility to check for any significant elevation changes that will affect the number and locations of test segments to insure that the minimum test pressures are met while not exceeding the Maximum Pressure.

The test pressure will be reached by increasing the line pressure in stages, allowing time for stabilization between pressure increases. For pipe 8" and larger, once the pressure has reached 80% of SMYS at the lowest elevation point in the test segment, the pressure shall be increased at no more than 10 psig per minute at a uniform rate. The test shall not begin until the temperatures recorded at each end of the test segment indicate stabilization from fill water temperatures. Once test pressure is achieved and the test period has started, if additional pumping is required to stay above the minimum test pressure, the test period must restart.



