



TOWN OF STRATTON
MOUNTAIN ROAD
11-21-2019

AMENDMENT AND ADDENDUM TO
BOX CULVERT PROJECT

Sheet 2 has been amended showing a more limited extent of the structural backfill around the culvert. The contractor shall provide a 3' thick layer of structural backfill around the sides and top of the culvert as shown in the cross section.

- The estimated amount of structural backfill gravel required for this project is 1,500 cu. yds.
- The estimated amount of subbase gravel that will be required beneath the pavement is 500 cu. yds.
- The estimated amount of bedding stone for the culvert is 100 cu. yds.

It is estimated that no additional gravel fill material will be required to complete the project. However, please provide a per cu. yd. cost for common gravel fill in the event that additional material is required beyond the volumes identified above.

Project Schedule: Due to issues with school buses and seasonal traffic, the project is to be completed between July 4, 2020 and September 1, 2020.