

Pool Construction Process

Below is a brief timeline of your pool construction process

Design



Contract & Color Selections: This is the time where you will meet with Myrick Pools personnel to pick your pool tile, interior and materials and finalize your pool details as well as sign your construction contract.



Permits & HOA Approvals: This process can take up to 30 days depending on your HOA meeting dates and the building department.



Irrigation Cap: This is the time to have your irrigation system capped off in the area of where your pool is to be constructed. This will prevent any torn or broken irrigation lines in your irrigation system and prepare for the construction process.

SOD Removal: Sod is stripped in the area where your pool will be constructed



Pool Layout: This is the first step in the actual construction process. The excavation crew will set the form boards and your new pool will begin to take shape. Strict attention is given to critical dimension as our crew carves out the custom shape. Construction is typically 8 to 10 weeks from excavation.

Excavation: After the sod has been stripped and the forms laid out the excavation of the pool can begin. Sometimes there is dirt leftover on the job that will be removed at a later date



Steel: Our steel reinforcement schedule exceeds ANSI standards for expansive soil conditions and is the basis for our unsurpassed structural warranty.



Gunite: Pneumatically applied under pressure to our specifications. This process creates the superior strength of a Myrick Pool. The crew members are masters at sculpting the gunite structure of your Myrick Pool.



Deck Grade: The excavation experts will come back and grade out the dirt to make way for the plumbing.

Plumbing: The hydraulic system for each and every Myrick Pool is designed for safety, energy efficiency and water purity. State of the art equipment ensures minimal effort to maintain you Masterpiece Pool.



Tile & Coping: Your selection of materials coupled with our craftsmanship set the tone and style for the project. Together we are truly creating art.



Equipment Set: Your pool equipment will be installed by a skilled professional. All plumbing to your pool will be completed at this time. (If this is new home construction then the pool equipment will be installed after the home has been stucco and painted)



Electrical: Licensed electricians will schedule an appointment to gain access to your main electrical panel and may need to access your attic. Electrical service re-routes and panel upgrades are determined by the city and electrical codes. (This takes place after pool equipment installation)



Termite Pre-Treat: Your deck will receive a termite pre-treat provided by a licensed termite company prior to the installation of the footer and/or deck pour.

INSPECTION: We will schedule a Footer/deck inspection to be performed by the building department.



Footer Form & Pour: Size, shape, design and location further set the tone for the project. The crew will set the footer forms according to plan. The crew will set the deck forms according to plan. Depending on your deck type, acrylic, pavers or travertine this step may just include footers.



Paver/Travertine Set: The material you have chosen for your pool deck becomes a focal point; our crews are craftsmen and your Myrick Pool is rapidly becoming a true work of art.



Screen Enclosure/Fence: Your screen enclosure or fence is now ready to be installed. Our skilled craftsman will install your screen enclosure according to the site specific screen engineering and site plan.

Clean up/Pool Prep for Plaster: Our crew will remove all construction debris, prepare the shell for plaster.



INSPECTION: The building department requires a Pre-plaster Inspection. In the event you have alarms you will need to be home to allow the inspector to inspect the operation of the alarms, if you have a baby barrier fence the inspector will inspect the baby barrier fence and the pool. This is a safety inspection of the pool allowing us to move forward to plaster and put water in your pool

Pool Finish/Plaster:

Day 1: Your choice of interior material is the now applied to your new pool. This is typically chosen at contract.

Day 2: The next day the acid wash crew will come and acid wash and prep for water fill. They will begin to fill the pool immediately after acid wash. Your lights will be installed at this time by the acid wash crew. Please allow the water to fill until the water reaches the middle of the skimmer/tile line. **DO NOT** turn off the water for any reason until the water is to the middle of the waterline tile. Turning off the water can result in a ring around the new pool finish similar to a bath tub ring that can be almost impossible to remove.



Start up Pool Equipment: Once your Myrick Pool is full of water someone will come out and start up your pool equipment so the pool water can start to circulate. Your returns and spa fitting if any will be installed at this time. It may take a week for your pool to BLUE out and become completely chemically balanced. Our staff is just a phone call away if you have questions or need support.

Final Grade: The excavation experts will come back and grade out the construction area and remove any debris and complete a final clean up of the yard.

Landscaping: It is the customers responsibility to landscape their property after the pool has been installed. Most building departments REQUIRE landscaping to be complete for the Pool Final Inspection so this part needs to be completed before we can obtain a pool final.



Final Inspection: This is the last step in the completion of your pool with regards to permitting and inspections. A final inspection will be performed by the building department. Alarms and/or baby barrier fence must be operational and installed for the building official to perform this final task.

Pool School/Instruction: Myrick Pools will assign someone to come out and complete a POOL SCHOOL with you to familiarize yourself with the operations of your pool equipment regarding the maintenance and care of your new pool.



Walk Thru & Customer Handover (Dog not included) :



Myrick Pools personnel will meet with you to do a walk thru. You will be given a Customer Care Manual at this time that will have all the specifics about your pool as well as important information regarding the care of your pool

YOUR POOL IS NOW COMPLETE!

This is the time that you will be required to take over the care of your pool weather you do it yourself or have a pool service.

We hope that you enjoy your new pool and have many years of enjoyment!