



A Red Light Running (RLR) Photo Enforcement System was installed at the intersection of 127th Street/Obama Drive at Ashland Avenue on January 1, 2015 (eastbound), after finding limited success with other attempted measures to promote safer driving and improve compliance with traffic laws. As a condition of use, both Illinois law and the Illinois Department of Transportation require periodic statistical analyses/evaluations be conducted.

Specifically, the Illinois Compiled Statutes, 625 ILCS 5/11-208.6 Automated Traffic Law Enforcement System states:

(k-7) A municipality or county operating an automated traffic law enforcement system shall conduct a statistical analysis to assess the safety impact of each automated traffic law enforcement system at an intersection following installation of the system. The statistical analysis shall be based upon the best available crash traffic and other data and shall cover a period of time before and after installation of the system sufficient to provide a statistically valid comparison of safety impact. The statistical analysis shall be consistent with professional judgment and acceptable industry practice. The statistical analysis also shall be consistent with the data required for valid comparisons of before and after conditions and shall be conducted within a reasonable period following the installation of the automated traffic law enforcement system. The statistical analysis required by this subsection (k-7) shall be made available to the public and shall be published on the website of the municipality or county. If the statistical analysis for the 36-month period following installation of the system indicates that there has been an increase in the rate of accidents at the approach to the intersection monitored by the system, the municipality or county shall undertake additional studies to determine the cause and severity of the accidents, and may take any action that it determines is necessary or appropriate to reduce the number or severity of the accidents at that intersection.

The Illinois Department of Transportation Safety Engineering Policy Memorandum, Safety 2-13, Automated Traffic Law Enforcement Systems: Red Light Running (RLR) Camera Enforcement Systems and Automated Railroad Grade Crossing (RGC) Enforcement Systems states:

Follow Up Evaluation

An Evaluation Report shall be prepared by the Permit Applicant one year after the installation and shall be prepared every three years thereafter. The Evaluation Report shall include the following:

- *Intersection location(s);*
- *Date of implementation;*
- *RLR Camera System manufacturer and contractor name;*
- *Crash data specific to RLR location(s) for the three (3) year period prior to and for the period post RLR Camera installation;*
- *An analysis of the crash data, including a summary of any increase in crash types;*
- *Signal timing and other settings before and after RLR Camera installation;*
- *Traffic volumes before and after RLR Camera System installation; and,*
- *Summary of adjudication experience and results.*


The following statistical analysis/evaluation was performed through 2017.

Calendar year 2018 was not included, as the Illinois Department of Transportation (IDOT) has not yet completed collecting all data. The statistical analysis will be updated annually, as IDOT collected data becomes available for release.



Obama Dr./127th Street at Ashland Avenue
Calumet Park, IL

- RLR Photo Enforcement System monitors violations occurring on the eastbound approach of the intersection
- RLR Photo Enforcement System installed: January 1, 2015






127th Street/Obama Drive at Ashland Ave, Northbound Approach



127th Street/Obama Drive at Ashland Ave, Southbound Approach






127th Street/Obama Drive at Ashland Ave, Eastbound Approach



127th Street/Obama Drive at Ashland Ave, Westbound Approach






Average Daily Traffic

Data was obtained from the Illinois Department of Transportation's website www.gettingaroundillinois.com.

127th Street/Obama Drive at Ashland Avenue (Northbound)

- 15,600 (2010)
- 12,900 (2014)






Average Daily Traffic (continued)

Data was obtained from the Illinois Department of Transportation's website www.gettingaroundillinois.com.

127th Street/Obama Drive at Ashland Avenue (Southbound)

- 15,600 (2010)
- 7,300 (2014)






Average Daily Traffic (continued)

Data was obtained from the Illinois Department of Transportation's website www.gettingaroundillinois.com.

127th Street/Obama Drive at Ashland Avenue (Eastbound)

- 18,000 (2010)
- 18,600 (2014)






Average Daily Traffic (continued)

Data was obtained from the Illinois Department of Transportation's website www.gettingaroundillinois.com.

127th Street/Obama Drive at Ashland Avenue (Westbound)

- 18,000 (2010)
- 18,700 (2014)





Adjudication Experience

RLR camera violations are contested and adjudicated through an administrative hearing conducted each month. Adjudication data for the Village's Automated Enforcement Program is shown below in Table 3.

VILLAGE OF CALUMET PARK ADJUDICATION FOR AUTOMATED PHOTO ENFORCEMENT PROGRAM		
YEAR /TOTALS	LIABLE	NOT LIABLE
2015	635	89
2016	891	117
2017	589	109
2018	423	67
2019*	256	50
TOTAL:	2,794	432

**2019 totals through October 2019.*

Table 3

The high quality video footage and photographic evidence produced by the enforcement system is a contributing factor in a majority of the contested RLR violations being upheld by the Hearing Officer. The police officers assigned to review and approve/reject potential violations are vigilant in applying the same officer discretion and criteria they would if issuing an in-person citation, resulting in only highly prosecutable violations being mailed out.



Crash History and Analysis

- Table 1 includes crash data obtained from the Illinois Department of Transportation, detailing angle, turning, rear-end, and other type crashes occurring at the intersection pre/post RLR Photo Enforcement System installation.

ALL INTERSECTION APPROACHES

	Crashes								
	Rear-End (% of Total)		Angle (% of Total)		Turning (% of Total)		Other (% of Total)		Total
2012	3	27.3%	1	9.1%	5	45.4%	2	18.2%	11
2013	6	66.7%	3	33.3%	0	0.0%	0	0.0%	9
2014	4	36.3%	2	18.2%	4	36.3%	1	9.1%	11
Total:	13	41.9%	6	19.3%	9	29.0%	3	9.7%	31
2012-2014 Average:	4.3		2.0		3.0		1.0		10.3

RLR Camera Installation: January 1, 2015									
2015	3	27.3%	3	27.3%	3	27.3%	2	18.2%	11
2016	6	33.3%	1	5.5%	9	50.0%	2	11.1%	18
2017	5	31.2%	3	18.7%	5	31.2%	3	18.7%	16
Total:	14	31.1%	7	15.5%	17	37.8%	7	15.5%	45
2015-2017 Average:	4.7		2.3		5.7		2.3		15.0

- Other indicates the following: Pedestrian, Pedal Cyclist, Fixed Object, Sideswipe, Head-On and Unknown

Table 1

DISCLAIMER: The motor vehicle crash data referenced herein was provided by the Illinois Department of Transportation, based upon information derived from multiple sources. Any conclusions drawn from analysis of the aforementioned data are the sole responsibility of the data recipient(s). Additionally, for coding years 2015 to present, the Bureau of Data Collection uses the exact latitude/longitude supplied by the investigating law enforcement agency to locate crashes. Therefore, location data may vary in prior years, since the data prior to 2015 was physically located by bureau personnel. Given the subjective nature of the reporting process, the modifications in the incident locating protocols and the changes to the crash reporting thresholds effective 2009, the Village of Calumet Park acknowledges the potential for discrepancies in the final conclusions drawn.



Crash History and Analysis (continued)

- Table 2 includes crash data obtained from the Illinois Department of Transportation, detailing angle, turning, rear-end, and other-type crashes occurring at the intersection on the eastbound approach only, pre/post RLR Photo Enforcement System installation.

**EASTBOUND APPROACH ONLY
 (PHOTO ENFORCED APPROACH)**

	Crashes								
	Rear-End (% of Total)		Angle (% of Total)		Turning (% of Total)		Other (% of Total)		Total
2012	1	16.7%	0	0.0%	4	66.7%	1	16.7%	6
2013	0	0.0%	3	100.0%	0	0.0%	0	0.0%	3
2014	2	33.3%	2	33.3%	2	33.3%	0	0.0%	6
Total:	3	20.0%	5	33.3%	6	40.0%	1	6.7%	15
2012-2014 Average:	1.0		1.7		2.0		0.3		5.0

RLR Camera Installation: January 1, 2015									
2015	0	0.0%	2	50.0%	1	25.0%	1	25.0%	4
2016	2	33.3%	0	0.0%	4	66.7%	0	0.0%	6
2017	2	33.3%	2	33.3%	1	16.7%	1	16.7%	6
Total:	4	25.0%	4	25.0%	6	37.5%	2	12.5%	16
2015-2017 Average:	1.3		1.3		2.0		0.7		5.3

- Other indicates the following: Pedestrian, Pedal Cyclist, Fixed Object, Sideswipe, Head-On and Unknown

Table 2

DISCLAIMER: The motor vehicle crash data referenced herein was provided by the Illinois Department of Transportation, based upon information derived from multiple sources. Any conclusions drawn from analysis of the aforementioned data are the sole responsibility of the data recipient(s). Additionally, for coding years 2015 to present, the Bureau of Data Collection uses the exact latitude/longitude supplied by the investigating law enforcement agency to locate crashes. Therefore, location data may vary in prior years, since the data prior to 2015 was physically located by bureau personnel. Given the subjective nature of the reporting process, the modifications in the incident locating protocols and the changes to the crash reporting thresholds effective 2009, the Village of Calumet Park acknowledges the potential for discrepancies in the final conclusions drawn.



Comparison of annual averages shows the total number of crashes increasing by 45.6% at the intersection for all approaches and by 6.0% on the eastbound (photo enforced) approach post-camera installation. Although overall crashes increased on the photo enforced approach of the intersection, it is important to note that Angle type crashes decreased by 23.5%. Angle type crashes typically result in greater number of personal injuries and higher property damage.

The US Department of Transportation Project Development and Design Manual states that turning, angle or head-on crashes have a number of probable crash causes, to include:

- Large volumes of left /right turns
- Large total intersection volume
- Excessive speed on approaches
- Inadequate traffic control devices
- Poor visibility of signals

While red light cameras cannot truly decrease the volume of cars entering the intersection, speed and proximity of vehicles entering an intersection or the amount of turning traffic volume, red light cameras and red light camera photo enforcement warning signs have the ability to reduce traffic crashes and improve compliance with traffic control devices.

Analysis of all available data indicates the Village's RLR Photo Enforcement Program is only just beginning to make an impact of traffic safety at this intersection. Continued enforcement and analysis is necessary to determine the overall effectiveness of this program as an enforcement tool.