

C-Series Sidewall Stairs

42.667" Farm System

Document Guide

Wall Bracket Layouts......3

Position Guides......5

Starting Layouts......7


Top Platform.....9

Stair Sections......17


Attaching Stairs.....20

Handrail......23

Bottom Stair Section.....27



1st Edition August 2022



Overall Run Distance can be determined using this formula:

Bolt Spaces: 2 + 5x ring count = Total Bolt Spaces

Bin sheets = Total bolt spaces/12

3 Spc = 3 bolt spaces = 28.14"

4 Spc = 4 bolt spaces = 37.52"


5 Spc = 5 bolt spaces = 46.9"

42.667" Bin Sheet Bolt Spacing

Wall bracket placement is marked by "Bolt Spaces" throughout these instructions.

On a 42.667" bin sheet, a bolt space is equal to 9.375 inches.

Bolt spaces and their corresponding lengths in inches:




Platform A-Frame 42.667" Position Guide




	PARTS LIST				
ITEM	QTY	PART NUMBER	DESCRIPTION		
1	1	CS-34261	Bracket, Platform 42.67" ring		
2	1	CS-34402	Brace, Plate, Platform		
3	1	CS-32002	Channel, K-Brace, C-Series		

There are 3 position adjustments for brackets mounted in or below the seam, On Farm Duty, only a top platform is installed, using the Mid Position

The Farm Duty wall brackets are bolted to the sheet seam using the 5th bolt hole up from the bottom (10.67")






Stair A-Frame 42.667" Position Guide


PARTS LIST				
ITEM	QTY	PART NUMBER	DESCRIPTION	
1	1	CS-42661	Bracket, Wall, 42.67" ring	
2	1	CS-40002	Channel, Crossbar	
3	1	CS-32002	Channel, K-Brace, C-Series	

Farm Duty platforms use the default position for all stair wall brackets



Eave Layout, C-Series Farm 42.667"Wall Brackets & A-frames

Wall brackets should be attached to the bin wall with at least two bolts. Field drill as needed.




Eave Layout, C-Series Farm 42.667"

Top Platform and Stair Sections

It is recommended to begin installation with the top platform and attach the stairs as the bin is jacked during the construction stage.


The top platform is followed by a 4-step section which aligns the sections with the bin sheet seams.





CF3546L Parts List C-Series Farm 42.667" Top Platform

Overview of top platform assembly Refer to the parts reference on pages 15-16

PARTS LIST CF3546L				
ITEM	QTY	PART NUMBER	DESCRIPTION	
1	2	CS-34261	Bracket, Platform 42.67" ring	
2	2	CS-34402	Brace, Plate, Platform	
3	2	CS-32002	Channel, K-Brace, C-Series	
4	1	CS-F30001	Tread, Platform, Trapezoid 55x24	
5	2	CS-40005	Bracket, Brace, Angle, Acute	
6	2	CS-40006	Bracket, Brace, Angle, Obtuse	
7	2	CS-34414	Bracket, Faceplate	
8	1	CS-40410	Lower Stringer Extension	
9	1	CS-40411	Platform Stringer Extension	
10	2	CS-34500	Angle, Post, J-channel, Right	
11	2	CS-34501	Angle, Post, J-channel, Left	
12	1	CS-34408	Channel, Kickboard, End	
13	1	CS-34407	Channel, Kickboard, Inside, Long	
14	1	CS-34406	Channel, Kickboard, Outside Long	
15	1	CS-3009	Bracket, Support, Platfrom	
16	1	CS-30010	Bracket, Plate, Handrail	
17	2	TRS1502800	28" Long 1.5 in tube railing slotted end tabs	
18	2	TRS1504800	48" Long 1.5 in tube railing slotted end tabs	
19	2	TRS1505400	54" long 1.5 in tube railing slotted end tabs	








C-Series Commercial Platform Assembly Kickboards

PARTS LIST				
ITEM	QTY	PART NUMBER	DESCRIPTION	
10	1	CS-34406	Channel, Kickboard, Outside Long	
11	1	CS-34407	Channel, Kickboard, Inside, Long	
12	1	CS-34408	Channel, Kickboard, End	

Attach toekicks using the slots that align at posts.




C-Series Farm Platform AssemblyRailing

	PARTS LIST			
IT	EM	QTY	PART NUMBER	DESCRIPTION
	13	2	CS-30010	Bracket, Plate, Handrail
	14	2	TRS1505400	54" long 1.5 in tube railing slotted end tabs
	15	2	TRS1502800	28 Long 1.5 in tube railing slotted end tabs

Attach Handrail and Midrail smashed end tubing at ~21" and ~42" from platform deck.

Orient the pre-drilled weep holes down for drainage




C-Series Commercial Platform Assembly


Center the platform assembly on top of the A-frame wall mounts.

Use 4 bolts (5/16") to attach each A-frame to the platform.

Use the bolt holes in the platform that best align with the A-frame mounts, this will vary according to the bin diameter.




CF3546L Top Platform Parts ID



CS-34261




CS-34402




CS-34500 (Right), CS-34501 (Left)


23.90 CS-3009

CS-40411, CS-40410







CS-40006




CS-40005




CS-F30001






PARTS LIST CF4604				
ITEM	QTY	PART NUMBER	DESCRIPTION	
1	4	CS-41224	Tread Step 24x12	
2	1	CS-42674	Siderail, inside, 4-step 42.67" ring	
3	1	CS-42678	Siderail, outside, 3-step 42.67" ring	
4	1	CS-42676	Siderail, outside, 1-step 42.67" ring	
5	1	CS-F40001	Post, Stair, Inside	
6	1	CS-F40011	Post, Stair Rail, Outside	
7	1	CS-42661	Bracket, Wall, 42.67" ring	
8	1	CS-40002	Channel, Crossbar	
9	1	CS-32002	Channel, K-Brace, C-Series	
10	1	HRC1500	Handrail Clamp for 1.5 in	
11	1	TR1506706	67" x1.5 in Railing 6" swage	
10	1	TR1006706	67" x1 in dia Railing 6" swage	

Parts List, CF4604 C-Series Farm 42.667" 4 Step Stair Section





The 4-step stair section is used after the top platform

NOTE:

Additional CF4604 stair sections are only needed if there will be a rest landing that interrupts the stair run, which is optional for Farm Duty packages.


CF4600 C-Series Farm 42.667" 5 Step Stair Section

On the CF4600 stair section; the inside siderail is a one piece 5-step, the outside siderail is a two piece, 3-step and 2-step.

PARTS LIST			
ITEM	QTY	PART NUMBER	DESCRIPTION
1	5	CS-41224	Tread Step 24x12
2	1	CS-42675	Siderail, Inside, 5-step 42.67" ring
3	1	CS-42678	Siderail, outside, 3-step 42.67" ring
4	1	CS-42677	Siderail, outside, 2-step 42.67" ring


Bolt together but DO NOT TIGHTEN until correctly

"fanned" (see page 22).




Arrow on Inside Siderails Arrows Always Face UP

The depicted siderail placement corresponds to Clockwise stair runs (turning to the right as they go up the bin). For Counterclockwise stair runs, the siderail placement should be mirrored.






Arrow & Circle on Outside Siderails
Arrows Always Face UP



Attaching the Posts to the A-Frame

	PARTS LIST				
ITEM	QTY	PART NUMBER	DESCRIPTION		
5	1	CS-F40001	Post, Stair, Inside		
6	1	CS-F40011	Post, Stair, Outside		
7	1	CS-42661	Bracket, Wall, 42.67" ring		
8	1	CS-40002	Channel, Crossbar		
9	1	CS-32002	Channel, K-Brace, C-Series		




Attaching the Stair Section to the A-Frame Assembly

Attach the inside and outside posts to the siderails at the 2nd step from the bottom. $\,$




Also find Greene Galvinized Stairs on YouTube for visual aids in C-Series assembly techniques


Bolt in the holes shown in detail views.



NOTE:

The depicted stair section placement corresponds to Clockwise stair runs (turning to the right as they go up the bin). For Counterclockwise stair runs, the stair placement should be mirrored.





Installing Handrails

It is recommended to use a Tube Roller Former as shown in the picture; form inside rails to match bin sheet curvature, form outside rails with slightly less bend.

Alternatively, use an assembled stair section to brace one end of each tube and bend rails by hand


Bolt the 1.5" P-clamps at the top of the post and angle them to match the stair run.

Attach the midrails with 1/4" self-tapping screws at the pre-drilled hole location.



When all handrail has been connected, secure at each handrail clamp with a self-tapping screw through the bottom of the clamp into the tube.

For more information and instructional videos on handrail installation and using a tube roller, go to our website at **greenestairs.com** and look for the **YouTube** channel link.





Handrail Transition at Platform


Use the flat plate on the outside platform post to attach the stair handrail and midrail with P-clamps

There are holes provided but it may be necessary to field-drill additional mounting locations

Field cut handrail to length and insert pipe caps to protect pipe interior








A-Frame Bottom Section

The bottom stair section is mounted to a modified A-frame assembly, shown here.

	PARTS LIST				
ITEM	QTY	PART NUMBER	DESCRIPTION		
1	1	CS-42661	Bracket, Wall, 42.67" ring		
2	1	CS-40002	Channel, Crossbar		
3	1	AS-40004	Bracket, Tie Brace		
4	1	CS-F40011	Post, Stair Rail, Outside		
5	1	CS-F40001	Post, Stair, Inside		




Bottom Stair Section Assembly

The AS-40004 tie brace and ART-2226 bottom end rail are included in the top platform package.

Install the bottom end rail into the stair handrail. Attach the flattened end to the stair post as shown.


Drill a hole at the lowest point for drainage.




28


Hardware

Hardware List			
ITEM	DESCRIPTION		
3/8 x 1 Bin Bolt	3/8"-16 x 1" Bin Bolt (wall brackets to bin wall)		
PC-1500	1.5" friction Pipe Cap		
PC-1000	1" friction Pipe Cap		
3/8-16SFN	3/8"-16 Whiz Lock Nut		
3/8-16x1SFB	3/8"-16 x 1" Flange Bolt (default stair assembly bolt)		
5/16-18SFN	5/16"-18 Whiz Lock Nut		
5/16-18x3/4FB	5/16"-18 x 3/4" Flange Bolt (platform surface bolt)		
Self-tapping Screw	#12-14 x 3/4" Screw (to secure handrail at clamps)		
1/4-14x1STS	1/4"-14 x 1" Self Tap Screw (midrail connection at post)		
HRC1500	Handrail Clamp for 1.5 in		
HRC1000	Handrail Clamp for 1.0 in		






3/8"-16 x 1" Flange Bolt



5/16"-18 x 3/4 Flange Bolt



5/16"-18 Whiz Lock Nut







3/8"-16 Whiz Lock Nut




PC-1000 Pipe Cap




#12-14 x 3/4" Screw



3/8"-16 x 1" Bin Bolt



PC-1500 Pipe Cap



1/4"-14 x 1" Self Tap Screw