



ATX GRIP Hybrid 4 Dolly

**Austin Office:
9201 Brown Ln Suite 290
Austin, Tx 78754
Austin Office Phone:
512-537-4201
832-651-3053
Austin Office Email:
Rentals@atxgrip.com**

SPECIFICATIONS

Carrying weight 395 lbs 179 kg

Standard operational weight (without payload) 463 lbs 210 kg

***Maximum payload 700 lbs 318 kg**

****Maximum payload with center mount kit 1900 lbs 862 kg**

Maximum camera mount height (with standard 12" riser) 6 ft 2 in 186 cm

Maximum camera mount height (without risers) 5 ft 2 in 157 cm

Minimum camera mount height 19 in 48 cm

Min. Cam. mount height w/hybrid low camera 90° plate 1 in 3 cm

Vertical boom travel 3 ft 7 in 109 cm

Maximum boom lifts (fully charged at 3,300 psi) 5 Lifts

**Chassis maximum length (wheels fully extended) 4 ft 6 in
137 cm**

**Chassis minimum length (Wheels Fully retracted) 3 ft 11 1/2
in 120 cm**

Minimum chassis height for transportation 20 1/2 in 52 cm

**Chassis variable widths – legs at 0° track position 27 in 69
cm**

**Chassis variable widths – legs at 12° track position 29 1/2
in 75 cm**

**Chassis variable widths – legs at 45° track position 3 1/2 in
90 cm**

**Chassis variable widths – front legs in 78.5°-880 track
position 38 1/2 in 98 cm**

**Chassis variable widths – legs at 90° track position 39 in 99
cm**

Steering post height 3 ft 91 cm

Accumulator charging time (110 AC and DC) 60 sec

Minimum door width hybrid can be carried through 18 in 46 cm

Dolly Crate Shipping Weight 661 lbs 299,8 kg

Dolly Crate Shipping Dimensions L 56 in x W 32 in x H 33 in

Dolly Accessory Crate Weight 909 lbs 412,3 kg

Dolly Accessory Crate Dimensions L 67 in x W 33 in x H 58 in

***Payload includes All Items (i.e. Man, Camera, Platform, Turret, Crane Arm, etc.) on Arm **Payload includes All Items (i.e. Camera, Platform, Turret, Crane Arm, etc.) on Base Mount..**

