



# ADLM Counties Environmental Public Health

## ***Septic System Inspections Chapter 69.3(1)***

- **Contact local Environmental Health Officer, minimum 24 hour notice for site evaluation.**

<p><b>Appanoose and Davis Counties</b>            Stacie Prevo, EHO            Office: 641-724-3511            Cell: 641-777-7511</p>	<p><b>Lucas, Monroe, and Appanoose Counties</b>            Cameron Willis, EHO            Office: 641-724-3511            Cell: 641-799-0331</p>
---	--
  
- **Pre-Site Inspection:** Prior to breaking ground.
- **Mid Inspections:** Per Discretion of the EHO Inspector and noted at time of pre-site.
- **Inspections:**
  - Primary System**

Septic Tanks    Schedule 40 PVC shall extend at least 2' beyond undisturbed ground  
 Minimum of 3' of undisturbed ground between tank and secondary  
 Prior to cover; or per discretion of Inspector noted at time of pre-site  
 Minimum liquid Depth 40" and Maximum liquid Depth 6 ½' from lid  
 Clean out required every 100' prior to tank  
 Evidence of pipe cleaner (prefer colored) on all PVC joints  
 Risers at grade
  - Secondary System**

*Sand Filters:*  
 EZ Flow: Probe of 34" of Sand prior to cover  
 (top of sand to bottom of excavation), may be after installation of EZ flow.  
 Bottom common vent with siphon/dose; top and bottom vents for gravity  
 (2) 10" bottom pipes prior to cover; corrugated poly tubing with socks  
 Evidence of pipe cleaner (prefer colored)  
 3' or greater from Septic Tank  
 4" schedule 40 PVC pipe  
 Varmint Guard  
 Filter Fabric

***Bio Filters/Recirculating Textile Filters:***  
 Prior to cover; or per discretion of Inspector noted at time of pre-site.  
 Inspect inside of peat moss and textile filters  
 Connections to septic tank  
 Vent lid free from cover
  - Final Approval of Onsite Wastewater Disposal System:***  
 Receipt of signed maintenance agreement if applicable  
 Documented tank location via GPS coordinates.  
 Document overall system with digital camera  
 Completion of Chapter 69.3(1) B Checklist  
 EHO Signature on Original permit  
 Finalize drawing of the system