



# CALENDAR

## Estimated 7-9 Weeks

Within the first 2 weeks we are done with the base construction of the project. Week 3 through 9 goes by slow and can be frustrating in the Summer months. Construction slows after the concrete pool shell is installed. The project is depended upon inspection schedules, material availability, equipment availability and third-party specialized installers. We will do our best to keep progress and inform you of delays. Delays during the peak months are common. Example: Concrete deking installation depends upon the compaction inspection, concrete delivery, concrete pump, weather, and the concrete crew used to finish. If one of the items is delayed then it impacts

### Before Excavation

- Turn off sprinklers to backyard
- Remove plants and trees in the way
- Clear an 8' path from the front to the back
- Driving heavy equipment over concrete can possibly crack it. (We will not budget for replacing concrete that cracks)
- Prepare the fence to be removed
- The path from the pool to the dump truck will be a path of destruction, please be aware.
- Stingray Pools will not budget for sprinklers, broken concrete, ect.....

### Phase 1 Excavation 3 DAYS

- We will arrive by 8am to gain access to your yard
- We will scrape and layout the pool shape
- Removal of trees, plants, grass and other items can increase the excavation cost
- Tree stump removal will be \$50 per stump that is less than 12" in diameter
- Sprinkler lines and drainage lines will be damaged. We will not budget for these repairs. These should be repaired by a landscaper and planned accordingly.
- Excavation will be 1-3 days
- The path from the pool to the dump truck will be very messy. It will be a path of destruction so please plan accordingly.

### Phase 2 Plumbing and Electrical: 3 DAYS

- We will trench all plumbing lines
- We will trench all electrical lines
- We will trench all gas lines
- We will cut and remove concrete if needed to gain access to the electrical box and gas meter.
- We will pressurize all plumbing lines with water pressure

Week 1

Week 1-2



### Phase 3 Rebar: 2 DAYS

- Week 2**
- We will have rebar delivered prior to your residence
  - We will install the rebar grid to code in 12" squares
  - Rebar will be double reinforced in the deep end and along the house if closer than 4'
  - We will install the first and third step during the gunite phase

**INSPECTION 1: Inspection will cover rough plumbing, electrical, gas lines and rebar**

### Phase 4 Gunite: 1 DAY INSTALL WITH A CURE TIME OF 7-10 DAYS

- Week 2-3**
- We will shoot the gunite (high pressure concrete that is sprayed)
  - It will be loud
  - It will take 4-7 hours
  - It will take up a lot of room in front of your residence for the trucks
  - Please make room for the trucks
  - Water the gunite down 1-2 times a day for 7-10 days, starting the day AFTER it is installed

### Phase 5 Tile: 1-3 DAY INSTALL WITH A CURE TIME OF 3-5 DAYS

- Week 4-5**
- Tile will be installed
  - Sheer waterfalls will be installed if applicable
  - Stone will be installed AFTER concrete if you have stone areas
  - Waterfalls will delay the job and add on 7-10 days. Crane access will be needed.

### Phase 6 Decking: 1-2 DAY FORM, THEN INSPECTION, 1-2 DAY POUR (5-8 DAYS) EXPECT DELAYS

- Week 5**
- We will form and compact the dirt for concrete
  - Trenches will be filled in
  - We will install a copper wire around the pool for bonding
  - We will pour concrete AFTER the pre-deck inspection

**INSPECTION 2: Inspection will cover compaction of dirt so we can pour concrete EXPECT DELAY**

### Phase 7 CONCRETE 3-5 DAYS TO CURE

- Week 5-6**
- We will pour concrete after the inspection
  - Expect a brief delay
  - Concrete will need to cure for 3-5 days
  - After concrete Stone will be Installed 1-2 days and could be delayed



## Phase 8 Finalize: Clean up and and prepare to plaster or pebble interior finish 1 WEEK

Week 6

- Install door alarms
- Fence will be secured (we do not budget for pool fencing or installing a new fence)
- We are not responsible for neighbor's fence conditions or middle board on neighbor's side for County Codes.
- Clean up job site for debris
- Rake dirt. Landscaping should be budgeted for to get the yard to pre-construction condition

**FINAL INSPECTION: SOMEONE WILL NEED TO BE HOME**

Week 7

## Phase 9 Interior pool finish 1-2 DAYS AND 2-3 DAYS TO FILL

- We will install the pebble or plaster
- Plaster will take only 1 day
- Pebble will take 1 day of install and another day to acid wash
- A water hose from the house will be used to fill the pool
- We will not incur any water charges to fill the pool if a water truck is needed.

## Phase 10: Equipment start up

Week 7

- When the water is half way up the tile, please call us.
- We will send out a third party pool professional to balance out the chemicals
- They will also program the equipment and walk you through the pool general maintenance
- We will help you through the first 30 days as new pool owner.

# 7-9 Week Process

Peak months, weather, material, special equipment, special additions and upgrades can impact the time.