

SECTION 00 91 14

ADDENDUM NUMBER 5

PARTICULARS

- 1.01 DATE: MAY 30, 2018**
- 1.02 PROJECT: AUSTIN HIGH SCHOOL CAREER TECH CENTER**
- 1.03 PROJECT NUMBER: B. C. NO. 2018112**
- 1.04 OWNER: DECATUR CITY SCHOOLS**
- 1.05 ARCHITECT: NOLA | VAN PEURSEM ARCHITECTS, PC**

TO PROSPECTIVE BIDDERS

- 2.01 THIS ADDENDUM FORMS A PART OF THE CONTRACT DOCUMENTS AND MODIFIES THE BIDDING DOCUMENTS DATED APRIL 25, 2018, WITH AMENDMENTS AND ADDITIONS NOTED BELOW.**
- 2.02 ACKNOWLEDGE RECEIPT OF THIS ADDENDUM IN THE SPACE PROVIDED IN THE PROPOSAL FORM. FAILURE TO DO SO MAY DISQUALIFY THE BIDDER.**
- 2.03 THIS ADDENDUM CONSISTS OF 2 PAGES.**

CHANGES TO THE PROJECT MANUAL (NOT USED)

CHANGES TO THE DRAWINGS

4.01 SHEET E-0.2 - ELECTRICAL DETAILS:

- A. Detail: Auxiliary outlet-Cabling, connectors and patch panel ports for Data outlet (wireless access point) shall be CAT6A compliant. CAT6A cabling shall be Berktek LANmark-10G2 Plenum UTP. CAT6A connector shall be Leviton# 6110G-R*6.

4.02 SHEET E-3.0 - FLOOR PLAN POWER & AUXILIARY:

- A. Auxiliary cabinet BB-N located in Office SPA 105: Change cabinet from Great Lakes model# DWR-18-26PD to Middle Atlantic# SR-40-32

4.03 SHEET E-4.0 - FLOOR PLAN - HVAC EQUIPMENT CONNECTIONS:

- A. Delete all electrical for HRU-1 and HRU-2 complete.
- B. HRU-1 – Furnish and install 2 each 30/3/3R safety switches. Furnish and install 3#10, 1#10G,3/4”C from safety switch(s) to panel new panel MP. Furnish and install 1 each 30/3 breaker and 1 each 25/3 breaker in panel MP and connect new unit feeders as required. Field verify exact breaker for the correct side of unit.

- C. HRU-2 – Furnish and install 2 each 30/3/3R safety switches. Furnish and install 3#10, 1#10G,3/4”C from safety switch(s) to panel new panel MP. Furnish and install 1 each 25/3 breaker and 1 each 20/3 breaker in panel MP and connect new unit feeders as required. Field verify exact breaker for the correct side of unit.

END OF ADDENDUM NUMBER 5