# Town Council Meeting Town of Carefree 3/3/2015



**UPDATE:** The Cave Creek Bike Lanes Project - - Design and Construction Grants

#### Background

- Federal CMAQ Program:
  - \$ 8.2 million in federal funds for Bike/Pedestrian projects available FFY2015 - FFY2017
- Cost Share: Federal 94.7%; Local Agencies 5.7%
- Grant awarded to Cave Creek as applicant with Carefree as partnering agency
- 2 Grants: Design Grant and Construction Grant
- Carefree to utilize HURF Funds

#### Grants

#### **Design Grant:**

\$ 339,343

Federal Grant Funds (94.3%): \$320,000 Local Match (5.7%): \$19,343

Local Match is 50% / 50%

Town of Carefree share (50%): \$9,671.50 Town of Cave Creek share (50%): \$9,671.50



#### Construction Grant:

Approximately \$ 3,754,109

Local Match is 5.7% of Scope of Work per Town

Federal Grant Funds @ 94.3%:

City's match @ 5.7%

(Carefree's Share)

City's funds @100%

**Total Project Construction** 

Carefree Total Construction:

Carefree Portion of Total Construction Cost =

(Cave Creek Portion of Total Construction Cost =

\$ 3,538,480

\$ 213,885

(\$ 138,415)

\$ 1,744

\$ 3,754,109

\$ 2,428,316

64.7%

35.3%)


# The Project




### Project Scope

- Widening existing pavement to provide continuous bike lanes in both directions throughout the project limits. The new pavement will match existing structural section.
- Slurry seal the existing roadways within the project limits (full width)
- Re-stripe the existing roadway
- Pavement marking for bicycle lanes
- Re-set existing survey monuments, manholes and valves as needed

# **Existing Conditions**











# Proposed Conditions (Typical)



- Restriping Only
  - Edge of pavement does not change
  - Roadway slurried and striped
  - Existing conditions remain

## Proposed Conditions (Typical)



- MedianReduction
  - Edge of pavement does not change
  - Medians reduced; planting salvaged or removed
  - Roadway slurried and striped


## Proposed Conditions (Typical)



- Pavement Addition
  - Extend edge of pavement to accommodate
     5' of bike lane
  - Regrading at 3:1 slope
  - Roadway slurried and striped

### Project Status

- Completion of 60% Construction Documents with Cost Estimates
- Awaiting 95% Submittal including Cost Estimates with revised budget
- Intergovernmental Agreement with Cave Creek
- Notice of Intent to Clear Land (AZ Dept of Agriculture)



#### Next Steps

- Construction
  - 100% Construction Documents ready to Bid
  - Revise IGA as needed
  - Bid and Award Contract
  - Construction Administration and Oversight
  - Project Acceptance

# Questions?