



# PROJECT PROFILE

## Barrick Elementary School

Houston, Texas



Before



After

The subject roof encompassed approximately 38,500 square feet. The scope of work included the removal of the existing material down to the deck; application of a modified bitumen secondary roof membrane on top of the deck; installation of tapered lightweight insulating concrete fill with encapsulated EPS board; and installation of a mechanically-attached base sheet and a two-ply modified bitumen membrane with a granule-surfaced cap sheet. The scope of work also included the covering over abandoned unit skylights; installation of new pre-finished sheet metal expansion joint covers, gutters, and downspouts; installation of new metal wall panels over rise walls; and new pre-manufactured supports for roof-top piping.

*Client/Owner:*

*Houston ISD  
Houston, Texas*

*Approximate Construction Cost:*

*\$393,500.00*

*Year Completed:*

*August 2008*



Before



After