



ARCHITECTURAL PRECAST REPAIR SCOPE OF WORK (STANDARD)

Included repairs:

- All repairs are anticipated to be for exposed finish precast.
- Cleaning of shipping, production and erection dirt.
- Patching chips and spalls. Equivalent 2 chips per panel (Less than 4").
- Repairing large breaks greater than 4" including epoxy bonding. 1 per 40 panels set.
- Patch exposed stripping and lifting devices. Typically amount and usually in window openings and top of roof parapet.

Repairs at additional cost:

- Crack repair:
 - Rub or patch cracks only.
 - Epoxy injection.
- Cutting panels for erection crew.
- Cut tight joints.
- Cutting in or aligning reveals.
- Toning discolored panels.
- Rubbing bug holes.

Included equipment:

- All hand tools
- Grinders (Diamond blades are reimbursable).
- Demo saws (Diamond blades are reimbursable).
- Bonding agents (excludes epoxies)
- Pressure washers
- Compressors
- Sandblast/Soda Blast pots
- Blasting media.
- Manlifts/swings

Items provided by Precaster:

- Cements and pigments
- Injection and bonding epoxies (PRS can provide at additional cost)
- Bricks including field and corner bricks