

**Town of Baldwin, Maine**  
**CULVERT INSTALLATION BID DETAILS**  
**NEW ROAD, WEST BALDWIN, ME**

- New Road Culverts:
  - replace two – 60" x 40' corrugated culverts
- Culvert replacement must be completed by Thursday, September 30<sup>th</sup>, 2021.
- Contractor to remove existing culverts. Town of Baldwin Public Works will haul off the old culverts. Contractor needs to crush culverts for transportation.
- All culverts and bands are supplied by the Town of Baldwin. Other materials to be supplied by the contractor.
- Contractor must contact dig safe.
- Culverts to be placed 3' – 5' apart for compaction.
- 6" to 12" rip-rap is required to be installed on either ends of the culverts and slopes. Fabric needs to be placed under rip-rap. Surface with crushed gravel.
- Compaction = 6" – 8" lifts on all sides of culverts for backfill.
- THE BALDWIN MUNICIPAL OFFICERS RESERVE THE RIGHT TO ACCEPT OR REJECT ANY AND ALL OFFERS SUBMITTED WHICH ARE NOT IN THE TOWN'S BEST INTEREST AS DETERMINED BY THE MUNICIPAL OFFICERS
- The Contractor shall have and maintain liability insurance that is in force until the work is completed and accepted by the Municipality. The Contractor shall furnish to the Municipality, a certificate of insurance, within two weeks of notice to the Contractor of the acceptance of its offer. The failure to provide this certificate will constitute a breach of the Contract and may at the discretion of the Municipality; result in termination of the Contract.