



PCI PERSONNEL

LUKE MALNAR ASSOCIATE PROJECT MANAGER

EDUCATION: Design and Development Construction Management
Sam Houston State University
Huntsville, Texas 77341

COMPANY: Price Consulting, Inc.
7122 Worcester Drive, Suite A
Spring, Texas 77379
Email: lmalnar@priceconsulting.com
www.priceconsulting.com

**PROFESSIONAL
REGISTRATION:** Certified IntegriScan Electric Leak Detection Equipment
Technician.
Level 1 Certified Thermographer

REPRESENTATIVE PROJECTS

Klein ISD Hildebrandt, Klein, Texas: Performed quality assurance inspection services during roof replacement involving fully adhered TPO single-ply, cover board and polyisocyanurate insulation on lightweight insulating concrete deck on 80,000 square foot existing school facility.

Lone Star College-Houston North Victory, Houston, Texas: Performed water spray testing of newly installed storefront windows in accordance with AAMA 501.2 standards.

Lone Star College-Houston North Victory, Houston, Texas: Performed field chamber water penetration tests on newly installed curtain wall and storefront windows in accordance with ASTM E1105 standards.

Fidelis Realty, Bellaire, Texas: Conducted condition assessments of existing roofs (single-ply, modified bitumen, and built-up roofing) on multiple facilities in multiple locations totaling more than 400 roof areas and over 5,000,000 square feet.

Macys, Houston, Texas: Performed infrared moisture survey on an existing 40,000 square foot retail and warehouse building.

HMH Medical Center, Scurlock Tower and Smith Tower, Houston, Texas: Performed load testing of existing rooftop tie-back anchors and davit assemblies on an existing medical building.

Magnolia ISD, Williams Elementary School, Magnolia, Texas: Performed quality assurance inspection services of single-ply retrofit over existing standing seam metal roof installation on a 60,000 square foot existing elementary school building.

Collin College, Plano, Texas: Performed quality assurance inspection services on roof replacement with PVC/KEE fully adhered single-ply membrane, cover board, and polyisocyanurate insulation on steel deck on 250,000 square foot existing educational office space.



PCI PERSONNEL

END OF RESUME